## Arizona City Elementary School - Millings Project Loma Vista



## J Banicki Construction

4720 E. Cotton Gin Loop, Suite 240

Phoenix, AZ 85040

Contact: Don Davis
Phone: 480-320-4358

Email: ddavis@banicki.com

Quote To: Toltec School District Job Name: AZ City Elementary School - Milling Pro

Attention:Jeff Van HandelOwner:Toltec School DistrictAddress:3315 N. Toltec RoadAddress:12115 Benito DriveCity State Zip:Toltec, AZ 85131City State Zip:Arizona City, AZ 85123

<u>Email:</u> jvanhandel@toltecsd.org <u>Phone:</u> 520-466-2363 <u>Phone:</u> 520-466-2363 <u>Date:</u> 10-6-17

Fax: N/A

ITEM	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	AMOUNT
10	Mobilization	1.00	LS	5,130.00	5,130.00
20	De-mobilization	1.00	LS	5,130.00	5,130.00
30	Mill exist PVMT - Include Placing Millings	1,612.00	SY	10.77	17,361.24
40	Remove Curb and Gutter - MAG Std Spec 350	4,781.00	LF	1.51	7,219.31
50	Remove sidewalk MAG Std Spec 350	100.00	SF	10.42	1,042.00
60	Miscellaneous demolition, not otherwise identified	1.00	LS	3,395.00	3,395.00
70	Traffic Control MAG Std Spec 401	1.00	LS	6,390.00	6,390.00
80	Install Curb Transitions	2.00	EA	540.00	1,080.00
90	Install MAG VC&G	76.00	LF	42.65	3,241.40

GRAND TOTAL \$49,988.95

## NOTES:

This proposal is to be included as part of the subcontract agreement entered into with J Banicki Construction, Inc. We propose to furnish labor, equipment, and materials complete in accordance with the plans and specifications supplied to us for the above mentioned project. All material is guaranteed to be as specified. All work will be completed in a workmanlike manner according to standard industry practices. Any alterations or deviations from the above specifications involving extra costs will be executed only upon written orders and will become an extra charge over and above the proposed estimate.

The following EXCLUSIONS apply to this proposal:

Earthwork operations for future athletic fields

Asphalt paving and aggregate base placement

Project information signs

Notification and coordination with property owners adjacent to project site

Yard site and laydown areas

Materials testing and quality control

Brooming of existing streets

Site Security

Site office or utilities

Removal or relocating or replacement of existing utilities or improvements

Utility lid adjustments for manholes or valve boxes Modifications to existing fencing at Arizona City Elementary School New roadway signs, Dead End signs, or end of street Type III barricades on Loma Vista

The following CLARIFICATIONS apply to this proposal:

All features of work that are included in this proposal are that which is shown on the 1 page of plans received for this project by J Banicki Construction from Toltec School District on 7-27-17 depicting the Arizona City Toltec Elementary School Campus Expansion (Street R/W Abandonment).

J Banicki Construction will use all millings generated from the full depth asphalt milling operation on Loma Vista Dr. to build the proposed temporary millings road that will connect Kino Dr. to Tubac Dr. No millings will be hauled off site for this project.

It is understood by J Banicki Construction that all materials testing / quality control will be provided by a third party quantity control testing firm retained by Toltec School District for this project.

It is understood by J Banicki Construction that the existing alignment of Kino Drive can be used to park equipment after completion of shift and that no separate yard is required for heavy equipment.

J Banicki Construction will provide continued access to the house on Loma Vista Dr. on the south side of this existing road during the performance of the contract.

This proposal does not include any modifications to existing utility lines or utility lids in the areas to the south of Loma Vista Dr. that may be present in the existing streets south of Loma Vista Dr. which area in disrepair and need of rehabilitation.

One mobilization is included for the entire scope of work for JBCI.

Prices based on Banicki's standard insurance coverage's. Wrap insurance and/or fees are excluded. If required, it is to be provided by others and J Banicki Construction must be named as additional insured.

The costs of Payment and Performance bonds are included in Banicki's pricing.

This proposal may be withdrawn by J Banicki Construction, Inc. if not accepted within 30 days.

It is the intention of J Banicki Construction, Inc. that this proposal and subsequent negotiations lead to execution of a contract to the mutual benefit of both parties.

Final payment is to be based on actual quantities of work performed.

Respectfully submitted, Don Davis APDM Manager J Banicki Construction

Date: 10-6-17