

# GLENDAL ELEMNTARY SCHOO DISTRICT SFB PROJECT RECAP

Prepared by:

**SPS+ Architects, LLP**  
8681 E. Via De Negocio  
Scottsdale, Arizona 85258

08.25.16 Issue Date  
09.02.16 Reissued with updates



# Glendale Elementary School District SFB Projects: Construction Cost Estimates

BRG: Project: Scope: Updated 9/1/16 Cost Estimate:

070440101-9999-003-BRG	Landmark Reseal		
	<b>Phase 1</b>	Sister wall: this is inclusive of footings, spoil removal, backfill, drilling, doweling, install and everything in the details and put back like we were never there.	\$ 907,038.00
		Adjustments required for sister wall installation; extend electrical, downspouts, relocate irrigation boxes and other conflicts	\$ 227,541.00
		<b>Estimated Phase 1 Subtotal</b>	<b>\$ 1,134,579.00</b>
	<b>Phase 2</b>	Installation of masonry control joints/repair CMU	\$ 40,000.00
		Weatherproof at new materials: Blockfill of new masonry and coating of Drylok extreme at exposed footing	\$ 11,000.00
		Drainage corrections to remove turf and irrigation against building and replace with decomposed granite from face of wall to 5'-0" away from building	\$ 46,765.00
		<b>Estimated Phase 2 Subtotal</b>	<b>\$ 97,765.00</b>
		<b>Estimated Total Repair:</b>	<b>\$ 1,232,344.00</b>

070440101-1001-009-BRG	Landmark Structural		
	<b>Phase 2</b>	Gervasio report regarding media center cracks	\$ 150,000.00
		Gervasio report regarding gym cracks	\$ 20,000.00
		Gervasio report regarding column cracks	\$ 25,000.00
		<b>Estimated Phase 2 Subtotal</b>	<b>\$ 195,000.00</b>
		<b>Estimated Total Repair:</b>	<b>\$ 195,000.00</b>

070440111-9999-004-BRG	Challenger Reseal		
	<b>Phase 1</b>	Sister wall: this is inclusive of footings, spoil removal, backfill, drilling, doweling, install and everything in the details and put back like we were never there.	\$ 870,756.00
		Adjustments required for sister wall installation; extend electrical, downspouts, relocate irrigation boxes and other conflicts	\$ 225,296.00
		<b>Estimated Phase 1 Subtotal</b>	<b>\$ 1,096,052.00</b>
	<b>Phase 2</b>	Installation of masonry control joints/repair CMU	\$ 60,000.00
		Beam bearing cracks	\$ 30,000.00
		Riddle blockfill of new masonry and coating of Drylok extreme at exposed footing	\$ 11,000.00
		<b>Estimated Phase 2 Subtotal</b>	<b>\$ 101,000.00</b>
		<b>Estimated Total Repair:</b>	<b>\$ 1,197,052.00</b>

070440111-1003-002-BRG	Challenger Structural		
	<b>Phase 2</b>	Gervasio crack repair	\$ 20,000.00
		<b>Estimated Phase 2 Subtotal</b>	<b>\$ 20,000.00</b>
		<b>Estimated Total Repair:</b>	<b>\$ 20,000.00</b>



# Glendale Elementary School District SFB Projects: Construction Cost Estimates

BRG:

Project:

Scope: Updated 9/1/16

Cost Estimate:

070440111-9999-005-BRG Challenger Drainage			
	Phase2	Chasse Estimate	\$ 273,966.25
		<b>Estimated Phase 2 Subtotal</b>	<b>\$ 273,966.25</b>
		<b>Estimated Total Repair:</b>	<b>\$ 273,966.25</b>

070440106-9999-011-BRG Mensendick Drainage			
	Phase2	Chasse Estimate	\$ 250,133.25
		<b>Estimated Phase 2 Subtotal</b>	<b>\$ 250,133.25</b>
		<b>Estimated Total Repair:</b>	<b>\$ 250,133.25</b>

070440106-9999-010-BRG Mensendick Structural			
	Phase 1	Temporary bracing of non-structural CMU walls - 55 panels	\$ 192,500.00
		<b>Estimated Phase 1 Subtotal</b>	<b>\$ 192,500.00</b>
	Phase 2	Installation of masonry control joints/repair CMU	\$ 80,000.00
		Securing of decorative wythe of CMU	\$ 60,000.00
		Repair of CMU surround the stair stepped cracks	\$ 100,000.00
		Install helical piers	\$ 400,000.00
		Grout injection of slab	\$ 100,000.00
		Repair of the cracked CMU and rusted reinforcing	\$ 250,000.00
		Riddle blockfill of new masonry, reseal with 10 year weatherization warranty and coating of Drylok extreme at exposed footing	\$ 200,000.00
		Remove turf and irrigation against building and replace with decomposed granite from face of wall to 5'-0" away from building	\$ 52,000.00
		<b>Estimated Phase 2 Subtotal</b>	<b>\$ 1,242,000.00</b>
		<b>Estimated Total Repair:</b>	<b>\$ 1,434,500.00</b>

070440103-9999-013-BRG Smith Structural and Drainage			
	Phase 2	Installation of masonry control joints/repair CMU	\$ 100,000.00
		Install helical piers	\$ 500,000.00
		Grout injection of slab	\$ 100,000.00
		Riddle blockfill of new masonry and coating of Drylok extreme at exposed footing	\$ 8,000.00
		Remove turf and irrigation against building and replace with decomposed granite from face of wall to 5'-0" away from building	\$ 40,000.00
		Chasse Drainage estimate	\$ 57,738.75
		<b>Estimated Phase 2 Subtotal</b>	<b>\$ 805,738.75</b>
		<b>Estimated Total Repair:</b>	<b>\$ 805,738.75</b>

<b>Phase 1 Total:</b>	<b>\$ 2,423,131.00</b>
<b>Phase 2 Total:</b>	<b>\$ 2,965,603.25</b>
<b>Total Estimated Construction Cost:</b>	<b>\$ 5,388,734.25</b>

September 2, 2016



**RE: GESD SFB Deficiency Corrections**  
Landmark, Challenger, Mensendick and Smith

Robert L Pian, AIA

William R Pittenger, RA, CSI

Mark A Davenport, AIA, LEED AP

Herb W Schneider, FAIA

Howell Lewis Shay, AIA

Please see below for a summary of work at each site:

**Landmark (070440101-1001-009, 070440101-999-003): Constructed in 1987**

- Structural: Our engineer agrees with the Gervasio reports for structural repairs at the gym, media and admin areas. This includes weatherization painting at areas of repair.
- Weatherization/Structural: please see below.
- Drainage corrections: This includes removal of turf and irrigation against buildings and replacement with decomposed granite from face of wall to 5'-0" away from building.

**Challenger (070440111-1003-002, 070440111-999-004, 070440111-999-005): Constructed in 1987**

- Structural: Our engineer agrees with the Gervasio reports for structural repairs. This includes weatherization painting at areas of repair.
- Weatherization/Structural: please see below.
- Civil: Construction documents are complete to make repairs at areas that get flooded.

**Mensendick (070440106-9999-010, 070440106-9999-011): Constructed in 1966/1958**

- Structural: Recommends to make repairs to cmu and interior slabs for functionality, weatherization and safety reasons. Weatherization/Structural: please see below. This includes weatherization painting at areas of repair.
- Civil: Construction documents are complete to make repairs at areas that get flooded.
- Drainage corrections: This includes removal of turf and irrigation against buildings and replacement with decomposed granite from face of wall to 5'-0" away from building.

**Smith (070440103-999-013): Constructed in 1952**

- Structural: Recommend making repairs to the masonry and interior slabs to increase functionality and weatherization. The estimate includes weatherization painting at areas of repair. Civil: Construction documents are complete to make repairs at areas that get flooded.
- Drainage corrections: This includes removal of turf and irrigation against buildings and replacement with decomposed granite from face of wall to 5'-0" away from building.

**Weatherization project conditions:** The structural assessments discovered a substantial amount of damage discovered in the horizontal (and in some cases the vertical) reinforcing steel at all campuses with the exception of Smith (which was unreinforced due to its age). This condition causes the engineer to be concerned about the integrity of the perimeter walls. As a result of moisture conditions, amount of cracking, and the test holes at reinforcing it is estimated that 33-75% of reinforcing along the length of the wall at grade is rusted, not the reinforcing in the entire wall. The result of cracks along grade, water infiltration and swelling of rusted reinforcing is that the CMU face shells are basically delaminating so that what originally calculated as an 8" wall is now functioning as a 4-6" wall, which obviously is not meeting the original code and is even further from compliance with current code. **Therefore, I concur with the engineer and recommend to move forward with these repairs as soon as possible and brace immediately.** Likely nothing happens, but from a calculations standpoint the engineer is unable to provide the appropriate safety assurances since we don't know the extent of the delamination and based

on our investigation we know the conditions won't hold for much load at all. In addition to civil projects that may be happening at these sites, we recommend removing grass and irrigation within 5 feet of the buildings.

On 8/25 we met with SFB, District, and engineering team to review the status of the projects as a result of the findings of the Structural Assessments. At that time it was recommended that calculations be completed and a shoring plan be reviewed and implemented immediately. Bixler was tasked with completing structural calculations and a sketch of a temporary shoring detail that would provide adequate reinforcing.

As requested we provided design fee proposals for each project. To ensure that Bixler's shoring solution was site adapted and the impacts to accessibility/safety were evaluated we scheduled a site visit. On 8/31 we walked the site with the District's pre-procured contractor Chasse, a masonry subcontractor, structural engineer and District representatives to review and discuss the best way to site adapt the Pre-Site Walk Shoring detail and still provide the least costly shoring alternatives based upon existing site conditions and the necessity to remain accessible and functional. **Shoring Alternative No. 1:** In this solution the calculations required a continuous metal angle and support members every 8' – 15' along the building perimeter. In each of these instances it was proposed that the end post would be driven 6' deep if the bracing was 8' on center; 8' deep if the bracing was 10' on center and 12' deep if the spacing was 15' on center. The mason stated that there was no physical way to drive the post in to that depth and that he would need to bore into the earth to create a footing and we had access issues that prohibited access to the larger equipment. A fence post digger could be used if the depth was to 4'-0" but the spacing on center would need to decrease to 4'-0" on center max. As we walked the site it became apparent to the mason that the expense for this shoring would be as much or more than an alternative solution. The mason estimated \$2.5 million at Challenger excluding the additional mobilization costs required to actually replace the horizontal rebar along the base of the walls, which the mason said would be difficult to estimate. **Relocation in lieu of shoring:** We also discussed the feasibility of a portable campus in lieu of shoring and it was determined that we wouldn't be able to secure permits, modular or utilities in an expeditious manner. **Potential student relocation to alternate campuses:** It was determined that the District didn't have available space at other campus locations to relocate students during repairs. **Shoring Alternative No. 2:** The mason proposed a solution that would provide a structural retaining wall essentially a "sister wall". This would allow the rusted rebar to be grouted in place and encapsulated. The "sister wall" would have its own footing and structural members that would provide the adequate strength when calculated in conjunction with the existing wall would restore the structural integrity of the wall (to the requirements at the time it was constructed).

The widely accepted useful life expectancy of a building is approximately 30 – 40 years we provided recommendations that address immediate repair to address life safety needs identified. These were identified as Phase 1 and should be implemented immediately. Phase 2 pricing will make safe the structure and allow additional time to plan for the implementation of a replacement campus.

**Landmark (070440101-1001-009, 070440101-999-003):**

- Recommendation is to proceed with Shoring Alternative No. 2 as a temporary solution
  - Based upon the calculations for shoring requirements and the existing conditions it was determined that the cost for shoring with the structural retaining wall would be less expensive than the Shoring Alternative No. 1 ("sister wall" was estimated to save at least \$1.8M over the initial shoring concept).
  - Estimated timeline to complete: 20 – 30 days.

**Landmark (070440101-1001-009, 070440101-999-003): Continued**

- Anticipated extension to useful life is 5 years. Contractor warranty would be 2 year.
- Minimizes amount of disruption at school because immediate shoring would remain in-situ and provides masonry repair at time of initial shoring.

**Challenger (070440111-1003-002, 070440111-999-004, 070440111-999-005):**

- Recommendation is to proceed with Shoring Alternative No. 2 as a temporary solution
  - Based upon the calculations for shoring requirements and the existing conditions it was determined that the cost for shoring with the structural retaining wall would be less expensive than the Shoring Alternative No. 1 ("sister wall" was estimated to save at least \$1.5M over the initial shoring concept).
  - Estimated timeline to complete: 20 – 30 days.
  - Anticipated extension to useful life is 5 years. Contractor warranty would be 2 year.
  - Minimizes amount of disruption at school because immediate shoring would remain in-situ and provides masonry repair at time of initial shoring.

**Mensendick (070440106-9999-010, 070440106-9999-011):**

- Recommendation is to proceed with Shoring Alternative No. 3 as a temporary solution.
  - Based upon the calculations for shoring requirements and the existing conditions of the 1966/1958 buildings it was determined that the age/condition of the building made it a poor candidate for the "sister wall" temporary solution. An alternative bracing plan was created to provide horizontal reinforcing.
  - Estimated timeline to complete: 20 – 30 days.
  - Anticipated extension to useful life is approximately 1-2 years in area of work. Contractor warranty would be 2 years only related to the 55 panels that were in the worst condition.

**Smith (070440103-999-013):**


- This building is unreinforced as that was not necessary at the time it was constructed in 1952, however deterioration is present and conditions are worsening.
  - No immediate need for temporary shoring needed at this site.

Sincerely,

SPS+ ARCHITECTS, LLP



Mark Davenport, AIA, LEED AP BD&C  
Partner



**NOTES:**

1. EXISTING MASONRY WALL.
2. EXISTING CONCRETE FOOTING.
3. EXISTING CONCRETE SLAB.
4. CONCRETE SLAB OR FINISHED GRADE AS OCCURS.
5. CONTINUOUS FULLY GROUTED BOND BEAM REINFORCED W/1-#4 CONTINUOUS.
6. 6" CONCRETE MASONRY WALL.
7. CAP BLOCK PER ARCHITECTURAL DRAWINGS.
8. WHERE "H" IS 12'-0" OR LESS, REINFORCE W/4 VERTICALS @ 32"O.C. WHERE "H" IS GREATER THAN 12'-0", REINFORCE W/4 VERTICALS @ 16"O.C.
9. #4 DOWELS WITH STD. 90° HOOK @ 48"O.C. MAX. DRILL AND EPOXY INTO EXISTING FULLY GROUTED CELL W/4" MIN. EMBED.
10. REMOVE DELAMINATED & CRACKED CMU & GROUT SOLID.
11. MORTAR COLLAR JOINT SOLID.
12. CONCRETE FOOTING.
13. 1-#4 CONTINUOUS.
14. #4 DOWELS WITH STD. 90° HOOK @ 18"O.C. MAX. DRILL AND EPOXY INTO EXISTING FOOTING W/4" MIN. EMBED.

1

SECTION

N.T.S.



David Bixler & Associates  
Structural Engineering

8360 East Raintree Drive, Suite 110  
Scottsdale, Arizona 85260

Office: (480) 219-2886 Fax: (480) 588-8584  
www.dbaaeng.com


UNLESS THIS DRAWING IS SIGNED AND SEALED BY A LICENSED STRUCTURAL ENGINEER, IT IS A PRELIMINARY DESIGN AND SHALL NOT BE USED FOR CONSTRUCTION

**LANDMARK SCHOOL**  
5730 WEST MYRTLE AVENUE  
GLENDALE, AZ



DRAWN BY:	ERB
CHECKED BY:	WDB
JOB NO:	16.097
PRINTED:	08.31.2016

**SSK1**



**NOTES:**

1. EXISTING MASONRY WALL.
2. EXISTING CONCRETE FOOTING.
3. EXISTING CONCRETE SLAB.
4. CONCRETE SLAB OR FINISHED GRADE AS OCCURS.
5. CONTINUOUS FULLY GROUTED BOND BEAM REINFORCED W/1-#4 CONTINUOUS.
6. 6" CONCRETE MASONRY WALL.
7. CAP BLOCK PER ARCHITECTURAL DRAWINGS.
8. WHERE "H" IS 12'-0" OR LESS, REINFORCE W/#4 VERTICALS @ 32"O.C. WHERE "H" IS GREATER THAN 12'-0", REINFORCE W/#4 VERTICALS @ 16"O.C.
9. #4 DOWELS WITH STD. 90° HOOK @ 48"O.C. MAX. DRILL AND EPOXY INTO EXISTING FULLY GROUTED CELL W/4" MIN. EMBED.
10. REMOVE DELAMINATED & CRACKED CMU & GROUT SOLID.
11. MORTAR COLLAR JOINT SOLID.

2

SECTION

N.T.S.



David Bixler & Associates  
Structural Engineering

8360 East Raintree Drive, Suite 110  
Scottsdale, Arizona 85260  
Office: (480) 219-2886 Fax: (480) 588-8584  
www.dbaaeng.com


UNLESS THIS DRAWING IS SIGNED AND SEALED BY A LICENSED STRUCTURAL ENGINEER, IT IS A PRELIMINARY DESIGN AND SHALL NOT BE USED FOR CONSTRUCTION.

**LANDMARK SCHOOL**  
5730 WEST MYRTLE AVENUE  
GLENDALE, AZ



DRAWN BY:	ERB
CHECKED BY:	WDB
JOB NO:	16.097
PRINTED:	08.31.2016

**SSK2**



**NOTES:**

1. EXISTING MASONRY WALL.
2. EXISTING CONCRETE FOOTING.
3. EXISTING CONCRETE SLAB.
4. CONCRETE SLAB OR FINISHED GRADE AS OCCURS.
5. CONTINUOUS FULLY GROUTED BOND BEAM REINFORCED W/1-#4 CONTINUOUS.
6. 6" CONCRETE MASONRY WALL.
7. CAP BLOCK PER ARCHITECTURAL DRAWINGS.
8. WHERE "H" IS 12'-0" OR LESS, REINFORCE W/#4 VERTICALS @ 32"O.C. WHERE "H" IS GREATER THAN 12'-0", REINFORCE W/#4 VERTICALS @ 16"O.C.
9. #4 DOWELS WITH STD. 90° HOOK @ 48"O.C. MAX. DRILL AND EPOXY INTO EXISTING FULLY GROUTED CELL W/4" MIN. EMBED.
10. REMOVE DELAMINATED & CRACKED CMU & GROUT SOLID.
11. MORTAR COLLAR JOINT SOLID.
12. CONCRETE FOOTING.
13. 1-#4 CONTINUOUS.
14. #4 DOWELS WITH STD. 90° HOOK @ 18"O.C. MAX. DRILL AND EPOXY INTO EXISTING FOOTING W/4" MIN. EMBED.

1

SECTION

N.T.S.



**David Bixler & Associates**  
Structural Engineering

8360 East Raintree Drive, Suite 110  
Scottsdale, Arizona 85260

Office: (480) 219-2886 Fax: (480) 588-8584  
www.dbaaeng.com

UNLESS THIS DRAWING IS SIGNED AND SEALED BY A LICENSED STRUCTURAL ENGINEER, IT IS A PRELIMINARY DESIGN AND SHALL NOT BE USED FOR CONSTRUCTION.


**CHALLENGER SCHOOL**  
6095 WEST MARYLAND AVENUE  
GLENDALE, AZ 85303



DRAWN BY:	ERB
CHECKED BY:	WDB
JOB NO:	16.096
PRINTED:	08.31.2016

**SSK1**





**NOTES:**

1. EXISTING MASONRY WALL.
2. EXISTING CONCRETE FOOTING.
3. EXISTING CONCRETE SLAB.
4. CONCRETE SLAB OR FINISHED GRADE AS OCCURS.
5. CONTINUOUS FULLY GROUTED BOND BEAM REINFORCED W/1-#4 CONTINUOUS.
6. 6" CONCRETE MASONRY WALL.
7. CAP BLOCK PER ARCHITECTURAL DRAWINGS.
8. WHERE "H" IS 12'-0" OR LESS, REINFORCE W/#4 VERTICALS @ 32"O.C. WHERE "H" IS GREATER THAN 12'-0", REINFORCE W/#4 VERTICALS @ 16"O.C.
9. #4 DOWELS WITH STD. 90° HOOK @ 48"O.C. MAX. DRILL AND EPOXY INTO EXISTING FULLY GROUTED CELL W/4" MIN. EMBED.
10. REMOVE DELAMINATED & CRACKED CMU & GROUT SOLID.
11. MORTAR COLLAR JOINT SOLID.

2

SECTION

N.T.S.




**David Bixler & Associates**  
Structural Engineering

8360 East Raintree Drive, Suite 110  
Scottsdale, Arizona 85260  
Office: (480) 219-2886 Fax: (480) 588-8584  
www.dbaaeng.com


UNLESS THIS DRAWING IS SIGNED AND SEALED BY A LICENSED STRUCTURAL ENGINEER, IT IS A PRELIMINARY DESIGN AND SHALL NOT BE USED FOR CONSTRUCTION.

**CHALLENGER SCHOOL**  
6095 WEST MARYLAND AVENUE  
GLENDALE, AZ 85303



DRAWN BY:	ERB
CHECKED BY:	WDB
JOB NO:	16.096
PRINTED:	08.31.2016

**SSK2**



**NOTES:**

1. EXISTING MASONRY WALL.
2. EXISTING WINDOW OPENING.
3. EXISTING WOOD COLUMN.
4. C6x8.2 CONT.
5. 1/2"Ø x 4" EMBED LAG SCREWS @ 24"O.C.
6. 1/2"Ø x 6" EMBED EPOXY BOLTS @ 24"O.C.
7. 1/4"x3"x1'-0" STEEL PLATE.

3

ELEVATION

N.T.S.




David Bixler & Associates  
Structural Engineering

8360 East Raintree Drive, Suite 110  
Scottsdale, Arizona 85260

Office: (480) 219-2886 Fax: (480) 588-8584  
www.dbaaeng.com

UNLESS THIS DRAWING IS SIGNED AND SEALED BY A LICENSED STRUCTURAL ENGINEER, IT IS A PRELIMINARY DESIGN AND SHALL NOT BE USED FOR CONSTRUCTION.

**DON MESSENDICK SCHOOL**  
5535 NORTH 67TH AVENUE  
GLENDALE, AZ 85301



DRAWN BY:	ERB
CHECKED BY:	WDB
JOB NO:	16.098
PRINTED:	08.31.2016

**SSK1**



DAVID  
**BIXLER**  
& ASSOCIATES

Project: GESD Pre-Site Walk


Project #: Proposed Shoring Detail

Prepared by: \_\_\_\_\_

Date: 8/30/16

Subject: \_\_\_\_\_

Sheet: \_\_\_\_\_ of: \_\_\_\_\_





# Glendale Elementary School District SFB Projects: Construction Cost Estimates

BRG: Project: Scope: Updated 9/1/16 Cost Estimate:

070440101-9999-003-BRG	Landmark Reseal		
	<b>Phase 1</b>	Sister wall: this is inclusive of footings, spoil removal, backfill, drilling, doweling, install and everything in the details and put back like we were never there.	\$ 907,038.00
		Adjustments required for sister wall installation; extend electrical, downspouts, relocate irrigation boxes and other conflicts	\$ 227,541.00
		<b>Estimated Phase 1 Subtotal</b>	<b>\$ 1,134,579.00</b>
	<b>Phase 2</b>	Installation of masonry control joints/repair CMU	\$ 40,000.00
		Weatherproof at new materials: Blockfill of new masonry and coating of Drylok extreme at exposed footing	\$ 11,000.00
		Drainage corrections to remove turf and irrigation against building and replace with decomposed granite from face of wall to 5'-0" away from building	\$ 46,765.00
		<b>Estimated Phase 2 Subtotal</b>	<b>\$ 97,765.00</b>
		<b>Estimated Total Repair:</b>	<b>\$ 1,232,344.00</b>

August 26, 2016



Mr. Greg Gilliam  
Director of Maintenance & Operations  
Glendale Elementary School District #40  
Support Services  
7015 W. Maryland Avenue  
Glendale, AZ 85303

Robert L Pian, AIA  
William R Pittenger, RA, CSI  
Mark A Davenport, AIA, LEED AP  
Herb W Schneider, FAIA  
Howell Lewis Shay, AIA

**RE: Glendale Elementary School District #40**  
**SFB Corrections at Landmark School – Additional Services Request**  
SPS+ Architects Fee Proposal 1535A.4  
GESD Purchase Order 3602079  
**SFB Project # 070440111-999-003-BRG**

Dear Mr. Gilliam:

Thank you for the opportunity to work with you on your SFB Corrections at the above referenced School. We understand this will be an SFB funded project using Building Renewal Grants. Thank you in advance for your consideration of our additional services request.

Additional Services Scope of work:

Structural remediation in accordance with the attached coversheet from our structural engineer Bixler and associates. Please see below for an executive summary:

- Structural: Our engineer agrees with the Gervasio reports for structural repairs at the gym, media and admin areas. This includes painting at areas of repair.
- Weatherization project conditions: There was a significant amount of damage discovered for the reinforcing steel near the bottom of the walls. When you add the moisture conditions present, the amount of cracking, the fact that basically all the holes that had reinforcing, the reinforcing was approximately 33% to 66% rusted. In essence, at all those cracks along grade, the CMU face shells are basically delaminated, so the old 8" wall is now 5-6" or 4" at that point and then obviously the wall that is not close to current code now, is much worse. The engineer is unable to perform calculations without knowing to what extent the steel has delaminated. Therefore, I concur with the engineer and recommend to move forward with these repairs as soon as possible and brace immediately. We also recommend removing grass and irrigation within 5 feet of the buildings.

Fee Proposal: \$34,650

Fee includes Architectural and Structural services for the following:

- Coordination of immediate implementation of wall bracing.
- Construction documents and construction administration utilizing a district procured contractor of the scope of work described above and attached.
- Special structural inspections during construction administration.
- Reimbursable expenses for printing, travel, etc.

Please let me know if you have any comments regarding our proposal. We are anticipating this proposal being approved at the September 7<sup>th</sup>, 2016 SFB board meeting.

Sincerely,

SPS+ ARCHITECTS, LLP

A handwritten signature in black ink, consisting of a stylized 'M' followed by a long, sweeping horizontal line that curves slightly upwards at the end.

Mark Davenport, AIA, LEED AP BD&C  
Partner

enclosure

Cc: Mike Barragan, David Kennon, Terry Tower, Jennifer Bowen





# DAVID BIXLER & ASSOCIATES

## Structural Engineering

### VISION

August 23, 2016

Our vision is  
to be recognized  
throughout the  
Southwest as the  
leader in structural  
engineering.

Mark Davenport AIA, CEFPI, LEED AP, BD+C  
SPS+ ARCHITECTS LLP  
8681 E. Via de Negocio  
Scottsdale, AZ 85258

**Re: Landmark Middle School  
Glendale, AZ**

### COMMITMENT

Dear Mr. Davenport:

We are committed to  
■ technological  
leadership  
■ innovative and cost-  
effective solutions  
■ quality work  
■ client satisfaction.

Per your request, we visited the Landmark Middle School on several occasions. I also have reviewed the reports from both Speedie and Associates and Gervasio and Associates, which are attached to the end of this report, along with pictures from our site visits during the CMU removal to investigate the reinforcing and typical pictures of the type of cracking along the buildings. We also reviewed the existing plans of the buildings which we have received. The purpose of this report is to review the conditions of the existing buildings along with the reports prepared by other consultants, and to recommend a plan of action going forward on the best course of action to remedy the deficient areas.

The buildings are typically steel and wood framed roofs bearing on CMU exterior walls and concrete spread footings.

### VALUES

Our team delivers  
integrity  
service  
collaboration  
quality  
efficiency

Based on the surface penetrating radar investigations Speedie and Associates performed, the vertical reinforcing appears to be installed for the most part correctly, and based off of their radar findings, there is nothing that is significantly different than what we would expect.

Based on the soils investigations performed by Speedie and Associate, there does not appear to be a specific cause of the masonry distress due to the soils themselves, except the fact that the soil conditions are very moist. The moisture fluctuations in the soils will have a tendency to cause continuous movement in the soils which will induce stresses on the buildings which will sometimes result in cracks of the CMU.



# DAVID BIXLER & ASSOCIATES

## Structural Engineering

There were three reports done by Gervasio and Associates that we have received and reviewed: (1) report dated February 15, 2011 dealing mostly with cracks in the North-East corner of the Gym Building, (2) report dated May 27, 2014 dealing with cracks in the masonry piers at the Administration building, and (3) report dated July 20, 2015 dealing with cracks in the interior and exterior walls, deteriorating concrete piers, corroded metal deck and steel joist bearings in the media center. For the gymnasium cracks, Gervasio maintains that there were three different types of cracks, a stair-stepped crack near the corner, a vertical crack at the change in parapet height and a crack at beam bearing. They indicated that only the crack at the beam bearing was in need of repair and that the others could be caulked to prevent moisture. Gervasio recommended that the crack at beam bearing be modified to allow for thermal movement in the beam. All of the additional investigations that have been performed since then would indicate that they are most likely correct. Since the moisture around the building is currently in the process of getting corrected, I would recommend that instead of just caulking the cracks, I would repoint and repair or replace the block as required to bring it back to its original state. At the vertical crack I would recommend adding the vertical masonry control joint that is missing to prevent future cracking.

Finally, at the beam bearing location, this bearing condition needs to be rebuilt with a neoprene pad below the beam bearing to allow for movement and the CMU below should be rebuilt and grouted properly. In the second report dealing with the vertical cracks in the masonry piers, Gervasio recommended tying the two walls together by doweling and epoxying them and attaching the piers to the building with doweling and epoxying as well. I agree with their recommendations since the moisture issue is being corrected. For the media center for the interior and exterior cracks, Gervasio recommends drying out the crawl space and fixing the broken water line and then repairing the cracks. For the deteriorated concrete piers Gervasio recommends installing new posts besides the beam to support the beam. Since the moisture issues are being corrected, I recommend repairing the concrete piers. This will not change the current load path and will remove the corroded steel in the piers which will continue to deteriorate even with the moisture removed. For the steel joist bearing on wood blocks, Gervasio recommends removing the wood shims and installing dry pack below the joist; I agree with this recommendation.

From our review of the CMU demolition and our cursory review of the buildings in general, we discovered numerous cracking and rusted reinforcing.

From the four holes that were opened up to expose the reinforcing, we found rusted and deteriorated vertical and horizontal reinforcing in each location. The footings in three of the locations appeared to be in good condition and the correct size, but the fourth was tapered from maybe only 8 inches thick to 2 inches thick at the edge.





# DAVID BIXLER & ASSOCIATES

## Structural Engineering

From our visual inspection, we noticed several different types of cracks, and too many to document all of them. They basically fell into two categories:

1. There were several areas where there are shrinkage cracks, most likely due to insufficient or improper locations of masonry control joints, or improperly installed masonry control joints (see photographs 8 and 11 on building 1, photos 4 and 9 on building 2, photo 6 and 15 on building 3 and photo 1 on building 6 and photo 3 on building 7). While these are not structural in nature, they will affect the waterproofing integrity of the building and therefore I recommend that new masonry control joints be installed and for the CMU in these areas to be tuck pointed and repaired or replaced as applicable. There were approximately 10-15 locations throughout the school where this occurred.

2. The remaining photos appear to be related to moisture and the rusting of the reinforcing in the CMU. Since reinforcing when it rusts can grow to over 400% of its original size, it appears that the reinforcing has rusted, expanded and has cracked the CMU. Since the face shell is now delaminated, it causes the CMU to be reduced in size and therefore to be reduced in strength. There is no real way to determine the loss in strength without knowing the exact thickness of the delaminated CMU. This is a very old building that does not comply with the current building codes, and there is reduced strength of the existing wall with the delamination of the face shells. The reduction in strength could easily range from 33%-90%. Therefore, I recommend that the CMU walls be braced immediately until the repairs are complete.

In addition, there is no real way to eliminate moisture from entering into the CMU with the cracks in it and this will continue to make the condition worse. There is no easy or accurate way to determine the extents of the rusting in the CMU without removing the face shells and investigating the reinforcing as we did in those four locations. The repair for these locations would be extremely expensive but would entail removing the CMU and exposing the rusted reinforcing and then removing it and replacing it with new reinforcing, grout and CMU. This would need to be done in an explorative manner where you start at each of the cracks and then you expand outward until you get to undamaged CMU and reinforcing. Therefore, there is no real way to determine the extents but due to the moisture conditions and the amount of cracking that is visible I would not be surprised if 50%-75% of the length of the walls at the grade line are damaged in this manner. The CMU walls should be braced immediately until the repairs are complete. To avoid continued and future damage, the drainage around the buildings should be also corrected. All sprinkler lines should be moved away from the buildings, and all of the grades should be sloped to divert the water away from the buildings.

If the decision is to repair the school, then this should start immediately, and we should brace the CMU walls until the repairs are completed. Without knowing the extent of the damage, it is extremely difficult to determine how the walls will perform as the reinforcing continues to rust and the walls continue to worsen.



# DAVID BIXLER & ASSOCIATES

## Structural Engineering

While it is extremely difficult to provide any budgetary numbers due to the uncertainty of the full scope and amount of damage we estimate the following corresponding to the item numbers above:

1) Temporary bracing of the CMU walls:	\$70,000
2) Installation of masonry control joints and repair of damaged CMU:	\$40,000
3) Repair of the cracked CMU and rusted reinforcing (not including drainage):	\$250,000
4) Gervasio report regarding gym cracks:	\$20,000
5) Gervasio report regarding column cracks:	\$25,000
6) Gervasio report regarding the media center:	\$150,000

Please understand that this report represents a professional opinion based upon the results of our limited observations, and past experience with similar conditions. Our study was strictly limited to visual observations as stated above. This report is not intended to be a complete or comprehensive study of the structure. We have not reviewed, nor have we been asked to review, the capacity of the existing structure per the current code. Our work has been performed in accordance with generally accepted principles and practices of structural engineering.


We cannot be responsible for any future changes in the condition of the structure. No warranty is provided, either expressed or implied.


If there are any additional concerns or questions, please feel free to contact our office. Thank you for the opportunity to assist you on this project.

Sincerely,

*David Bixler*

David Bixler, PE, SE President  
David Bixler & Associates, PLLC





# NOTES:

1. EXISTING MASONRY WALL.
2. EXISTING CONCRETE FOOTING.
3. EXISTING CONCRETE SLAB.
4. CONCRETE SLAB OR FINISHED GRADE AS OCCURS.
5. CONTINUOUS FULLY GROUTED BOND BEAM REINFORCED W/1-#4 CONTINUOUS.
6. 6" CONCRETE MASONRY WALL.
7. CAP BLOCK PER ARCHITECTURAL DRAWINGS.
8. WHERE "H" IS 12'-0" OR LESS, REINFORCE W/#4 VERTICALS @ 32"O.C. WHERE "H" IS GREATER THAN 12'-0", REINFORCE W/#4 VERTICALS @ 16"O.C.
9. #4 DOWELS WITH STD. 90° HOOK @ 48"O.C. MAX. DRILL AND EPOXY INTO EXISTING FULLY GROUTED CELL W/4" MIN. EMBED.
10. REMOVE DELAMINATED & CRACKED CMU & GROUT SOLID.
11. MORTAR COLLAR JOINT SOLID.
12. CONCRETE FOOTING.
13. 1-#4 CONTINUOUS.
14. #4 DOWELS WITH STD. 90° HOOK @ 18"O.C. MAX. DRILL AND EPOXY INTO EXISTING FOOTING W/4" MIN. EMBED.

1

SECTION

N.T.S.



David Bixler & Associates  
Structural Engineering

8360 East Raintree Drive, Suite 110  
Scottsdale, Arizona 85260

Office: (480) 219-2886 Fax: (480) 588-8584  
www.dbaaeng.com

UNLESS THIS DRAWING IS SIGNED AND SEALED BY A LICENSED STRUCTURAL ENGINEER, IT IS A PRELIMINARY DESIGN AND SHALL NOT BE USED FOR CONSTRUCTION


**LANDMARK SCHOOL**  
5730 WEST MYRTLE AVENUE  
GLENDALE, AZ



DRAWN BY:	ERB
CHECKED BY:	WDB
JOB NO:	16.097
PRINTED:	08.31.2016

**SSK1**





**NOTES:**

1. EXISTING MASONRY WALL.
2. EXISTING CONCRETE FOOTING.
3. EXISTING CONCRETE SLAB.
4. CONCRETE SLAB OR FINISHED GRADE AS OCCURS.
5. CONTINUOUS FULLY GROUTED BOND BEAM REINFORCED W/1-#4 CONTINUOUS.
6. 6" CONCRETE MASONRY WALL.
7. CAP BLOCK PER ARCHITECTURAL DRAWINGS.
8. WHERE "H" IS 12'-0" OR LESS, REINFORCE W/#4 VERTICALS @ 32"O.C. WHERE "H" IS GREATER THAN 12'-0", REINFORCE W/#4 VERTICALS @ 16"O.C.
9. #4 DOWELS WITH STD. 90° HOOK @ 48"O.C. MAX. DRILL AND EPOXY INTO EXISTING FULLY GROUTED CELL W/4" MIN. EMBED.
10. REMOVE DELAMINATED & CRACKED CMU & GROUT SOLID.
11. MORTAR COLLAR JOINT SOLID.

2

SECTION

N.T.S.



David Bixler & Associates  
Structural Engineering

8360 East Raintree Drive, Suite 110  
Scottsdale, Arizona 85260  
Office: (480) 219-2886 Fax: (480) 588-8584  
www.dbaaeng.com

UNLESS THIS DRAWING IS SIGNED AND SEALED BY A LICENSED STRUCTURAL ENGINEER, IT IS A PRELIMINARY DESIGN AND SHALL NOT BE USED FOR CONSTRUCTION.

**LANDMARK SCHOOL**  
5730 WEST MYRTLE AVENUE  
GLENDALE, AZ



DRAWN BY:	ERB
CHECKED BY:	WDB
JOB NO:	16.097
PRINTED:	08.31.2016

**SSK2**







# STRUCTURAL CALCULATIONS FOR LANDMARK ELEMENTARY SCHOOL WALL REPAIRS

DBAA Job No. 16.097

August 31, 2016

## PREPARED FOR:

Jennifer Bowen, Director of Design

SPS+ Architects LLP

[jbowen@spsplusarchitects.com](mailto:jbowen@spsplusarchitects.com)


480.544.5851



## PREPARED BY:

DAVID BIXLER & ASSOCIATES  
STRUCTURAL ENGINEERING  
8360 E. RAIN TREE DR., SUITE 110  
SCOTTSDALE, AZ 85260  
PHONE: (480) 219-2886  
[david.bixler@dbaaeng.com](mailto:david.bixler@dbaaeng.com)  
[www.dbaaeng.com](http://www.dbaaeng.com)





DAVID  
**BIXLER**  
& ASSOCIATES

$$> .12' \times 3075 \text{ PSF} (24' / 2) = 360 \text{ k}$$

$$M = 360 \text{ k} (3' - 4") = 1198 \text{ k-ft}$$

$$M_u = 1.2 (1198 \text{ k-ft}) = 1438 \text{ k-ft}$$

Project

Project #:

Prepared by:

Date:

Subject:

> 42' - 0"

Sheet: of:

34 PSF

$$34 \text{ PSF} (12' / 2) = 204 \text{ k}$$

$$204 \text{ k} (3' - 4") = 680 \text{ k-ft}$$

$$680 \text{ k-ft} (108 \text{ k-ft})$$

REMOVE DELTA AND JAZZ  
& CRACKED CONCRETE  
\* 6" REINFORCING

Fill Column  
IT SOUND

DRILL & GROUT  
#4 DOWEL WITH SPD  
90° HOOK (4" DIA)  
= 4" OK MARK

CAP BLOCK  
ZERO TO MARK

3' - 4" STRAP

CUT ROUGH BORN WITH  
1 - #4

6" CONCRETE WITH

#4 @ 32"

#4 @ 16"

SPD  
90°  
HOOK  
5" DIA  
AS  
DETA

18" DIA


CUT #4

SPD

#4 DOWEL WITH SPD  
90° HOOK @ 18" OK







DAVID  
**BIXLER**  
& ASSOCIATES

Project: \_\_\_\_\_


Project #: \_\_\_\_\_

Prepared by: \_\_\_\_\_

Date: \_\_\_\_\_

Subject: \_\_\_\_\_

Sheet: \_\_\_\_\_ of: \_\_\_\_\_







# Wind Analysis for Low-rise Building, Based on ASCE 7-2010

## INPUT DATA

Exposure category (B, C or D, ASCE 7-10 26.7.3)

Importance factor (ASCE 7-10 Table 1.5-2)

Basic wind speed (ASCE 7-10 26.5.1 or 2012 IBC)

Topographic factor (ASCE 7-10 26.8 & Table 26.8-1)

Building height to eave


Building height to ridge

Building length

Building width

Effective area of components (or Solar Panel area)

C  
 $I_w = 1.00$  for all Category  
 $V = 120$  mph  
 $K_{zt} = 1$  Flat  
 $h_e = 10$  ft  
 $h_r = 10$  ft  
 $L = 100$  ft  
 $B = 50$  ft  
 $A = 33$  ft<sup>2</sup>



## DESIGN SUMMARY

Max horizontal force normal to building length, L, face

Max horizontal force normal to building length, B, face

Max total horizontal torsional load

Max total upward force

= 19.12 kips, SD level (LRFD level), Typ.  
= 9.93 kips  
= 222.03 ft-kips  
= 97.43 kips

## ANALYSIS

### Velocity pressure

$$q_h = 0.00256 K_h K_{zt} K_d V^2 = 26.63 \text{ psf}$$

where:  $q_h$  = velocity pressure at mean roof height, h. (Eq. 28.3-1 page 298 & Eq. 30.3-1 page 316)

$K_h$  = velocity pressure exposure coefficient evaluated at height, h, (Tab. 28.3-1, pg 299)

$K_d$  = wind directionality factor. (Tab. 26.6-1, for building, page 250)

h = mean roof height

= 0.85

= 0.85

= 10.00 ft

< 60 ft, [Satisfactory]

(ASCE 7-10 26.2.1)

< Min (L, B), [Satisfactory]

(ASCE 7-10 26.2.2)

### Design pressures for MWFRS

$$p = q_h [(G C_{pf}) - (G C_{pi})]$$

where: p = pressure in appropriate zone. (Eq. 28.4-1, page 298).

$p_{min} = 16$  psf (ASCE 7-10 28.4.4)

$G C_{pf}$  = product of gust effect factor and external pressure coefficient, see table below. (Fig. 28.4-1, page 300 & 301)

$G C_{pi}$  = product of gust effect factor and internal pressure coefficient. (Tab. 26.11-1, Enclosed Building, page 258)

= 0.18 or -0.18


a = width of edge strips, Fig 28.4-1, note 9, page 301, MAX[ MIN(0.1B, 0.1L, 0.4h), MIN(0.04B, 0.04L), 3] = 4.00 ft

### Net Pressures (psf), Basic Load Cases

Surface	Roof angle $\theta = 0.00$			Roof angle $\theta = 0.00$		
	$G C_{pf}$	Net Pressure with		$G C_{pf}$	Net Pressure with	
		(+GC <sub>pi</sub> )	(-GC <sub>pi</sub> )		(+GC <sub>pi</sub> )	(-GC <sub>pi</sub> )
1	0.40	5.86	15.45	-0.45	-16.78	-7.19
2	-0.69	-23.17	-13.58	-0.69	-23.17	-13.58
3	-0.37	-14.65	-5.06	-0.37	-14.65	-5.06
4	-0.29	-12.52	-2.93	-0.45	-16.78	-7.19
5				0.40	5.86	15.45
6				-0.29	-12.52	-2.93
1E	0.61	11.45	21.04	-0.48	-17.58	-7.99
2E	-1.07	-33.29	-23.70	-1.07	-33.29	-23.70
3E	-0.53	-18.91	-9.32	-0.53	-18.91	-9.32
4E	-0.43	-16.25	-6.66	-0.48	-17.58	-7.99
5E				0.61	11.45	21.04
6E				-0.43	-16.25	-6.66

### Net Pressures (psf), Torsional Load Cases


Surface	Roof angle $\theta = 0.00$		
	$G C_{pf}$	Net Pressure with	
		(+GC <sub>pi</sub> )	(-GC <sub>pi</sub> )
1T	0.40	1.46	3.86
2T	-0.69	-5.79	-3.40
3T	-0.37	-3.66	-1.27
4T	-0.29	-3.13	-0.73
Surface	Roof angle $\theta = 0.00$		
	$G C_{pf}$	Net Pressure with	
		(+GC <sub>pi</sub> )	(-GC <sub>pi</sub> )
5T	0.40	1.46	3.86
6T	-0.29	-3.13	-0.73



Load Case A (Transverse)

Load Case B (Longitudinal)

Basic Load Cases



Load Case A (Transverse)

Load Case B (Longitudinal)

Torsional Load Cases

**Basic Load Case A (Transverse Direction)**

Surface	Area (ft <sup>2</sup> )	Pressure (k) with	
		(+GC <sub>p1</sub> )	(-GC <sub>p1</sub> )
1	920	5.39	14.21
2	2300	-53.30	-31.24
3	2300	-33.69	-11.64
4	920	-11.52	-2.70
1E	80	0.92	1.68
2E	200	-6.66	-4.74
3E	200	-3.78	-1.86
4E	80	-1.30	-0.53
Σ	Horiz.	19.12	19.12
	Vert.	-97.43	-49.49
Min. wind	Horiz.	16.00	16.00
28.4.4	Vert.	-80.00	-80.00

**Basic Load Case B (Longitudinal Direction)**

Surface	Area (ft <sup>2</sup> )	Pressure (k) with	
		(+GC <sub>p1</sub> )	(-GC <sub>p1</sub> )
2	2300	-53.30	-31.24
3	2300	-33.69	-11.64
5	420	2.46	6.49
6	420	-5.26	-1.23
2E	200	-6.66	-4.74
3E	200	-3.78	-1.86
5E	80	0.92	1.68
6E	80	-1.30	-0.53
Σ	Horiz.	9.93	9.93
	Vert.	-87.37	-41.73
Min. wind	Horiz.	8.00	8.00
28.4.4	Vert.	-80.00	-80.00

**Torsional Load Case A (Transverse Direction)**

Surface	Area (ft <sup>2</sup> )	Pressure (k) with		Torsion (ft-k)	
		(+GC <sub>p1</sub> )	(-GC <sub>p1</sub> )	(+GC <sub>p1</sub> )	(-GC <sub>p1</sub> )
1	420	2.46	6.49	57	149
2	1050	-24.33	-14.26	0	0
3	1050	-15.38	-5.31	0	0
4	420	-5.26	-1.23	121	28
1E	80	0.92	1.68	42	77
2E	200	-6.66	-4.74	0	0
3E	200	-3.78	-1.86	0	0
4E	80	-1.30	-0.53	60	25
1T	500	0.73	1.93	-18	-48
2T	1250	-7.24	-4.24	0	0
3T	1250	-4.58	-1.58	0	0
4T	500	-1.56	-0.37	-39	-9
Total Horiz. Torsional Load, M <sub>T</sub>				222	222

**Torsional Load Case B (Longitudinal Direction)**

Surface	Area (ft <sup>2</sup> )	Pressure (k) with		Torsion (ft-k)	
		(+GC <sub>p1</sub> )	(-GC <sub>p1</sub> )	(+GC <sub>p1</sub> )	(-GC <sub>p1</sub> )
2	2300	-53.30	-31.24	0	0
3	2300	-33.69	-11.64	0	0
5	170	1.00	2.63	10	28
6	170	-2.13	-0.50	22	5
2E	200	-6.66	-4.74	0	0
3E	200	-3.78	-1.86	0	0
5E	80	0.92	1.68	21	39
6E	80	-1.30	-0.53	30	12
5T	250	0.37	0.97	-5	-12
6T	250	-0.78	-0.18	-10	-2
Total Horiz. Torsional Load, M <sub>T</sub>				69.4	69.4

**Design pressures for components and cladding**


$$p = q_h [ (G C_p) - (G C_{pi}) ]$$

where: p = pressure on component. (Eq. 30.4-1, pg 318)

p<sub>min</sub> = 16.00 psf (ASCE 7-10 30.2.2)

G C<sub>p</sub> = external pressure coefficient.


see table below. (ASCE 7-10 30.4.2)



Walls



Roof θ < 7°



Roof θ > 7°

	Effective Area (ft <sup>2</sup> )	Zone 1		Zone 2		Zone 3		Zone 4		Zone 5	
		GC <sub>p</sub>	-GC <sub>p</sub>	GC <sub>p</sub>	-GC <sub>p</sub>	GC <sub>p</sub>	-GC <sub>p</sub>	GC <sub>p</sub>	-GC <sub>p</sub>	GC <sub>p</sub>	-GC <sub>p</sub>
Comp.	33	0.25	-0.95	0.25	-1.44	0.25	-1.92	0.82	-0.91	0.82	-1.10

(Walls reduced 10 %, Fig. 6-11A note 5.)

Comp. & Cladding Pressure (psf)	Zone 1		Zone 2		Zone 3		Zone 4		Zone 5	
	Positive	Negative	Positive	Negative	Positive	Negative	Positive	Negative	Positive	Negative
	16.00	-30.05	16.00	-43.07	16.00	-55.89	26.57	-28.97	26.57	-33.96

Note: If the effective area is roof Solar Panel area, the only zone 1, 2, or 3 apply.

Title Block Line 1  
 You can change this area  
 using the "Settings" menu item  
 and then using the "Printing &  
 Title Block" selection.  
 Title Block Line 6

Project Title:  
 Engineer:  
 Project Descr:

Project ID:

Printed: 31 AUG 2016, 1:46PM

## Masonry Slender Wall

File = \\dbaa-sv2\projects\16096 Challenger Middle School\Engineering\16096 challenger.ec6

ENERCALC, INC. 1983-2016, Build 6.16.6.7, Ver 6.16.6.7

Licensee : DAVID BIXLER AND ASSOCIATES

Lic. # : KW-06009174

Description : equivalent cantilevered wall in front of existing wall

### Code References

Calculations per ACI 530-11, IBC 2012, CBC 2013, ASCE 7-10

Load Combinations Used : ASCE 7-10

### General Information

Calculations per ACI 530-11, IBC 2012, CBC 2013, ASCE 7-10

Construction Type : Grouted Hollow Concrete Masonry


F'm = 1.50 ksi  
 Fy - Yield = 60.0 ksi  
 Fr - Rupture = 61.0 psi  
 Em = f'm \* = 900.0  
 Max % of  $\rho_{bal}$  = 0.1106  
 Grout Density = 140 pcf  
 Block Weight Normal Weight  
 Wall Weight = 47.0 psf  
 Wall is grouted at rebar cells only

Nom. Wall Thickness 6 in  
 Actual Thickness 5.625 in  
 Rebar "d" distance 3.8125 in  
 Lower Level Rebar ...  
 Bar Size # 4  
 Bar Spacing 32.0 in  
 Temp Diff across thickness = deg F  
 Min Allow Out-of-plane Defl Ratio = 0  
 Minimum Vertical Steel % = 0.0020

### One-Story Wall Dimensions

A Clear Height = 4.660 ft  
 B Parapet height = 0.0 ft

Wall Support Condition Top & Bottom Pinned



### Lateral Loads

Wind Loads :

Full area WIND load 34.0 psf

Seismic Loads :

Wall Weight Seismic Load Input Method :

Direct entry of Lateral Wall Weight

Seismic Wall Lateral Load

0.0 psf

Fp 1.0 = 0.0 psf

(Applied to full "STRIP Width")

	D	Lr	L	E	W	Endpoints from Base top bottom
Distributed Lateral Load	0.0	0.0	0.0	0.0	4.0 k/ft	4.660 3.660 k/ft

Title Block Line 1  
 You can change this area  
 using the "Settings" menu item  
 and then using the "Printing &  
 Title Block" selection.  
 Title Block Line 6

Project Title:  
 Engineer:  
 Project Descr:

Project ID:

Printed: 31 AUG 2016, 1:46PM

## Masonry Slender Wall

File = \\dbaa-sv2\projects\16096 Challenger Middle School\Engineering\16096 challenger.ec6

ENERCALC, INC. 1983-2016, Build 6.16.6.7, Ver 6.16.6.7

Licensee : DAVID BIXLER AND ASSOCIATES

Lic. # : KW-06009174

Description : equivalent cantilevered wall in front of existing wall

### DESIGN SUMMARY

### Results reported for "Strip Width" of 12.0 in

Governing Load Combination . . .		Actual Values . . .		Allowable Values . . .	
<b>PASS</b>	Moment Capacity Check +0.90D+W+0.90H	Maximum Bending Stress Ratio =	<b>0.9770</b>		
		Max Mu	1.215 k-ft	Phi * Mn	1.245 k-ft
<b>PASS</b>	Service Deflection Check W Only	Actual Defl. Ratio L/	405	Allowable Defl. Ratio	150
		Max. Deflection	0.1380 in		
<b>PASS</b>	Axial Load Check +1.20D+0.50Lr+0.50L+W+1.60H	Max Pu / Ag	1.126 psi	Max. Allow. Defl.	0.3728 in
		Location	3.806 ft	0.2 * fm	300.0 psi
<b>PASS</b>	Reinforcing Limit Check	Controlling As/bd	0.001639	As/bd @ 1106 rho bal	0.1106

### Maximum Reactions . . . for Load Combination....

Top Horizontal	W Only	3.152 k
Base Horizontal	W Only	0.3854 k
Vertical Reaction	+D+0.60W+H	0.2190 k

### Design Maximum Combinations - Moments

### Results reported for "Strip Width" = 12 in.

Load Combination	Axial Load		Mcr k-ft	Mu k-ft	Moment Values			As Ratio	0.6 * rho bal
	Pu k	0.2*fm*b*t k			Phi	Phi Mn k-ft	As in^2		
	0.000	0.000	0.00	0.00	0.00	0.00	0.000	0.0000	0.0000
	0.000	0.000	0.00	0.00	0.00	0.00	0.000	0.0000	0.0000
	0.000	0.000	0.00	0.00	0.00	0.00	0.000	0.0000	0.0000
	0.000	0.000	0.00	0.00	0.00	0.00	0.000	0.0000	0.0000
+1.20D+1.60Lr+0.50W+1.60H at 3.73 to 3.88	0.053	14.400	0.26	0.61	0.90	1.25	0.075	0.0016	0.1106
	0.000	0.000	0.00	0.00	0.00	0.00	0.000	0.0000	0.0000
+1.20D+1.60S+0.50W+1.60H at 3.73 to 3.88	0.053	14.400	0.26	0.61	0.90	1.25	0.075	0.0016	0.1106
+1.20D+0.50Lr+0.50L+W+1.60H at 3.73 to 3.88	0.054	14.400	0.26	1.22	0.90	1.25	0.075	0.0016	0.1106
+1.20D+0.50L+0.50S+W+1.60H at 3.73 to 3.88	0.054	14.400	0.26	1.22	0.90	1.25	0.075	0.0016	0.1106
	0.000	0.000	0.00	0.00	0.00	0.00	0.000	0.0000	0.0000
+0.90D+W+0.90H at 3.73 to 3.88	0.041	14.400	0.26	1.22	0.90	1.24	0.075	0.0016	0.1106
	0.000	0.000	0.00	0.00	0.00	0.00	0.000	0.0000	0.0000

### Design Maximum Combinations - Deflections

### Results reported for "Strip Width" = 12 in.

Load Combination	Axial Load Pu k	Moment Values		I gross in^4	Stiffness		Deflections	
		Mcr k-ft	Mactual k-ft		I cracked in^4	I effective in^4	Deflection in	Defl. Ratio
	0.000	0.00	0.00	0.00	0.00	0.000	0.000	0.0
	0.000	0.00	0.00	0.00	0.00	0.000	0.000	0.0
	0.000	0.00	0.00	0.00	0.00	0.000	0.000	0.0
	0.000	0.00	0.00	0.00	0.00	0.000	0.000	0.0
	0.000	0.00	0.00	0.00	0.00	0.000	0.000	0.0
	0.000	0.00	0.00	0.00	0.00	0.000	0.000	0.0
+D+0.60W+H at 2.80 to 2.95	0.088	0.26	0.58	142.30	16.85	17.206	0.065	858.4
	0.000	0.00	0.00	0.00	0.00	0.000	0.000	0.0
+D+0.750Lr+0.750L+0.450W+H at 2.80 to 2.95	0.088	0.26	0.44	142.30	16.85	17.867	0.038	1,465.1
+D+0.750L+0.750S+0.450W+H at 2.80 to 2.95	0.088	0.26	0.44	142.30	16.85	17.867	0.038	1,465.1
	0.000	0.00	0.00	0.00	0.00	0.000	0.000	0.0
+0.60D+0.60W+0.60H at 2.80 to 2.95	0.053	0.26	0.58	142.30	16.74	17.098	0.065	854.1
	0.000	0.00	0.00	0.00	0.00	0.000	0.000	0.0
	0.000	0.00	0.00	0.00	0.00	0.000	0.000	0.0
	0.000	0.00	0.00	0.00	0.00	0.000	0.000	0.0
	0.000	0.00	0.00	0.00	0.00	0.000	0.000	0.0
	0.000	0.00	0.00	0.00	0.00	0.000	0.000	0.0

Title Block Line 1  
 You can change this area  
 using the "Settings" menu item  
 and then using the "Printing &  
 Title Block" selection.  
 Title Block Line 6

Project Title:  
 Engineer:  
 Project Descr:

Project ID:

Printed 31 AUG 2016, 1:46PM

## Masonry Slender Wall

File = \\dbaa-sv2\projects\16096 Challenger Middle School\Engineering\16096 challenger.ec6

ENERCALC, INC. 1983-2016, Build 6.16.6.7, Ver 6.16.6.7

Lic. # : KW-06009174

Licensee : DAVID BIXLER AND ASSOCIATES

Description : equivalent cantilevered wall in front of existing wall

### Design Maximum Combinations - Deflections

Results reported for "Strip Width" = 12 in.

Load Combination	Axial Load	Moment Values		Stiffness			Deflections	
	Pu	Mcr	Mactual	I gross	I cracked	I effective	Deflection	Defl. Ratio
	k	k-ft	k-ft	in^4	in^4	in^4	in	
W Only at 2.64 to 2.80	0.000	0.00	0.00	0.00	0.00	0.000	0.000	0.0
	0.000	0.26	0.92	142.30	16.58	16.657	0.138	405.4
	0.000	0.00	0.00	0.00	0.00	0.000	0.000	0.0
	0.000	0.00	0.00	0.00	0.00	0.000	0.000	0.0

### Reactions - Vertical & Horizontal

Results reported for "Strip Width" = 12 in.

Load Combination	Base Horizontal		Top Horizontal		Vertical @ Wall Base	
+D+H	0.0	k	0.00	k	0.219	k
+D+L+H	0.0	k	0.00	k	0.219	k
+D+Lr+H	0.0	k	0.00	k	0.219	k
+D+S+H	0.0	k	0.00	k	0.219	k
+D+0.750Lr+0.750L+H	0.0	k	0.00	k	0.219	k
+D+0.750L+0.750S+H	0.0	k	0.00	k	0.219	k
+D+0.60W+H	0.2	k	1.89	k	0.219	k
+D+0.70E+H	0.0	k	0.00	k	0.219	k
+D+0.750Lr+0.750L+0.450W+H	0.2	k	1.42	k	0.219	k
+D+0.750L+0.750S+0.450W+H	0.2	k	1.42	k	0.219	k
+D+0.750L+0.750S+0.5250E+H	0.0	k	0.00	k	0.219	k
+0.60D+0.60W+0.60H	0.2	k	1.89	k	0.131	k
+0.60D+0.70E+0.60H	0.0	k	0.00	k	0.131	k
D Only	0.0	k	0.00	k	0.219	k
Lr Only	0.0	k	0.00	k	0.000	k
L Only	0.0	k	0.00	k	0.000	k
S Only	0.0	k	0.00	k	0.000	k
W Only	0.4	k	3.15	k	0.000	k
E Only	0.0	k	0.00	k	0.000	k
H Only	0.0	k	0.00	k	0.000	k



# Wind Analysis for Low-rise Building, Based on ASCE 7-2010

## INPUT DATA

Exposure category (B, C or D, ASCE 7-10 26.7.3)

Importance factor (ASCE 7-10 Table 1.5-2)

Basic wind speed (ASCE 7-10 26.5.1 or 2012 IBC)

Topographic factor (ASCE 7-10 26.8 & Table 26.8-1)

Building height to eave


Building height to ridge

Building length

Building width

Effective area of components (or Solar Panel area)

C  
 $I_w = 1.00$  for all Category  
 $V = 120$  mph  
 $K_{zt} = 1$  Flat  
 $h_e = 20$  ft  
 $h_r = 20$  ft  
 $L = 100$  ft  
 $B = 50$  ft  
 $A = 140$  ft<sup>2</sup>



## DESIGN SUMMARY

Max horizontal force normal to building length, L, face

Max horizontal force normal to building length, B, face

Max total horizontal torsional load

Max total upward force

= 40.89 kips, SD level (LRFD level), Typ.  
= 21.43 kips  
= 492.60 ft-kips  
= 103.92 kips

## ANALYSIS

### Velocity pressure

$$q_h = 0.00256 K_h K_{zt} K_d V^2 = 28.20 \text{ psf}$$

where:  $q_h$  = velocity pressure at mean roof height, h. (Eq. 28.3-1 page 298 & Eq. 30.3-1 page 316)

$K_h$  = velocity pressure exposure coefficient evaluated at height, h, (Tab. 28.3-1, pg 299)

$K_d$  = wind directionality factor. (Tab. 26.6-1, for building, page 250)

$h$  = mean roof height

= 0.90

= 0.85

= 20.00 ft

< 60 ft, [Satisfactory]

(ASCE 7-10 26.2.1)

< Min (L, B), [Satisfactory]

(ASCE 7-10 26.2.2)

### Design pressures for MWFRS

$$p = q_h [(G C_{pf}) - (G C_{pi})]$$

where:  $p$  = pressure in appropriate zone. (Eq. 28.4-1, page 298).

$p_{min} = 16$  psf (ASCE 7-10 28.4.4)

$G C_{pf}$  = product of gust effect factor and external pressure coefficient, see table below. (Fig. 28.4-1, page 300 & 301)

$G C_{pi}$  = product of gust effect factor and internal pressure coefficient. (Tab. 26.11-1, Enclosed Building, page 258)

= 0.18 or -0.18





$a$  = width of edge strips, Fig 28.4-1, note 9, page 301, MAX[ MIN(0.1B, 0.1L, 0.4h), MIN(0.04B, 0.04L), 3] = 5.00 ft

### Net Pressures (psf), Basic Load Cases

Surface	Roof angle $\theta = 0.00$			Roof angle $\theta = 0.00$		
	$G C_{pf}$	Net Pressure with		$G C_{pf}$	Net Pressure with	
		(+GC <sub>pi</sub> )	(-GC <sub>pi</sub> )		(+GC <sub>pi</sub> )	(-GC <sub>pi</sub> )
1	0.40	6.20	16.36	-0.45	-17.77	-7.61
2	-0.69	-24.53	-14.38	-0.69	-24.53	-14.38
3	-0.37	-15.51	-5.36	-0.37	-15.51	-5.36
4	-0.29	-13.25	-3.10	-0.45	-17.77	-7.61
5				0.40	6.20	16.36
6				-0.29	-13.25	-3.10
1E	0.61	12.13	22.28	-0.48	-18.61	-8.46
2E	-1.07	-35.25	-25.10	-1.07	-35.25	-25.10
3E	-0.53	-20.02	-9.87	-0.53	-20.02	-9.87
4E	-0.43	-17.20	-7.05	-0.48	-18.61	-8.46
5E				0.61	12.13	22.28
6E				-0.43	-17.20	-7.05

### Net Pressures (psf), Torsional Load Cases

Surface	Roof angle $\theta = 0.00$		
	$G C_{pf}$	Net Pressure with	
		(+GC <sub>pi</sub> )	(-GC <sub>pi</sub> )
1T	0.40	1.55	4.09
2T	-0.69	-6.13	-3.60
3T	-0.37	-3.88	-1.34
4T	-0.29	-3.31	-0.78
Surface	Roof angle $\theta = 0.00$		
	$G C_{pf}$	Net Pressure with	
		(+GC <sub>pi</sub> )	(-GC <sub>pi</sub> )
5T	0.40	1.55	4.09
6T	-0.29	-3.31	-0.78



Load Case A (Transverse)

Load Case B (Longitudinal)

Basic Load Cases

Load Case A (Transverse)

Load Case B (Longitudinal)

Torsional Load Cases

**Basic Load Case A (Transverse Direction)**

Surface	Area (ft <sup>2</sup> )	Pressure (k) with	
		(+GC <sub>p1</sub> )	(-GC <sub>p1</sub> )
1	1800	11.17	29.44
2	2250	-55.20	-32.36
3	2250	-34.90	-12.06
4	1800	-23.86	-5.58
1E	200	2.43	4.46
2E	250	-8.81	-6.27
3E	250	-5.01	-2.47
4E	200	-3.44	-1.41
Σ	Horiz.	40.89	40.89
	Vert.	-103.92	-53.16
Min. wind	Horiz.	32.00	32.00
28.4.4	Vert.	-80.00	-80.00

**Basic Load Case B (Longitudinal Direction)**

Surface	Area (ft <sup>2</sup> )	Pressure (k) with	
		(+GC <sub>p1</sub> )	(-GC <sub>p1</sub> )
2	2250	-55.20	-32.36
3	2250	-34.90	-12.06
5	800	4.96	13.09
6	800	-10.60	-2.48
2E	250	-8.81	-6.27
3E	250	-5.01	-2.47
5E	200	2.43	4.46
6E	200	-3.44	-1.41
Σ	Horiz.	21.43	21.43
	Vert.	-91.12	-41.37
Min. wind	Horiz.	16.00	16.00
28.4.4	Vert.	-80.00	-80.00

**Torsional Load Case A (Transverse Direction)**

Surface	Area (ft <sup>2</sup> )	Pressure (k) with		Torsion (ft-k)	
		(+GC <sub>p1</sub> )	(-GC <sub>p1</sub> )	(+GC <sub>p1</sub> )	(-GC <sub>p1</sub> )
1	800	4.96	13.09	112	294
2	1000	-24.53	-14.38	0	0
3	1000	-15.51	-5.36	0	0
4	800	-10.60	-2.48	239	56
1E	200	2.43	4.46	109	201
2E	250	-8.81	-6.27	0	0
3E	250	-5.01	-2.47	0	0
4E	200	-3.44	-1.41	155	63
1T	1000	1.55	4.09	-39	-102
2T	1250	-7.67	-4.49	0	0
3T	1250	-4.85	-1.67	0	0
4T	1000	-3.31	-0.78	-83	-19
Total Horiz. Torsional Load, M <sub>T</sub>				493	493

**Torsional Load Case B (Longitudinal Direction)**

Surface	Area (ft <sup>2</sup> )	Pressure (k) with		Torsion (ft-k)	
		(+GC <sub>p1</sub> )	(-GC <sub>p1</sub> )	(+GC <sub>p1</sub> )	(-GC <sub>p1</sub> )
2	2250	-55.20	-32.36	0	0
3	2250	-34.90	-12.06	0	0
5	300	1.86	4.91	19	49
6	300	-3.98	-0.93	40	9
2E	250	-8.81	-6.27	0	0
3E	250	-5.01	-2.47	0	0
5E	200	2.43	4.46	55	100
6E	200	-3.44	-1.41	77	32
5T	500	0.78	2.04	-10	-26
6T	500	-1.66	-0.39	-21	-5
Total Horiz. Torsional Load, M <sub>T</sub>				160.0	160.0

**Design pressures for components and cladding**


$$p = q_h [(G C_p) - (G C_{pi})]$$

where:  $p$  = pressure on component. (Eq. 30.4-1, pg 318)

$$p_{min} = 16.00 \text{ psf (ASCE 7-10 30.2.2)}$$

$G C_p$  = external pressure coefficient.

see table below. (ASCE 7-10 30.4.2)



Walls



Roof 0 ≤ 7°



Roof 0 > 7°

	Effective Area (ft <sup>2</sup> )	Zone 1		Zone 2		Zone 3		Zone 4		Zone 5	
		GC <sub>p</sub>	-GC <sub>p</sub>	GC <sub>p</sub>	-GC <sub>p</sub>	GC <sub>p</sub>	-GC <sub>p</sub>	GC <sub>p</sub>	-GC <sub>p</sub>	GC <sub>p</sub>	-GC <sub>p</sub>
Comp.	140	0.20	-0.90	0.20	-1.10	0.20	-1.10	0.72	-0.81	0.72	-0.90

(Walls reduced 10 %, Fig. 6-11A note 5.)

Comp. & Cladding Pressure (psf)	Zone 1		Zone 2		Zone 3		Zone 4		Zone 5	
	Positive	Negative	Positive	Negative	Positive	Negative	Positive	Negative	Positive	Negative
	16.00	-30.46	16.00	-36.10	16.00	-36.10	25.32	-27.86	25.32	-30.34

Note: If the effective area is roof Solar Panel area, the only zone 1, 2 , or 3 apply.



Title Block Line 1  
You can change this area  
using the "Settings" menu item  
and then using the "Printing &  
Title Block" selection.  
Title Block Line 6

Project Title:  
Engineer:  
Project Descr:

Project ID:

Printed: 31 AUG 2016, 2:07PM

## Masonry Slender Wall

File = \\dbaa-sv2\projects\16096 Challenger Middle School\Engineering\16096 challenger.ec6

ENERCALC, INC. 1983-2016, Build 6.16.6.7, Ver: 6.16.6.7

Lic. #: KW-06009174

Licensee: DAVID BIXLER AND ASSOCIATES

Description: equivalent cantilevered wall in front of existing wall

### Code References

Calculations per ACI 530-11, IBC 2012, CBC 2013, ASCE 7-10

Load Combinations Used: ASCE 7-10

### General Information

Calculations per ACI 530-11, IBC 2012, CBC 2013, ASCE 7-10

Construction Type: Grouted Hollow Concrete Masonry


F'm	=	1.50 ksi	Nom. Wall Thickness	6 in	Temp Diff across thickness	=	deg F
Fy - Yield	=	60.0 ksi	Actual Thickness	5.625 in	Min Allow Out-of-plane Defl Ratio	=	0
Fr - Rupture	=	61.0 psi	Rebar "d" distance	3.813 in	Minimum Vertical Steel %	=	0.0020
Em = f'm *	=	900.0	Lower Level Rebar				
Max % of ρ bal.	=	0.1455	Bar Size	# 4			
Grout Density	=	140 pcf	Bar Spacing	16.0 in			
Block Weight		Normal Weight					
Wall Weight	=	52.0 psf					

Wall is grouted at rebar cells only

### One-Story Wall Dimensions

A Clear Height	=	4.660 ft
B Parapet height	=	ft

Wall Support Condition Top & Bottom Pinned



### Lateral Loads

Wind Loads:

Full area WIND load 34.0 psf

Seismic Loads:

Wall Weight Seismic Load Input Method:  
Seismic Wall Lateral Load

Direct entry of Lateral Wall Weight  
psf

Fp 1.0 = 0.0 psf

(Applied to full "STRIP Width")

Distributed Lateral Load

D	Lr	L	E	W	Endpoints from Base top bottom
				7.0 k/ft	4.660 3.660 k/ft

Title Block Line 1  
 You can change this area  
 using the "Settings" menu item  
 and then using the "Printing &  
 Title Block" selection.  
 Title Block Line 6

Project Title:  
 Engineer:  
 Project Descr:

Project ID:

Printed: 31 AUG 2016, 2:07PM

## Masonry Slender Wall

File = \\dbaa-sv2\projects\16096 Challenger Middle School\Engineering\16096 challenger ec6

ENERCALC, INC. 1983-2016, Build 6.16.6.7, Ver:6.16.6.7

Lic. #: KW-06009174

Licensee: DAVID BIXLER AND ASSOCIATES

Description: equivalent cantilevered wall in front of existing wall

### DESIGN SUMMARY

### Results reported for "Strip Width" of 12.0 in

Governing Load Combination . . .		Actual Values . . .		Allowable Values . . .	
PASS	Moment Capacity Check +0.90D+W+0.90H	Maximum Bending Stress Ratio =	0.8757		
		Max Mu	2.087 k-ft	Phi * Mn	2.383 k-ft
PASS	Service Deflection Check W Only	Actual Defl. Ratio	0.383	Allowable Defl. Ratio	150
		Max. Deflection	0.1462 in		
PASS	Axial Load Check +1.20D+0.50Lr+0.50L+W+1.60H	Max Pu / Ag	1.135 psi	Max. Allow. Defl.	0.3728 in
		Location	3.806 ft	0.2 * f'm	300.0 psi
PASS	Reinforcing Limit Check	Controlling As/bd	0.003278	As/bd @ 1455 rho bal	0.1455
Maximum Reactions . . . for Load Combination...					
		Top Horizontal	W Only		5.456 k
		Base Horizontal	W Only		0.6151 k
		Vertical Reaction	+D+0.60W+H		0.2423 k

### Design Maximum Combinations - Moments

### Results reported for "Strip Width" = 12 in.

Load Combination	Axial Load		Mcr k-ft	Mu k-ft	Phi	Moment Values		As in <sup>2</sup>	As Ratio	0.6 * rho bal
	Pu k	0.2*f'm*b*t k				Phi Mn k-ft				
	0.000	0.000	0.00	0.00	0.00	0.00	0.000	0.0000	0.0000	
	0.000	0.000	0.00	0.00	0.00	0.00	0.000	0.0000	0.0000	
	0.000	0.000	0.00	0.00	0.00	0.00	0.000	0.0000	0.0000	
	0.000	0.000	0.00	0.00	0.00	0.00	0.000	0.0000	0.0000	
+1.20D+1.60Lr+0.50W+1.60H at 3.73 to 3.88	0.059	16.200	0.28	1.04	0.90	2.39	0.150	0.0033	0.1454	
	0.000	0.000	0.00	0.00	0.00	0.00	0.000	0.0000	0.0000	
+1.20D+1.60S+0.50W+1.60H at 3.73 to 3.88	0.059	16.200	0.28	1.04	0.90	2.39	0.150	0.0033	0.1454	
+1.20D+0.50Lr+0.50L+W+1.60H at 3.73 to 3.88	0.061	16.200	0.28	2.09	0.90	2.39	0.150	0.0033	0.1454	
+1.20D+0.50L+0.50S+W+1.60H at 3.73 to 3.88	0.061	16.200	0.28	2.09	0.90	2.39	0.150	0.0033	0.1454	
	0.000	0.000	0.00	0.00	0.00	0.00	0.000	0.0000	0.0000	
+0.90D+W+0.90H at 3.73 to 3.88	0.047	16.200	0.28	2.09	0.90	2.38	0.150	0.0033	0.1454	
	0.000	0.000	0.00	0.00	0.00	0.00	0.000	0.0000	0.0000	

### Design Maximum Combinations - Deflections

### Results reported for "Strip Width" = 12 in.

Load Combination	Axial Load Pu k	Moment Values		I gross in <sup>4</sup>	Stiffness		Deflections	
		Mcr k-ft	Mactual k-ft		I cracked in <sup>4</sup>	I effective in <sup>4</sup>	Deflection in	Defl. Ratio
	0.000	0.00	0.00	0.00	0.00	0.000	0.000	0.0
	0.000	0.00	0.00	0.00	0.00	0.000	0.000	0.0
	0.000	0.00	0.00	0.00	0.00	0.000	0.000	0.0
	0.000	0.00	0.00	0.00	0.00	0.000	0.000	0.0
	0.000	0.00	0.00	0.00	0.00	0.000	0.000	0.0
	0.000	0.00	0.00	0.00	0.00	0.000	0.000	0.0
+D+0.60W+H at 2.64 to 2.80	0.105	0.28	0.93	154.20	29.17	29.324	0.079	709.1
	0.000	0.00	0.00	0.00	0.00	0.000	0.000	0.0
+D+0.750Lr+0.750L+0.450W+H at 2.64 to 2.80	0.105	0.28	0.70	154.20	29.17	29.572	0.053	1,049.2
+D+0.750L+0.750S+0.450W+H at 2.64 to 2.80	0.105	0.28	0.70	154.20	29.17	29.572	0.053	1,049.2
	0.000	0.00	0.00	0.00	0.00	0.000	0.000	0.0
+0.60D+0.60W+0.60H at 2.64 to 2.80	0.063	0.28	0.93	154.20	29.07	29.221	0.079	707.2
	0.000	0.00	0.00	0.00	0.00	0.000	0.000	0.0
	0.000	0.00	0.00	0.00	0.00	0.000	0.000	0.0
	0.000	0.00	0.00	0.00	0.00	0.000	0.000	0.0
	0.000	0.00	0.00	0.00	0.00	0.000	0.000	0.0
	0.000	0.00	0.00	0.00	0.00	0.000	0.000	0.0

Title Block Line 1  
 You can change this area  
 using the "Settings" menu item  
 and then using the "Printing &  
 Title Block" selection.  
 Title Block Line 6

Project Title:  
 Engineer:  
 Project Descr:

Project ID:

Printed: 31 AUG 2016, 2:07PM

## Masonry Slender Wall

File = \\dbaa-sv2\projects\16096 Challenger Middle School\Engineering\16096 challenger.ec6

ENERCALC, INC. 1983-2016, Build: 6.16.6.7, Ver: 6.16.6.7

Lic. #: KW-06009174

Licensee: DAVID BIXLER AND ASSOCIATES

Description: equivalent cantilevered wall in front of existing wall

### Design Maximum Combinations - Deflections

Results reported for "Strip Width" = 12 in.

Load Combination	Axial Load	Moment Values		I gross	Stiffness		Deflections	
	Pu k	Mcr k-ft	Mactual k-ft		I cracked in <sup>4</sup>	I effective in <sup>4</sup>	Deflection in	Defl. Ratio
W Only at 2.64 to 2.80	0.000	0.00	0.00	0.00	0.00	0.000	0.000	0.0
	0.000	0.28	1.55	154.20	28.91	28.941	0.146	382.6
	0.000	0.00	0.00	0.00	0.00	0.000	0.000	0.0
	0.000	0.00	0.00	0.00	0.00	0.000	0.000	0.0

### Reactions - Vertical & Horizontal

Results reported for "Strip Width" = 12 in.

Load Combination	Base Horizontal		Top Horizontal		Vertical @ Wall Base	
+D+H	0.0	k	0.00	k	0.242	k
+D+L+H	0.0	k	0.00	k	0.242	k
+D+Lr+H	0.0	k	0.00	k	0.242	k
+D+S+H	0.0	k	0.00	k	0.242	k
+D+0.750Lr+0.750L+H	0.0	k	0.00	k	0.242	k
+D+0.750L+0.750S+H	0.0	k	0.00	k	0.242	k
+D+0.60W+H	0.4	k	3.27	k	0.242	k
+D+0.70E+H	0.0	k	0.00	k	0.242	k
+D+0.750Lr+0.750L+0.450W+H	0.3	k	2.46	k	0.242	k
+D+0.750L+0.750S+0.450W+H	0.3	k	2.46	k	0.242	k
+D+0.750L+0.750S+0.5250E+H	0.0	k	0.00	k	0.242	k
+0.60D+0.60W+0.60H	0.4	k	3.27	k	0.145	k
+0.60D+0.70E+0.60H	0.0	k	0.00	k	0.145	k
D Only	0.0	k	0.00	k	0.242	k
Lr Only	0.0	k	0.00	k	0.000	k
L Only	0.0	k	0.00	k	0.000	k
S Only	0.0	k	0.00	k	0.000	k
W Only	0.6	k	5.46	k	0.000	k
E Only	0.0	k	0.00	k	0.000	k
H Only	0.0	k	0.00	k	0.000	k





# DAVID BIXLER & ASSOCIATES

## Structural Engineering

### VISION

August 23, 2016

Our vision is  
to be recognized  
throughout the  
Southwest as the  
leader in structural  
engineering.

Mark Davenport AIA, CEFPI, LEED AP, BD+C  
SPS+ ARCHITECTS LLP  
8681 E. Via de Negocio  
Scottsdale, AZ 85258

**Re: Landmark Middle School  
Glendale, AZ**

### COMMITMENT

Dear Mr. Davenport:

We are committed to  
■ technological  
leadership  
■ innovative and cost-  
effective solutions  
■ quality work  
■ client satisfaction.

Per your request, we visited the Landmark Middle School on several occasions. I also have reviewed the reports from both Speedie and Associates and Gervasio and Associates, which are attached to the end of this report, along with pictures from our site visits during the CMU removal to investigate the reinforcing and typical pictures of the type of cracking along the buildings. We also reviewed the existing plans of the buildings which we have received. The purpose of this report is to review the conditions of the existing buildings along with the reports prepared by other consultants, and to recommend a plan of action going forward on the best course of action to remedy the deficient areas.

The buildings are typically steel and wood framed roofs bearing on CMU exterior walls and concrete spread footings.

### VALUES

Our team delivers  
integrity  
service  
collaboration  
quality  
efficiency

Based on the surface penetrating radar investigations Speedie and Associates performed, the vertical reinforcing appears to be installed for the most part correctly, and based off of their radar findings, there is nothing that is significantly different than what we would expect.

Based on the soils investigations performed by Speedie and Associate, there does not appear to be a specific cause of the masonry distress due to the soils themselves, except the fact that the soil conditions are very moist. The moisture fluctuations in the soils will have a tendency to cause continuous movement in the soils which will induce stresses on the buildings which will sometimes result in cracks of the CMU.





# DAVID BIXLER & ASSOCIATES

## Structural Engineering

There were three reports done by Gervasio and Associates that we have received and reviewed: (1) report dated February 15, 2011 dealing mostly with cracks in the North-East corner of the Gym Building, (2) report dated May 27, 2014 dealing with cracks in the masonry piers at the Administration building, and (3) report dated July 20, 2015 dealing with cracks in the interior and exterior walls, deteriorating concrete piers, corroded metal deck and steel joist bearings in the media center. For the gymnasium cracks, Gervasio maintains that there were three different types of cracks, a stair-stepped crack near the corner, a vertical crack at the change in parapet height and a crack at beam bearing. They indicated that only the crack at the beam bearing was in need of repair and that the others could be caulked to prevent moisture. Gervasio recommended that the crack at beam bearing be modified to allow for thermal movement in the beam. All of the additional investigations that have been performed since then would indicate that they are most likely correct. Since the moisture around the building is currently in the process of getting corrected, I would recommend that instead of just caulking the cracks, I would repoint and repair or replace the block as required to bring it back to its original state. At the vertical crack I would recommend adding the vertical masonry control joint that is missing to prevent future cracking.

Finally, at the beam bearing location, this bearing condition needs to be rebuilt with a neoprene pad below the beam bearing to allow for movement and the CMU below should be rebuilt and grouted properly. In the second report dealing with the vertical cracks in the masonry piers, Gervasio recommended tying the two walls together by doweling and epoxying them and attaching the piers to the building with doweling and epoxying as well. I agree with their recommendations since the moisture issue is being corrected. For the media center for the interior and exterior cracks, Gervasio recommends drying out the crawl space and fixing the broken water line and then repairing the cracks. For the deteriorated concrete piers Gervasio recommends installing new posts besides the beam to support the beam. Since the moisture issues are being corrected, I recommend repairing the concrete piers. This will not change the current load path and will remove the corroded steel in the piers which will continue to deteriorate even with the moisture removed. For the steel joist bearing on wood blocks, Gervasio recommends removing the wood shims and installing dry pack below the joist; I agree with this recommendation.

From our review of the CMU demolition and our cursory review of the buildings in general, we discovered numerous cracking and rusted reinforcing.

From the four holes that were opened up to expose the reinforcing, we found rusted and deteriorated vertical and horizontal reinforcing in each location. The footings in three of the locations appeared to be in good condition and the correct size, but the fourth was tapered from maybe only 8 inches thick to 2 inches thick at the edge.





# DAVID BIXLER & ASSOCIATES

## Structural Engineering

From our visual inspection, we noticed several different types of cracks, and too many to document all of them. They basically fell into two categories:

1. There were several areas where there are shrinkage cracks, most likely due to insufficient or improper locations of masonry control joints, or improperly installed masonry control joints (see photographs 8 and 11 on building 1, photos 4 and 9 on building 2, photo 6 and 15 on building 3 and photo 1 on building 6 and photo 3 on building 7). While these are not structural in nature, they will affect the waterproofing integrity of the building and therefore I recommend that new masonry control joints be installed and for the CMU in these areas to be tuck pointed and repaired or replaced as applicable. There were approximately 10-15 locations throughout the school where this occurred.

2. The remaining photos appear to be related to moisture and the rusting of the reinforcing in the CMU. Since reinforcing when it rusts can grow to over 400% of its original size, it appears that the reinforcing has rusted, expanded and has cracked the CMU. Since the face shell is now delaminated, it causes the CMU to be reduced in size and therefore to be reduced in strength. There is no real way to determine the loss in strength without knowing the exact thickness of the delaminated CMU. This is a very old building that does not comply with the current building codes, and there is reduced strength of the existing wall with the delamination of the face shells. The reduction in strength could easily range from 33%-90%. Therefore, I recommend that the CMU walls be braced immediately until the repairs are complete.

In addition, there is no real way to eliminate moisture from entering into the CMU with the cracks in it and this will continue to make the condition worse. There is no easy or accurate way to determine the extents of the rusting in the CMU without removing the face shells and investigating the reinforcing as we did in those four locations. The repair for these locations would be extremely expensive but would entail removing the CMU and exposing the rusted reinforcing and then removing it and replacing it with new reinforcing, grout and CMU. This would need to be done in an explorative manner where you start at each of the cracks and then you expand outward until you get to undamaged CMU and reinforcing. Therefore, there is no real way to determine the extents but due to the moisture conditions and the amount of cracking that is visible I would not be surprised if 50%-75% of the length of the walls at the grade line are damaged in this manner. The CMU walls should be braced immediately until the repairs are complete. To avoid continued and future damage, the drainage around the buildings should be also corrected. All sprinkler lines should be moved away from the buildings, and all of the grades should be sloped to divert the water away from the buildings.

If the decision is to repair the school, then this should start immediately, and we should brace the CMU walls until the repairs are completed. Without knowing the extent of the damage, it is extremely difficult to determine how the walls will perform as the reinforcing continues to rust and the walls continue to worsen.



# DAVID BIXLER & ASSOCIATES

## Structural Engineering

While it is extremely difficult to provide any budgetary numbers due to the uncertainty of the full scope and amount of damage we estimate the following corresponding to the item numbers above:

1) Temporary bracing of the CMU walls:	\$70,000
2) Installation of masonry control joints and repair of damaged CMU:	\$40,000
3) Repair of the cracked CMU and rusted reinforcing (not including drainage):	\$250,000
4) Gervasio report regarding gym cracks:	\$20,000
5) Gervasio report regarding column cracks:	\$25,000
6) Gervasio report regarding the media center:	\$150,000

Please understand that this report represents a professional opinion based upon the results of our limited observations, and past experience with similar conditions. Our study was strictly limited to visual observations as stated above. This report is not intended to be a complete or comprehensive study of the structure. We have not reviewed, nor have we been asked to review, the capacity of the existing structure per the current code. Our work has been performed in accordance with generally accepted principles and practices of structural engineering.


We cannot be responsible for any future changes in the condition of the structure. No warranty is provided, either expressed or implied.

If there are any additional concerns or questions, please feel free to contact our office. Thank you for the opportunity to assist you on this project.

Sincerely,

*David Bixler*


David Bixler, PE, SE President  
David Bixler & Associates, PLLC



# CMU REMOVAL AND INVESTIGATION PICTURES







① SITE PLAN  
SCALE: 1" = 20'-0"

A100

DATE: 2/28/2011  
JOB NO: 14348  
SHEET:

REVIEWED BY:  
DESIGNED BY:  
PRELIMINARY  
NOT FOR  
CONSTRUCTION

THIS PLAN IS THE PROPERTY OF SPS+ ARCHITECTS LLP. IT IS TO BE USED ONLY FOR THE PROJECT AND SITE SPECIFICALLY IDENTIFIED HEREON. IT IS NOT TO BE REPRODUCED, COPIED, OR TRANSMITTED IN ANY FORM OR BY ANY MEANS, ELECTRONIC OR MECHANICAL, WITHOUT THE WRITTEN PERMISSION OF SPS+ ARCHITECTS LLP.

**LANDMARK MIDDLE SCHOOL**  
GLENDALE ELEMENTARY SCHOOL DISTRICT NO. 40  
5730 WEST MYRTLE AVENUE  
GLENDALE, AZ 85301

SITE PLAN

SPS+ ARCHITECTS LLP  
1100 CHANDLER AVENUE, SUITE 200  
CHANDLER, AZ 85226  
TEL: 480.991.0800  
FAX: 480.991.2123  
www.spsarchitects.com

**SPS+ ARCHITECTS**





**LANDMARK – BLDG. 7 - MARKER #1**



**PICTURE NO. 1**



**PICTURE NO. 2**





**LANDMARK – BLDG. 7 - MARKER #1**



**PICTURE NO. 3**



**PICTURE NO. 4**





**LANDMARK – BLDG. 3 - MARKER #2**



**PICTURE NO. 1**



**PICTURE NO. 2**





**LANDMARK – BLDG. 2 - MARKER #3**



**PICTURE NO. 1**



**PICTURE NO. 2**



**LANDMARK – BLDG. 2 - MARKER #3**



**PICTURE NO. 3**



**LANDMARK – BLDG. 2 - MARKER #3**



**PICTURE NO. 4**





**LANDMARK – BLDG. 1 - MARKER #4**



**PICTURE NO. 1**



**PICTURE NO. 2**



**LANDMARK – BLDG. 1 - MARKER #4**



**PICTURE NO. 3**




**SITE**

**INVESTIGATION**

**PICTURES**







① SITE PLAN  
SCALE: 1" = 30'-0"

REVIEWED BY  
DRAWN BY  
DATE: 11/19/21  
JOB No: 14348  
SHEET  
**A100**

PRELIMINARY  
NOT FOR  
CONSTRUCTION


THIS PLAN IS A PRELIMINARY  
DRAWING AND IS NOT TO BE  
USED FOR CONSTRUCTION  
OR FOR ANY OTHER PURPOSE  
WITHOUT THE WRITTEN  
CONSENT OF SPS+ ARCHITECTS

**LANDMARK MIDDLE SCHOOL**  
GLENDALE ELEMENTARY SCHOOL DISTRICT NO. 40  
5730 WEST MYRTLE AVENUE  
GLENDALE, AZ 85301

SITE PLAN

**SPS+ ARCHITECTS**  
305 ARCHITECT LLP  
305 ARCHITECT LLP  
TEL: 480.971.1000  
FAX: 480.971.1000  
305ARCHITECTS.COM





1 BUILDING B FLOOR PLAN  
SCALE: 1/8" = 1'-0"


**LANDMARK MIDDLE SCHOOL**  
 GLENDALE ELEMENTARY SCHOOL DISTRICT NO. 40  
 5730 WEST MYRTLE AVENUE  
 GLENDALE, AZ 85301  
 BUILDING B FLOOR PLAN

103 N. 44TH AVENUE  
 SCOTTSDALE, AZ 85262  
 TEL. 480.971.0200  
 FAX. 480.971.1243  
 3250 N. 10TH AVENUE  
 SCOTTSDALE, AZ 85262



REVIEWED BY  
 DRAWN BY  
 PRELIMINARY  
 NOT FOR  
 CONSTRUCTION  
 DATE: 2/10/01  
 JOB NO: 1434B  
 SHEET: A201





LANDMARK MIDDLE SCHOOL  
 GLENDALE ELEMENTARY SCHOOL DISTRICT NO. 40  
 5730 WEST MYRTLE AVENUE  
 GLENDALE, AZ 85301

BUILDING C + D FLOOR PLANS

SPS+ ARCHITECTS  
 3501 DOW AVE. SUITE 100  
 GLENDALE, AZ 85301  
 TEL: 480.971.0200  
 FAX: 480.971.0201  
 WWW.SPSARCHITECTS.COM




REVIEWED BY  
 DRAWN BY  
 DATE 7/14/2015  
 JOB No. 1420  
 SHEET  
 A202

PRELIMINARY  
 NOT FOR  
 CONSTRUCTION







LANDMARK MIDDLE SCHOOL  
GLENDALE ELEMENTARY SCHOOL DISTRICT NO. 40  
5730 WEST MYRTLE AVENUE  
GLENDALE, AZ 85301

BUILDING F + G FLOOR PLAN


SPS+ ARCHITECTS  
3525 N. CENTRAL AVENUE, SUITE 100  
PHOENIX, AZ 85018  
TEL: 480.971.1883  
FAX: 480.971.2423  
www.spsarchitects.com

**SPS+**  
ARCHITECTS

REVIEWED BY:  
DRAWN BY:  
DATE: 10/20/18  
JOB NO: 18080  
SHEET: A204

A204





① BUILDING A FLOOR PLAN  
SCALE: 1/8"=1'-0"



SPS+ ARCHITECTS  
SCOTTDALE, AZ 85338  
TEL: 480.971.0800  
FAX: 480.971.2823  
WWW.SPS+ARCHITECTS.COM

**SPS+**  
**ARCHITECTS**

**LANDMARK MIDDLE SCHOOL**  
GLENDALE ELEMENTARY SCHOOL DISTRICT NO. 40  
5730 WEST MYRTLE AVENUE  
GLENDALE, AZ 85301

BUILDING A FLOOR PLAN

THIS DOCUMENT IS A PRELIMINARY  
DESIGN. IT IS NOT TO BE USED FOR  
CONSTRUCTION. ANY CHANGES  
SHOULD BE APPROVED BY THE  
ARCHITECT.


DATE: 07-15-2010  
DRAWN BY: [Signature]  
CHECKED BY: [Signature]

REVIEWED BY:  
DRAWN BY:  
CHECKED BY:  
DATE: 7/15/2010  
JOB NO: 10000  
SHEET: 1

DATE: 7/15/2010  
JOB NO: 10000  
SHEET: 1  
A200







1 BUILDING E FLOOR PLANS  
SCALE: 1/8" = 1'-0"

**LANDMARK MIDDLE SCHOOL**  
 GLENDALE ELEMENTARY SCHOOL DISTRICT NO. 40  
 5730 WEST MYRTLE AVENUE  
 GLENDALE, AZ 85301

BUILDING E FLOOR PLAN

**SPS+ ARCHITECTS**

SPS+ ARCHITECTS LLP  
 5730 WEST MYRTLE AVENUE  
 GLENDALE, AZ 85301  
 TEL: 480.991.0001  
 WWW.SPS+ARCHITECTS.COM


REVIEWED BY:  
 DRAWN BY:  
 Schematic

DATE: 2/24/2015  
 JOB NO: 14043  
 SHEET: 31 (E7)

**A203**



1 BUILDING H FLOOR PLAN  
 SCALE 7/8" = 1'-0"



**LANDMARK MIDDLE SCHOOL**  
 GLENDALE ELEMENTARY SCHOOL DISTRICT NO. 40  
 5730 WEST MYRTLE AVENUE  
 GLENDALE, AZ 85301

BUILDING H FLOOR PLAN

**SPS+ ARCHITECTS**  
 3511 ARCHITECTURE  
 3500 WEST MYRTLE AVENUE  
 GLENDALE, AZ 85301  
 TEL: 480.991.0000  
 FAX: 480.991.0000  
 WWW.SPS-ARCHITECTS.COM

DESIGNED BY  
 DRAWN BY  
 CHECKED BY  
 PRELIMINARY  
 NOT FOR  
 CONSTRUCTION

DATE 2/16/2011  
 JOB NO. 44348  
 SHEET  
**A205**



**LANDMARK – BUILDING 1**



**MARKER NO. 1**



**MARKER NO. 2**



## LANDMARK – BUILDING 1



**MARKER NO. 3**



**MARKER NO. 4**



## LANDMARK – BUILDING 1



**MARKER NO. 5**



**MARKER NO. 6**



**LANDMARK – BUILDING 1**



**MARKER NO. 7**



**MARKER NO. 8**



**LANDMARK – BUILDING 1**



**MARKER NO. 9**



**MARKER NO. 10**

**LANDMARK – BUILDING 1**



**MARKER NO. 11**



## LANDMARK – BUILDING 2



**MARKER NO. 1**



**MARKER NO. 2**

## LANDMARK – BUILDING 2



**MARKER NO. 3**



**MARKER NO. 4**



## LANDMARK – BUILDING 2



**MARKER NO. 5**



**MARKER NO. 6**



**LANDMARK – BUILDING 2**




**MARKER NO. 7**



**MARKER NO. 8**



## LANDMARK – BUILDING 2



**MARKER NO. 9**



**MARKER NO. 10**



**LANDMARK – BUILDING 2**



**MARKER NO. 11**




**MARKER NO. 12**

## LANDMARK – BUILDING 2



**MARKER NO. 13**



**MARKER NO. 14**



**LANDMARK – BUILDING 2**



**MARKER NO. 15**



**MARKER NO. 16**



**LANDMARK – BUILDING 2**



**MARKER NO. 17**



**MARKER NO. 18**



## LANDMARK – BUILDING 3



**MARKER NO. 1**




**MARKER NO. 2**



## LANDMARK – BUILDING 3



MARKER NO. 3




MARKER NO. 4



## LANDMARK – BUILDING 3



**MARKER NO. 5**



**MARKER NO. 6**



### LANDMARK – BUILDING 3



**MARKER NO. 7**



**MARKER NO. 8**



**LANDMARK – BUILDING 3**



**MARKER NO. 9**



**MARKER NO. 10**



**LANDMARK – BUILDING 3**



**MARKER NO. 11**



**MARKER NO. 12**



**LANDMARK – BUILDING 3**



**MARKER NO. 13**



**MARKER NO. 14**

**LANDMARK – BUILDING 3**



**MARKER NO. 15**



## LANDMARK – BUILDING 5



**MARKER NO. 1**



**MARKER NO. 2**



**LANDMARK – BUILDING 5**




**MARKER NO. 3**



**MARKER NO. 4**

**LANDMARK – BUILDING 6**



**MARKER NO. 1**



## LANDMARK – BUILDING 6



**MARKER NO. 2**



**MARKER NO. 3**

**LANDMARK – BUILDING 6**



**MARKER NO. 4**



**LANDMARK – BUILDING 7**



**MARKER NO. 1**



**MARKER NO. 2**

**LANDMARK – BUILDING 7**



**MARKER NO. 3**



**MARKER NO. 4**

# **SURFACE PENETRATING RADAR REPORT**





## GROUND PENETRATING RADAR FIELD REPORT

<b>Project Name:</b> Landmark School-Building Distress - GPR		<b>Project #:</b> 161292TA	<b>Date:</b> 07/11/16
<b>Project Location:</b> 5730 W. Myrtle Ave. - Glendale, AZ.		<b>Time Start:</b> 4:30 AM	<b>Time Stop:</b> 12:30 PM
<b>Client:</b> SPS Arrchitects		<b>Rep:</b> Jennifer Bowen	<b>Doc #:</b> GPR RW434

**WORK ORDERED BY CLIENT:**

**STRUCTURE TYPE:**    Cast in Place ☒    Pre-Cast ☐    Masonry ☒    Other ☐ \_\_\_\_\_

**STRUCTURE ELEMENT:**    Footing ☐    SOG ☒    Wall ☒    Column ☐    Beam ☐    Deck ☐    Other ☐ \_\_\_\_\_

**TARGET INDICATIONS:**    Reinforcing Steel ☒    PT Cables ☐    PVC Conduit ☐    Voids ☐  
    Grouted Cells ☒    Un-Grouted Cells ☒    Other ☐ \_\_\_\_\_

**PICTURES TAKEN:**    Yes ☒    No ☐    **TARGETS MARKED WITH:**    Crayon ☐    Paint ☐    Duct Tape ☒

**SIZE / LOCATION OF AREA(S):**

S&A performed Ground Penetrating Radar (GPR) scanning at the Landmark Elementary School buildings. We utilized the GSSI SIR-3000 Data Acquisition System with model 5100B - 1600 and 2000 MHz antennas. We scanned the CMU walls at locations that were predetermined by the structural engineer to identify and note reinforcement indications. Per our proposal, we scanned each approximate 10' x 10' wall section from the bottom of existing exterior grade. The existing grade was removed about a shovels width along the stem wall at many locations. We utilized colored tape to marked reinforcement indications. The tape markings were terminated at the limits of the scanned sections.

- \* Please see our attached site plan for specific locations.
- \* Observations and measurements were reported separately at each scan location (see scan notes).
- \* A photo of each scanned location was taken for reference (see photo outline-(PO)) .

1. Landmark Elementary School:  
 A. (7) CMU Wall with approximate 10'x10' areas scanned.

GPR SERVICE PROVIDED:	QUANTITY	UNIT PRICE	EXTENSION
Trip Charge	_____	\$ _____	\$ _____
GPR Technician    (3 hr. minimum)	_____	\$ _____	\$ _____
Support Tech        (3 hr. minimum)	_____	\$ _____	\$ _____
3-D Imaging	_____	\$ _____	\$ _____
Additional Services	_____	\$ _____	\$ _____
<b>TOTAL</b>			

**On Account** ☒    **COD – Cash** ☐    **Check** ☐    **#** \_\_\_\_\_    **Credit Card - VISA** ☐    **MC** ☐    **DISCOVER** ☐

The information presented is based upon interpretation of the data collected and is provided solely for illustration and informational purposes. Speedie & Associates is not responsible for any loss or damage caused, arising out of the use of or reliance on the data collected or the report generated. Speedie & Associates hereby disclaims all warranties, expressed or implied with respect to the nature, or quality of the services performed hereunder and except to the extent of its sole gross negligence shall not be liable for any damages as a result of its performance.

**Accepted By:** \_\_\_\_\_    **Technician:** Rodd Whisel



## GROUND PENETRATING RADAR SCAN NOTES

<b>Project Name:</b> Landmark Elementary School Distress - GPR	<b>Project #:</b> 161292TA	<b>Date:</b> 07/11/2016
<b>Project Location:</b> 5730 W. Myrtle Ave., Glendale AZ	<b>Time Start:</b> 4:30AM	<b>Time Stop:</b> 12:30PM
<b>Client:</b> SPS Architects	<b>Rep:</b> Jennifer Bowen	<b>Doc #:</b> GPR RW434-1

**SCAN NUMBER:** 1-Wall

**SCAN LOCATION:** Landmark School, Gym Building, North Wall (PO - Picture 1)

**STRUCTURE TYPE:** Cast in Place ☐ Pre-Cast ☐ Masonry ☒ Other ☐ \_\_\_\_\_

**STRUCTURE ELEMENT:** Footing ☐ SOG ☐ Wall ☒ Column ☐ Beam ☐ Deck ☐ Other ☐ \_\_\_\_\_

**TARGET INDICATIONS:** Reinforcing Steel ☒ PT Cables ☐ PVC Conduit ☐ Voids ☐  
Grouted Cells ☒ Un-Grouted Cells ☐ Other ☐ \_\_\_\_\_

**PICTURES TAKEN:** Yes ☒ No ☐ **TARGETS MARKED WITH:** Crayon ☐ Paint ☐ Tape ☒

**CONCRETE TARGET INDICATION ORIENTATION / APPROXIMATE SPACING AND DEPTH:**

Vertical Target Spacing: \_\_\_\_\_  
Vertical Target Depth: \_\_\_\_\_

Horizontal Target Spacing: \_\_\_\_\_  
Horizontal Target Depth: \_\_\_\_\_

Longitudinal Target Spacing: \_\_\_\_\_  
Longitudinal Target Depth: \_\_\_\_\_

Lateral Target Spacing: \_\_\_\_\_  
Lateral Target Depth: \_\_\_\_\_

**CMU TARGET INDICATION ORIENTATION / APPROXIMATE SPACING AND DEPTH:**

Vertical Target Spacing: Varies, see photo outline pic 1. (grouted)  
Vertical Target Depth: \_\_\_\_\_

Horizontal Target Spacing: Bottom course-stem wall (grouted)  
Horizontal Target Depth: \_\_\_\_\_

Masonry Joint Reinf. Spacing: Approx. 16" OC

**ADDITIONAL NOTES/OBSERVATIONS:**

8"x8"x8" & 4"x8"x16" CMU block  
Stem appears to be at or slightly above existing grade elevation

The information presented is based upon interpretation of the data collected and is provided solely for illustration and informational purposes. Speedie & Associates is not responsible for any loss or damage caused, arising out of the use of or reliance on the data collected or the report generated. Speedie & Associates hereby disclaims all warranties, expressed or implied with respect to the nature, or quality of the services performed hereunder and except to the extent of its sole gross negligence shall not be liable for any damages as a result of its performance.

Accepted By: \_\_\_\_\_ Technician: Rodd Whisel





## GROUND PENETRATING RADAR SCAN NOTES

<b>Project Name:</b> Landmark Elementary School Distress - GPR	<b>Project #:</b> 161292TA	<b>Date:</b> 07/11/2016
<b>Project Location:</b> 5730 W. Myrtle Ave., Glendale AZ	<b>Time Start:</b> 4:30AM	<b>Time Stop:</b> 12:30PM
<b>Client:</b> SPS Architects	<b>Rep:</b> Jennifer Bowen	<b>Doc #:</b> GPR RW434-2

**SCAN NUMBER:** 2-Wall

**SCAN LOCATION:** Landmark School, Kitchen Building, North Wall (PO - Picture 2)

**STRUCTURE TYPE:**    Cast in Place ☐    Pre-Cast ☐    Masonry ☒    Other ☐ \_\_\_\_\_

**STRUCTURE ELEMENT:**    Footing ☐    SOG ☐    Wall ☒    Column ☐    Beam ☐    Deck ☐    Other ☐ \_\_\_\_\_

**TARGET INDICATIONS:**    Reinforcing Steel ☒    PT Cables ☐    PVC Conduit ☐    Voids ☐  
   Grouted Cells ☒    Un-Grouted Cells ☐    Other ☐ \_\_\_\_\_

**PICTURES TAKEN:**    Yes ☒    No ☐    **TARGETS MARKED WITH:**    Crayon ☐    Paint ☐    Tape ☒

**CONCRETE TARGET INDICATION ORIENTATION / APPROXIMATE SPACING AND DEPTH:**

Vertical Target Spacing: \_\_\_\_\_  
Vertical Target Depth: \_\_\_\_\_

Horizontal Target Spacing: \_\_\_\_\_  
Horizontal Target Depth: \_\_\_\_\_

Longitudinal Target Spacing: \_\_\_\_\_  
Longitudinal Target Depth: \_\_\_\_\_

Lateral Target Spacing: \_\_\_\_\_  
Lateral Target Depth: \_\_\_\_\_

**CMU TARGET INDICATION ORIENTATION / APPROXIMATE SPACING AND DEPTH:**

Vertical Target Spacing: 48" on-center, wall corner and at control joint see pic 2. (grouted)  
Vertical Target Depth: \_\_\_\_\_

Horizontal Target Spacing: Bond beam at approx. 9' above FF elev. (grouted)  
Horizontal Target Depth: \_\_\_\_\_

Masonry Joint Reinf. Spacing: Varies. (see picture for specific spacing)

**ADDITIONAL NOTES/OBSERVATIONS:**

8"x8"x8" & 4"x8"x16" CMU block  
Stem wall appears to be at existing grade elevation

The information presented is based upon interpretation of the data collected and is provided solely for illustration and informational purposes. Speedie & Associates is not responsible for any loss or damage caused, arising out of the use of or reliance on the data collected or the report generated. Speedie & Associates hereby disclaims all warranties, expressed or implied with respect to the nature, or quality of the services performed hereunder and except to the extent of its sole gross negligence shall not be liable for any damages as a result of its performance.

Accepted By: \_\_\_\_\_ Technician: Rodd Whisel



## GROUND PENETRATING RADAR SCAN NOTES

<b>Project Name:</b> Landmark Elementary School Distress - GPR	<b>Project #:</b> 161292TA	<b>Date:</b> 07/11/2016
<b>Project Location:</b> 5730 W. Myrtle Ave., Glendale AZ	<b>Time Start:</b> 4:30AM	<b>Time Stop:</b> 12:30PM
<b>Client:</b> SPS Architects	<b>Rep:</b> Jennifer Bowen	<b>Doc #:</b> GPR RW434-3

**SCAN NUMBER:** 3-Wall

**SCAN LOCATION:** Landmark School, Building 'D', South Wall (PO - Picture 3)

**STRUCTURE TYPE:**    Cast in Place ☐    Pre-Cast ☐    Masonry ☒    Other ☐ \_\_\_\_\_

**STRUCTURE ELEMENT:**    Footing ☐    SOG ☐    Wall ☒    Column ☐    Beam ☐    Deck ☐    Other ☐ \_\_\_\_\_

**TARGET INDICATIONS:**    Reinforcing Steel ☒    PT Cables ☐    PVC Conduit ☐    Voids ☐  
   Grouted Cells ☒    Un-Grouted Cells ☐    Other ☐ \_\_\_\_\_

**PICTURES TAKEN:**    Yes ☒    No ☐    **TARGETS MARKED WITH:**    Crayon ☐    Paint ☐    Tape ☒

**CONCRETE TARGET INDICATION ORIENTATION / APPROXIMATE SPACING AND DEPTH:**

Vertical Target Spacing: \_\_\_\_\_  
Vertical Target Depth: \_\_\_\_\_

Horizontal Target Spacing: \_\_\_\_\_  
Horizontal Target Depth: \_\_\_\_\_

Longitudinal Target Spacing: \_\_\_\_\_  
Longitudinal Target Depth: \_\_\_\_\_

Lateral Target Spacing: \_\_\_\_\_  
Lateral Target Depth: \_\_\_\_\_

**CMU TARGET INDICATION ORIENTATION / APPROXIMATE SPACING AND DEPTH:**

Vertical Target Spacing: Varies see pic 3. (grouted)  
Vertical Target Depth: \_\_\_\_\_

Horizontal Target Spacing: Stem wall and bond beam at approx. 9'-8" above FF elev. (grouted)  
Horizontal Target Depth: \_\_\_\_\_

Masonry Joint Reinf. Spacing: Varies (see picture for specific spacing)

**ADDITIONAL NOTES/OBSERVATIONS:**

8"x8"x8" & 4"x8"x16" & 8"x8"x16" CMU block  
Stem appears to be at or slightly above existing grade with one 8"x8"x16" course buried below it

The information presented is based upon interpretation of the data collected and is provided solely for illustration and informational purposes. Speedie & Associates is not responsible for any loss or damage caused, arising out of the use of or reliance on the data collected or the report generated. Speedie & Associates hereby disclaims all warranties, expressed or implied with respect to the nature, or quality of the services performed hereunder and except to the extent of its sole gross negligence shall not be liable for any damages as a result of its performance.

Accepted By: \_\_\_\_\_ Technician: Rodd Whisel





## GROUND PENETRATING RADAR SCAN NOTES

<b>Project Name:</b> Landmark Elementary School Distress - GPR	<b>Project #:</b> 161292TA	<b>Date:</b> 07/11/2016
<b>Project Location:</b> 5730 W. Myrtle Ave., Glendale AZ	<b>Time Start:</b> 4:30AM	<b>Time Stop:</b> 12:30PM
<b>Client:</b> SPS Architects	<b>Rep:</b> Jennifer Bowen	<b>Doc #:</b> GPR RW434-4

**SCAN NUMBER:** 4-Wall

**SCAN LOCATION:** Landmark School, Building 'C', East Wall (PO - Picture 4)

**STRUCTURE TYPE:**    Cast in Place ☐    Pre-Cast ☐    Masonry ☒    Other ☐ \_\_\_\_\_

**STRUCTURE ELEMENT:**    Footing ☐    SOG ☐    Wall ☒    Column ☐    Beam ☐    Deck ☐    Other ☐ \_\_\_\_\_

**TARGET INDICATIONS:**    Reinforcing Steel ☒    PT Cables ☐    PVC Conduit ☐    Voids ☐  
   Grouted Cells ☒    Un-Grouted Cells ☐    Other ☐ \_\_\_\_\_

**PICTURES TAKEN:**    Yes ☒    No ☐    **TARGETS MARKED WITH:**    Crayon ☐    Paint ☐    Tape ☒

**CONCRETE TARGET INDICATION ORIENTATION / APPROXIMATE SPACING AND DEPTH:**

Vertical Target Spacing: \_\_\_\_\_  
Vertical Target Depth: \_\_\_\_\_

Horizontal Target Spacing: \_\_\_\_\_  
Horizontal Target Depth: \_\_\_\_\_

Longitudinal Target Spacing: \_\_\_\_\_  
Longitudinal Target Depth: \_\_\_\_\_

Lateral Target Spacing: \_\_\_\_\_  
Lateral Target Depth: \_\_\_\_\_

**CMU TARGET INDICATION ORIENTATION / APPROXIMATE SPACING AND DEPTH:**

Vertical Target Spacing: Varies at approx. 56", 40", 48", see pic 3. (grouted)  
Vertical Target Depth: \_\_\_\_\_

Horizontal Target Spacing: Stem wall and bond beam at approx. 9'-4" above FF elev. (grouted)  
Horizontal Target Depth: \_\_\_\_\_

Masonry Joint Reinf. Spacing: Varies (see picture for specific spacing)

**ADDITIONAL NOTES/OBSERVATIONS:**

8"x8"x8" & 4"x8"x16" & 8"x8"x16" CMU block  
Stem appears to be at or above existing grade with one 8"x8"x16" course buried below

The information presented is based upon interpretation of the data collected and is provided solely for illustration and informational purposes. Speedie & Associates is not responsible for any loss or damage caused, arising out of the use of or reliance on the data collected or the report generated. Speedie & Associates hereby disclaims all warranties, expressed or implied with respect to the nature, or quality of the services performed hereunder and except to the extent of its sole gross negligence shall not be liable for any damages as a result of its performance.

Accepted By: \_\_\_\_\_ Technician: Rodd Whisel



## GROUND PENETRATING RADAR SCAN NOTES

<b>Project Name:</b> Landmark Elementary School Distress - GPR	<b>Project #:</b> 161292TA	<b>Date:</b> 07/11/2016
<b>Project Location:</b> 5730 W. Myrtle Ave., Glendale AZ	<b>Time Start:</b> 4:30AM	<b>Time Stop:</b> 12:30PM
<b>Client:</b> SPS Architects	<b>Rep:</b> Jennifer Bowen	<b>Doc #:</b> GPR RW434-5

**SCAN NUMBER:** 5-Wall

**SCAN LOCATION:** Landmark School, Building 'B', East Wall (PO - Picture 5)

**STRUCTURE TYPE:** Cast in Place ☐ Pre-Cast ☐ Masonry ☒ Other ☐ \_\_\_\_\_

**STRUCTURE ELEMENT:** Footing ☐ SOG ☐ Wall ☒ Column ☐ Beam ☐ Deck ☐ Other ☐ \_\_\_\_\_

**TARGET INDICATIONS:** Reinforcing Steel ☒ PT Cables ☐ PVC Conduit ☐ Voids ☐  
Grouted Cells ☒ Un-Grouted Cells ☐ Other ☐ \_\_\_\_\_

**PICTURES TAKEN:** Yes ☒ No ☐ **TARGETS MARKED WITH:** Crayon ☐ Paint ☐ Tape ☒

**CONCRETE TARGET INDICATION ORIENTATION / APPROXIMATE SPACING AND DEPTH:**

Vertical Target Spacing: \_\_\_\_\_  
Vertical Target Depth: \_\_\_\_\_

Horizontal Target Spacing: \_\_\_\_\_  
Horizontal Target Depth: \_\_\_\_\_

Longitudinal Target Spacing: \_\_\_\_\_  
Longitudinal Target Depth: \_\_\_\_\_

Lateral Target Spacing: \_\_\_\_\_  
Lateral Target Depth: \_\_\_\_\_

**CMU TARGET INDICATION ORIENTATION / APPROXIMATE SPACING AND DEPTH:**

Vertical Target Spacing: At corner and 40" OC (grouted)  
Vertical Target Depth: \_\_\_\_\_

Horizontal Target Spacing: Stem wall and bond beam at approx. 9'-8" above existing grade elev. (grouted)  
Horizontal Target Depth: \_\_\_\_\_

Masonry Joint Reinf. Spacing: 16" OC

**ADDITIONAL NOTES/OBSERVATIONS:**

8"x8"x8" & 4"x8"x16" & 8"x8"x16" CMU block  
Stem appears to be above existing grade with one 8"x8"x16" course buried below it

The information presented is based upon interpretation of the data collected and is provided solely for illustration and informational purposes. Speedie & Associates is not responsible for any loss or damage caused, arising out of the use of or reliance on the data collected or the report generated. Speedie & Associates hereby disclaims all warranties, expressed or implied with respect to the nature, or quality of the services performed hereunder and except to the extent of its sole gross negligence shall not be liable for any damages as a result of its performance.

Accepted By: \_\_\_\_\_ Technician: Rodd Whisel





## GROUND PENETRATING RADAR SCAN NOTES

<b>Project Name:</b> Landmark Elementary School Distress - GPR	<b>Project #:</b> 161292TA	<b>Date:</b> 07/11/2016
<b>Project Location:</b> 5730 W. Myrtle Ave., Glendale AZ	<b>Time Start:</b> 4:30AM	<b>Time Stop:</b> 12:30PM
<b>Client:</b> SPS Architects	<b>Rep:</b> Jennifer Bowen	<b>Doc #:</b> GPR RW434-6

**SCAN NUMBER:** 6-Wall

**SCAN LOCATION:** Landmark School, Building 'B', Student Services, North Wall (PO - Picture 6)

**STRUCTURE TYPE:**    Cast in Place ☐    Pre-Cast ☐    Masonry ☒    Other ☐ \_\_\_\_\_

**STRUCTURE ELEMENT:**    Footing ☐    SOG ☐    Wall ☒    Column ☐    Beam ☐    Deck ☐    Other ☐ \_\_\_\_\_

**TARGET INDICATIONS:**    Reinforcing Steel ☒    PT Cables ☐    PVC Conduit ☐    Voids ☐  
   Grouted Cells ☒    Un-Grouted Cells ☐    Other ☐ \_\_\_\_\_

**PICTURES TAKEN:**    Yes ☒    No ☐    **TARGETS MARKED WITH:**    Crayon ☐    Paint ☐    Tape ☒

**CONCRETE TARGET INDICATION ORIENTATION / APPROXIMATE SPACING AND DEPTH:**

Vertical Target Spacing: \_\_\_\_\_  
Vertical Target Depth: \_\_\_\_\_

Horizontal Target Spacing: \_\_\_\_\_  
Horizontal Target Depth: \_\_\_\_\_

Longitudinal Target Spacing: \_\_\_\_\_  
Longitudinal Target Depth: \_\_\_\_\_

Lateral Target Spacing: \_\_\_\_\_  
Lateral Target Depth: \_\_\_\_\_

**CMU TARGET INDICATION ORIENTATION / APPROXIMATE SPACING AND DEPTH:**

Vertical Target Spacing: Varies see pic 6 (grouted)  
Vertical Target Depth: \_\_\_\_\_

Horizontal Target Spacing: Stem wall and bond beam at approx. 9' above FF elev. (grouted)  
Horizontal Target Depth: \_\_\_\_\_

Masonry Joint Reinf. Spacing: Varies see pic 6

**ADDITIONAL NOTES/OBSERVATIONS:**

8"x8"x8" & 4"x8"x16" & 8"x8"x16" CMU block  
Stem appears to be at or slightly above existing grade with one 8"x8"x16" course below

The information presented is based upon interpretation of the data collected and is provided solely for illustration and informational purposes. Speedie & Associates is not responsible for any loss or damage caused, arising out of the use of or reliance on the data collected or the report generated. Speedie & Associates hereby disclaims all warranties, expressed or implied with respect to the nature, or quality of the services performed hereunder and except to the extent of its sole gross negligence shall not be liable for any damages as a result of its performance.

Accepted By: \_\_\_\_\_ Technician: Rodd Whisel



## GROUND PENETRATING RADAR SCAN NOTES

<b>Project Name:</b> Landmark Elementary School Distress - GPR	<b>Project #:</b> 161292TA	<b>Date:</b> 07/11/2016
<b>Project Location:</b> 5730 W. Myrtle Ave., Glendale AZ	<b>Time Start:</b> 4:30AM	<b>Time Stop:</b> 12:30PM
<b>Client:</b> SPS Architects	<b>Rep:</b> Jennifer Bowen	<b>Doc #:</b> GPR RW434-7

**SCAN NUMBER:** 7-Wall

**SCAN LOCATION:** Landmark School, Building 'H', PD Room, North Wall (PO - Picture 7)

**STRUCTURE TYPE:** Cast in Place ☐ Pre-Cast ☐ Masonry ☒ Other ☐ \_\_\_\_\_

**STRUCTURE ELEMENT:** Footing ☐ SOG ☐ Wall ☒ Column ☐ Beam ☐ Deck ☐ Other ☐ \_\_\_\_\_

**TARGET INDICATIONS:** Reinforcing Steel ☒ PT Cables ☐ PVC Conduit ☐ Voids ☐  
Grouted Cells ☒ Un-Grouted Cells ☐ Other ☐ \_\_\_\_\_

**PICTURES TAKEN:** Yes ☒ No ☐ **TARGETS MARKED WITH:** Crayon ☐ Paint ☐ Tape ☒

**CONCRETE TARGET INDICATION ORIENTATION / APPROXIMATE SPACING AND DEPTH:**

Vertical Target Spacing: \_\_\_\_\_  
Vertical Target Depth: \_\_\_\_\_

Horizontal Target Spacing: \_\_\_\_\_  
Horizontal Target Depth: \_\_\_\_\_

Longitudinal Target Spacing: \_\_\_\_\_  
Longitudinal Target Depth: \_\_\_\_\_

Lateral Target Spacing: \_\_\_\_\_  
Lateral Target Depth: \_\_\_\_\_

**CMU TARGET INDICATION ORIENTATION / APPROXIMATE SPACING AND DEPTH:**

Vertical Target Spacing: Varies see pic 7 (grouted)  
Vertical Target Depth: \_\_\_\_\_

Horizontal Target Spacing: Stem wall and bond beam at approx. 8'-4" above FF elev. (grouted)  
Horizontal Target Depth: \_\_\_\_\_

Masonry Joint Reinf. Spacing: Varies see pic 7

**ADDITIONAL NOTES/OBSERVATIONS:**

8"x8"x8" & 4"x8"x16" & CMU block  
Stem appears to be at or slightly above existing grade

The information presented is based upon interpretation of the data collected and is provided solely for illustration and informational purposes. Speedie & Associates is not responsible for any loss or damage caused, arising out of the use of or reliance on the data collected or the report generated. Speedie & Associates hereby disclaims all warranties, expressed or implied with respect to the nature, or quality of the services performed hereunder and except to the extent of its sole gross negligence shall not be liable for any damages as a result of its performance.

Accepted By: \_\_\_\_\_ Technician: Rodd Whisel





## GROUND PENETRATING RADAR SCAN NOTES

<b>Project Name:</b> Mensendick/Jack Elementary School Distress - GPR		<b>Project #:</b> 161288TA	<b>Date:</b> 07/07/2016
<b>Project Location:</b> 535 N. 67th Ave., Glendale AZ		<b>Time Start:</b> 4:30AM	<b>Time Stop:</b> 2:30PM
<b>Client:</b> SPS Architects		<b>Rep:</b> Jennifer Bowen	<b>Doc #:</b> GPR

**SCAN NUMBER:** \_\_\_\_\_

**SCAN LOCATION:** \_\_\_\_\_

**STRUCTURE TYPE:**    Cast in Place ☐    Pre-Cast ☐    Masonry ☐    Other ☐ \_\_\_\_\_

**STRUCTURE ELEMENT:**    Footing ☐    SOG ☐    Wall ☐    Column ☐    Beam ☐    Deck ☐    Other ☐ \_\_\_\_\_

**TARGET INDICATIONS:**    Reinforcing Steel ☐    PT Cables ☐    PVC Conduit ☐    Voids ☐  
   Grouted Cells ☐    Un-Grouted Cells ☐    Other ☐ \_\_\_\_\_

**PICTURES TAKEN:**    Yes ☐    No ☐    **TARGETS MARKED WITH:**    Crayon ☐    Paint ☐    Tape ☐

**CONCRETE TARGET INDICATION ORIENTATION / APPROXIMATE SPACING AND DEPTH:**

Vertical Target Spacing: \_\_\_\_\_  
Vertical Target Depth: \_\_\_\_\_

Horizontal Target Spacing: \_\_\_\_\_  
Horizontal Target Depth: \_\_\_\_\_

Longitudinal Target Spacing: \_\_\_\_\_  
Longitudinal Target Depth: \_\_\_\_\_

Lateral Target Spacing: \_\_\_\_\_  
Lateral Target Depth: \_\_\_\_\_

**CMU TARGET INDICATION ORIENTATION / APPROXIMATE SPACING AND DEPTH:**

Vertical Target Spacing: \_\_\_\_\_  
Vertical Target Depth: \_\_\_\_\_

Horizontal Target Spacing: \_\_\_\_\_  
Horizontal Target Depth: \_\_\_\_\_

Masonry Joint Reinf. Spacing: \_\_\_\_\_

**ADDITIONAL NOTES/OBSERVATIONS:**


  
  
  
  
  
  
  
  
  
  

The information presented is based upon interpretation of the data collected and is provided solely for illustration and informational purposes. Speedie & Associates is not responsible for any loss or damage caused, arising out of the use of or reliance on the data collected or the report generated. Speedie & Associates hereby disclaims all warranties, expressed or implied with respect to the nature, or quality of the services performed hereunder and except to the extent of its sole gross negligence shall not be liable for any damages as a result of its performance.

Accepted By: \_\_\_\_\_ Technician: Rodd Whisel







▲ - APPROXIMATE GPR SCAN LOCATIONS (CMU WALL)



# G.P.R. SCAN LOCATION PLAN

LANDMARK SCHOOL BUILDING DISTRESS  
5730 W. MYRTLE AVENUE  
GLENDALE, ARIZONA

**SPEEDIE  
AND ASSOCIATES**  
GEOTECHNICAL/ENVIRONMENTAL/MATERIALS ENGINEERS  
3331 E. WOOD BL.  
PHOENIX, ARIZONA 85040  
(602) 977-4341

DR: TSW	REV:	CHK:	DATE: 07/06/16	PROJECT NO. 161292TA
---------	------	------	----------------	----------------------











**Project Address: 5730 W. Myrtle Ave. - Glendale, AZ.  
Photo Outline**

Project No.:161292TA / GPR RW434

Date: July 11, 2016




	
<p>No. 1</p>	<p>No. 2</p>
	
<p>No. 3</p>	<p>No. 4</p>

**Project Name: Landmark School-Building Distress - GPR**

**Project Address: 5730 W. Myrtle Ave. - Glendale, AZ.  
Photo Outline**

Project No.:161292TA / GPR RW434

Date: July 11, 2016

	
<p>No. 5 Scan 5 Wall: Bldg. B Courtyard, E. Wall. White tape-vert. &amp; horiz. reinf (grouted). Green tape-joint reinf.</p>	<p>No. 6 Scan 6 Wall: Bldg. B Student Services, N. Wall. White tape-vert. &amp; horiz. reinf (grouted). Green tape-joint reinf.</p>
	
<p>No. 7 Scan 7 Wall: Bldg. H, PD Room, N. Wall. White-vert. &amp; horiz. reinf (grouted), Green-joint reinf.</p>	

**Project Name: Landmark School-Building Distress - GPR**

# SOILS INVESTIGATION REPORT





August 9, 2016

Jennifer Bowen, AIA  
SPS+ Partners Architects LLP  
8681 E. Via de Negocio  
Scottsdale, AZ 85258

**RE: Project No. 161301SA  
Landmark School Building Distress  
5730 W. Myrtle Avenue  
Glendale, AZ  
Findings & Test Results**

Dear Ms. Bowen:

This letter presents the findings of our visual site assessment, limited subsurface investigation and our opinions on the possible cause(s) for the stair step cracking of the masonry walls, separation of doorframes from masonry walls and evidence of slab movement of the interior of the buildings resulting in slab cracks.

On July 11, 2016, representatives from Speedie & Associates were at the site to conduct a limited soil investigation, as outlined in our proposal number 56067s. The investigation was broken into three tasks. The first task consisted of coring the interior slab of the buildings at two (2) locations and obtaining soil samples. The second task was to hand auger up to fifteen (15) exterior locations and obtaining soil samples. The third task was to drill three (3) deep structural borings to depths of 20 feet below existing ground surface and obtaining soil samples.

The results of the sampling and individual logs of each core, boring and test pit location and laboratory data are attached to this report. The approximate locations of each are located on the attached Soil Boring Location Plan.

#### **Interior Testing**

Two cores were selected at the interior of two separate buildings spread throughout the school campus. Each core was made along the interior walls. Coring consisted of hand augering and sampling of soils from 0.8 to 3 feet below grade. Coring C-1 encountered auger refusal on gravel at a depth of 10 inches below existing grade.

The concrete building slab thicknesses were ranged from 3.5 to 4.0 inches underlain by 4.0 to 4.5 inches of aggregate base course. The subgrade soils consisted of lean clay with sand and subordinate

amounts of gravel. Based on visual and tactile observation, the soils were in a 'dry to moist' to 'moist' state at the time of investigation. An undisturbed ring sample was taken of the subgrade soils of core C-2 at a depth of 1.5 feet below the existing surface. The sample was obtained by driving a ring sampler with a 30-lb post hammer. It took 16 blows to drive the hammer 12 inches.

### **Exterior Testing**

Fifteen hand auger borings were selected throughout the school campus in the landscaped areas closest to the buildings. The majority of the landscaping was consistent with irrigated grass and large trees. Each boring was hand augured to a depth of approximately three feet below existing grade and soil a sample was obtained at each location.

An undisturbed ring sample was taken of the subgrade soils at borings B-1 and B-11 at a depth of 1.0 foot below the existing surface. The samples were obtained by driving a ring sampler with a 30-lb post hammer. It took 22 blows for boring B-1 and 16 blows for boring B-11 to drive the hammer 12 inches. Subgrade soils consisted predominately of lean clay with sand, silty clayey sand, silty sand and clayey sand with subordinate amounts of gravel. Based on visual and tactile observation, the soils were in a 'dry' to 'moist' state at the time of investigation.

### **Drill Rig Borings**

As part of this analysis, three locations of the campus were selected to drill structural borings to a depth of 20 feet below existing grade. Boring B-17 was not accessible by the drill rig and Boring B-18 was relocated to the west side along 58<sup>th</sup> Avenue. An undisturbed ring sample was taken at a depth of 1 foot and 5 feet below existing grades for each boring. A Standard Penetration Resistance Test (SPT) was then taken at five foot intervals thereafter. The SPT values ranged from 7 to 50+ blows per foot. It is noted that loose/firm soils were encountered at boring B-16 at a depth of 10 feet and at boring B-18 at a depth of 1 to 10 feet. The subgrade soils consisted of sandy lean clay, clayey sand and silty clayey sand with subordinate amounts of gravel and weak calcareous cementation. Based on visual and tactile observation, the soils ranged from a 'dry' to 'moist' state at the time of investigation.

### **General Subsurface Conditions**

The native subsoils consisted primarily of clayey sand, sandy lean clay and lean clay. Subordinate amounts of gravel and weak calcareous cementation were also noted throughout the profile. No groundwater was encountered during this investigation. Based on visual and tactile observation, the upper soils ranged from a 'dry' to 'moist' state at the time of investigation. It is noted that structural fill was encountered in borings B-6, B-8, B-9, B-14, B-15 and B-16 at depths of 1.0 to 2.5 feet below existing grade.

Laboratory testing indicates in-situ dry densities of the upper soils ranged from 74 to 112 pcf and water contents from 3.7 to 33.1 percent at the time of investigation. Liquid limits ranged from 30 to 46 percent with plasticity indices at 7 to 22 percent. The upper clayey soils exhibit volume increase (swell) due to wetting of 5.4 percent when compacted to moisture and density levels normally expected during construction. Undisturbed samples displayed minor to moderate (1.5 to 2.5%) compression due to incremental loading and moderate to moderate (1 to 3%) additional compression due to inundation under a maximum confining load of 3,200 psf.

### Conclusions

At this time no obvious single cause was observed to cause the distress in the building. Based on the limited investigation, our laboratory testing and field observation, it is our opinion that the distress may be related to a combination of water induced settlement, or shrinkage of the soil and possibly minor amounts of slab heave or swell as a result of moisture fluctuations in the supporting soils. These moisture fluctuations are a result of the constant irrigation of the grassy areas surrounding the buildings. Based on the soil classification and observations, the soils on the site are moisture sensitive and will be prone to volume change (both shrinkage and swelling) as a result of moisture changes (drying and wetting).

Most all soils related issues are in direct relationship to moisture change in the supporting soils. This can come from results of wet utility leaks or breaks, over irrigation, or poor drainage. Based on the samples obtained, the amounts of moisture in the majority of the soils were around the optimum moisture percentage.

At this time our scope was only to conduct the field sampling and laboratory testing and provide the data obtained. If there are any questions, or wish to discuss the results please feel free to call.

Respectfully Submitted,  
SPEEDIE & ASSOCIATES, INC.




Ray C. Markley Jr., E.I.T.



Keith R. Gravel, P.E.



Attachments:



- ◆ - APPROXIMATE HAND-AUGER BORING LOCATIONS
- ✕ - APPROXIMATE FLOOR SLAB CORE LOCATIONS
- ◎ - APPROXIMATE SOIL BORING LOCATIONS (20' DEPTH)



## SOIL BORING LOCATION PLAN

LANDMARK SCHOOL BUILDING DISTRESS

5730 W. MYRTLE AVENUE

GLENDALE, ARIZONA

**SPEEDIE  
AND ASSOCIATES**  
GEOLOGICAL/ENVIRONMENTAL/INFRASTRUCTURE ENGINEERS  
501 E. 1000 ST.  
PHOENIX, ARIZONA 85006 (602) 997-1234

PROJECT NO. 1612125A


DATE: 07/06/16

CHK.

REV.

DR. TSW





Boring Date: 7-11-16  
 Field Engineer/Technician: T. Wilmsen  
 Driller: R. Markley  
 Contractor: Speedie & Assoc.

Water Level		
Depth	Hour	Date
Free Water was Not Encountered		

NT = Not Tested

<b>SPEEDIE AND ASSOCIATES</b>
Log of Test Boring Number: <b>B- 1</b>
<b>Landmark School-Building Distress</b>  <b>5730 West Myrtle Avenue</b>  <b>Glendale, Arizona</b>  Project No.: <b>161212SA</b>

SPEEDIE 161212SA.GPJ GENGEO.GDT 7/28/16

Graphic  
Log

## Visual Classification

Brown LEAN CLAY with SAND (CL-Moist)  
with Little Gravel

Penetration  
Resistance  
Blows  
per Foot

0 25 50

### 3.0

AS-1

### 3.0

26.9

NT

## End of Boring

### Water Level

Depth	Hour	Date
<b>Free Water was Not Encountered</b>		

NT = Not Tested

# SPEEDIE AND ASSOCIATES

Log of Test Boring Number: B-2

## Landmark School-Building Distress

**5730 West Myrtle Avenue**

## Glendale, Arizona

**Project No.: 161212SA**

**SPEEDIE 161212SA.GPJ GENGEO.GDT 72646**

Depth (feet)	Graphic Log	<b>Rig Type:</b> Hand Auger <b>Boring Type:</b> Hollow Stem Auger <b>Surface Elevation:</b> N/A					
		Visual Classification	Sample Number	Depth of Sample	Natural Water Content (%)	In-place Dry Density (P.C.F.)	Penetration Resistance Blows per Foot
0		Brown <u>LEAN CLAY</u> with <u>SAND</u> (CL-Moist) with Trace Gravel					
5							
		End of Boring	3.0	AS-1	3.0	26.2	NT

Boring Date: 7-11-16  
 Field Engineer/Technician: T. Wilmsen  
 Driller: R. Markley  
 Contractor: Speedie & Assoc.

Water Level		
Depth	Hour	Date
Free Water was Not Encountered		

NT = Not Tested

<b>SPEEDIE AND ASSOCIATES</b>
Log of Test Boring Number: <b>B- 3</b>
<b>Landmark School-Building Distress</b>  <b>5730 West Myrtle Avenue</b>  <b>Glendale, Arizona</b>  <b>Project No.: 161212SA</b>

SPEEDIE 161212SA.GPJ GENGEO.GDT 7/28/16

Depth (feet)	Graphic Log	<b>Rig Type:</b> Hand Auger <b>Boring Type:</b> Hollow Stem Auger <b>Surface Elevation:</b> N/A	Sample Number	Depth of Sample	Natural Water Content (%)	In-place Dry Density (P.C.F.)	Penetration Resistance Blows per Foot
0		Visual Classification					
		Brown <u>LEAN CLAY</u> with <u>SAND</u> (CL-Dry) with Trace Gravel					
3.0		End of Boring	AS-1	3.0	7.5	NT	
5							

Boring Date: 7-11-16  
 Field Engineer/Technician: T. Wilmsen  
 Driller: R. Markley  
 Contractor: Speedie & Assoc.


Water Level		
Depth	Hour	Date
Free Water was Not Encountered		

NT = Not Tested

<b>SPEEDIE AND ASSOCIATES</b>
Log of Test Boring Number: <b>B-4</b>
<b>Landmark School-Building Distress</b>  <b>5730 West Myrtle Avenue</b>  <b>Glendale, Arizona</b>  <b>Project No.: 161212SA</b>

SPEEDIE 161212SA.GPJ GENGEO.GDT 7/26/16




Depth (feet)	Graphic Log	Rig Type: Hand Auger Boring Type: Hollow Stem Auger Surface Elevation: N/A	Visual Classification	Sample Number	Depth of Sample	Natural Water Content (%)	In-place Dry Density (P.C.F.)	Penetration Resistance Blows per Foot
0		Brown <u>LEAN CLAY</u> with <u>SAND</u> (CL-Moist) with Trace Gravel						
		End of Boring		AS-1	3.0	17.3	NT	
5								

Boring Date: 7-11-16  
 Field Engineer/Technician: T. Wilmsen  
 Driller: R. Markley  
 Contractor: Speedie & Assoc.

Water Level		
Depth	Hour	Date
Free Water was Not Encountered		

NT = Not Tested



Log of Test Boring Number: **B- 5**

Landmark School-Building Distress  
 5730 West Myrtle Avenue  
 Glendale, Arizona  
 Project No.: 161212SA

SPEEDIE 161212SA.GPJ GENGEO.GDT 7/26/16

Depth (feet)	Graphic Log	Rig Type: Hand Auger Boring Type: Hollow Stem Auger Surface Elevation: N/A	Sample Number	Depth of Sample	Natural Water Content (%)	In-place Dry Density (P.C.F.)	Penetration Resistance Blows per Foot
0		Visual Classification					
		FILL: Brown <u>SILTY, CLAYEY SAND</u> (SC/SM-Dry) with Some Gravel					
		Auger Refusal on Gravel	AS-1	2.0	3.7	NT	
5							

Boring Date: 7-11-16  
 Field Engineer/Technician: T. Wilmsen  
 Driller: R. Markley  
 Contractor: Speedie & Assoc.

Water Level		
Depth	Hour	Date
Free Water was Not Encountered		

NT = Not Tested

<b>SPEEDIE AND ASSOCIATES</b>
Log of Test Boring Number: B-6
Landmark School-Building Distress  5730 West Myrtle Avenue  Glendale, Arizona  Project No.: 161212SA

\_SPEEDIE 161212SA.GPJ GENGEO.GDT 8/9/16

Graphic  
Log

Rig Type:	Hand Auger
Boring Type:	Hollow Stem Auger
Surface Elevation:	N/A

## Visual Classification

**Brown LEAN CLAY with SAND (CL-Dry to Moist) with Trace Gravel**

Sample Number

Depth  
of  
Sample

Natural Water Content (%)
---------------------------

**In-place  
Dry Density  
(P.C.F.)**

Penetration  
Resistance  
Blows  
per Foot

0 25 50

3.0

**AS-1**

3.0

## 10.4

**NT**

## End of Boring

5-

**Boring Date:** 7-11-16  
**Field Engineer/Technician:** T. Wilmsen  
**Driller:** R. Markley  
**Contractor:** Speedie & Assoc.

Water Level		
Depth	Hour	Date
<i><b>Free Water was Not Encountered</b></i>		

**NT = Not Tested**

# SPEEDIE AND ASSOCIATES

Log of Test Boring Number: **B-7**


### Landmark School-Building Distress

**5730 West Myrtle Avenue**

## Glendale, Arizona

**Project No.: 161212SA**

SPEEDIE 161212SA.GPJ GENGED.GDT 172676



Boring Date: 7-11-16  
 Field Engineer/Technician: T. Wilmsen  
 Driller: R. Markley  
 Contractor: Speedie & Assoc.


Water Level		
Depth	Hour	Date
Free Water was Not Encountered		

NT = Not Tested

<b>SPEEDIE AND ASSOCIATES</b>
Log of Test Boring Number: <b>B- 8</b>
Landmark School-Building Distress 5730 West Myrtle Avenue Glendale, Arizona Project No.: 161212SA

SPEEDIE 161212SA.GPJ GENGELO.DOT 7/28/16





**Boring Date:** 7-11-16  
**Field Engineer/Technician:** T. Wilmsen  
**Driller:** R. Markley  
**Contractor:** Speedie & Assoc.

Water Level		
Depth	Hour	Date
Free Water was Not Encountered		

NT = Not Tested

<b>SPEEDIE AND ASSOCIATES</b>
<b>Log of Test Boring Number: B- 9</b>
<b>Landmark School-Building Distress</b>  <b>5730 West Myrtle Avenue</b>  <b>Glendale, Arizona</b>  <b>Project No.: 161212SA</b>

\_SPEEDIE 161212SA.GPJ GEN GEO.GDT 7/26/16

Depth (feet)	Graphic Log	<b>Rig Type:</b> Hand Auger <b>Boring Type:</b> Hollow Stem Auger <b>Surface Elevation:</b> N/A	Sample Number	Depth of Sample	Natural Water Content (%)	In-place Dry Density (P.C.F.)	Penetration Resistance Blows per Foot
0		Visual Classification					0 25 50
		Stiff Brown <u>LEAN CLAY</u> with <u>SAND</u> (CL-Moist) with Trace Gravel					
		End of Boring	AS-1	3.0	21.6	NT	
5							


**Boring Date:** 7-11-16  
**Field Engineer/Technician:** T. Wilmsen  
**Driller:** R. Markley  
**Contractor:** Speedie & Assoc.

Water Level		
Depth	Hour	Date
Free Water was Not Encountered		

NT = Not Tested

<b>SPEEDIE AND ASSOCIATES</b>
<b>Log of Test Boring Number: B-10</b>
<b>Landmark School-Building Distress</b>  <b>5730 West Myrtle Avenue</b>  <b>Glendale, Arizona</b>
<b>Project No.: 161212SA</b>

SPEEDIE 161212SA.GPJ GENGEO.GDT 7/26/16



Sample Number	Depth of Sample	Natural Water Content (%)	In-place Dry Density (P.C.F.)	Penetration Resistance Blows per Foot
RS-1	2.0	14.3	109.5	

Boring Date: 7-11-16  
Field Engineer/Technician: T. Wilmsen  
Driller: R. Markley  
Contractor: Speedie & Assoc.

Water Level		
Depth	Hour	Date
Free Water was Not Encountered		

NT = Not Tested

**SPEEDIE AND ASSOCIATES**

Log of Test Boring Number: **B-11**

Landmark School-Building District

5730 West Myrtle Avenue

Glendale, Arizona

Project No.: 161212SA

**Graphic Log**

Rig Type:	Hand Auger
Boring Type:	Hollow Stem Auger
Surface Elevation:	N/A

## Visual Classification

Brown LEAN CLAY with SAND (CL-Moist to Wet) with Trace Gravel

## End of Boring

### 3.0

AS-1

### 3.0

### 33.1

NT

5-

**Boring Date:** 7-11-16  
**Field Engineer/Technician:** T. Wilmsen  
**Driller:** R. Markley  
**Contractor:** Speedie & Assoc.

Water Level		
Depth	Hour	Date
<i>Free Water was Not Encountered</i>		

**NT = Not Tested**

# SPEEDIE AND ASSOCIATES

Log of Test Boring Number: **B-12**

## Landmark School-Building Distress

**5730 West Myrtle Avenue**

## Glendale, Arizona

**Project No.: 161212SA**

SPEEDIE 101212SA.GPJ GENGE0.GDT 7/26/16

Depth (feet)	Graphic Log	Rig Type: Hand Auger Boring Type: Hollow Stem Auger Surface Elevation: N/A	Sample Number	Depth of Sample	Natural Water Content (%)	In-place Dry Density (P.C.F.)	Penetration Resistance Blows per Foot
0		Visual Classification					
		Brown <u>LEAN CLAY with SAND</u> (CL-Moist) with Little Gravel					
3.0		End of Boring	AS-1	3.0	21.4	NT	
5							

Boring Date: 7-11-16  
 Field Engineer/Technician: T. Wilmsen  
 Driller: R. Markley  
 Contractor: Speedie & Assoc.


Water Level		
Depth	Hour	Date
<b>Free Water was Not Encountered</b>		

NT = Not Tested

<b>SPEEDIE AND ASSOCIATES</b>
Log of Test Boring Number: <b>B-13</b>
<b>Landmark School-Building Distress</b>  <b>5730 West Myrtle Avenue</b>  <b>Glendale, Arizona</b>  <b>Project No.: 161212SA</b>

SPEEDIE 161212SA.GPJ GENGEO.GDT 7/26/16






Boring Date: **7-11-16**  
 Field Engineer/Technician: **T. Wilmsen**  
 Driller: **R. Markley**  
 Contractor: **Speedie & Assoc.**

Water Level		
Depth	Hour	Date
<b>Free Water was Not Encountered</b>		

NT = Not Tested

<b>SPEEDIE AND ASSOCIATES</b>
Log of Test Boring Number: <b>B-14</b>
<b>Landmark School-Building Distress</b>  <b>5730 West Myrtle Avenue</b>  <b>Glendale, Arizona</b>  Project No.: <b>161212SA</b>

SPEEDIE 161212SA.GPJ GENO.GDT 7/29/16




Boring Date: 7-11-16  
 Field Engineer/Technician: T. Wilmsen  
 Driller: R. Markley  
 Contractor: Speedie & Assoc.

Water Level		
Depth	Hour	Date
Free Water was Not Encountered		

NT = Not Tested

<b>SPEEDIE AND ASSOCIATES</b>
Log of Test Boring Number: <b>B-15</b>
<b>Landmark School-Building Distress</b>  <b>5730 West Myrtle Avenue</b>  <b>Glendale, Arizona</b>
Project No.: <b>161212SA</b>

SPEEDIE 161212SA.GPJ GENGEO.GDT 7/26/16



Boring Date: 7-13-16  
 Field Engineer/Technician: K. Euge II  
 Driller: C. Garcia  
 Contractor: Geomechanics SW

Water Level		
Depth	Hour	Date
<b>Free Water was Not Encountered</b>		

NT = Not Tested

<b>SPEEDIE AND ASSOCIATES</b>
Log of Test Boring Number: <b>B-16</b>
<b>Landmark School-Building Distress</b>  <b>5730 West Myrtle Avenue</b>  <b>Glendale, Arizona</b>
Project No.: <b>161212SA</b>

SPEEDIE 161212SA.GPJ GENGEO.GDT 7/28/16

Depth (feet)	Graphic Log	Rig Type: <b>CME-75</b> Boring Type: <b>Hollow Stem Auger</b> Surface Elevation: <b>N/A</b>	Sample Number	Depth of Sample	Natural Water Content (%)	In-place Dry Density (P.C.F.)	Penetration Resistance Blows per Foot
		Visual Classification					
0		NOT ACCESSIBLE					0 25 50
5							
10							
15							
20							


Boring Date: **7-13-16**  
 Field Engineer/Technician: **K. Euge II**  
 Driller: **C. Garcia**  
 Contractor: **Geomechanics SW**

Water Level		
Depth	Hour	Date
<i>Free Water was Not Encountered</i>		

NT = Not Tested

<b>SPEEDIE AND ASSOCIATES</b>
Log of Test Boring Number: <b>B-17</b>
<b>Landmark School-Building Distress</b>  <b>5730 West Myrtle Avenue</b>  <b>Glendale, Arizona</b>
Project No.: <b>161212SA</b>

SPEEDIE 161212SA.GPJ GENGEO.GDT 8/3/16



Boring Date: 7-13-16  
 Field Engineer/Technician: K. Euge II  
 Driller: C. Garcia  
 Contractor: Geomechanics SW

Water Level		
Depth	Hour	Date
Free Water was Not Encountered		

NT = Not Tested

<b>SPEEDIE AND ASSOCIATES</b>
Log of Test Boring Number: <b>B-18</b>
Landmark School-Building Distress 5730 West Myrtle Avenue Glendale, Arizona Project No.: 161212SA

SPEEDIE 161212SA.GPJ GENGEO.GDT 7/28/16



Depth (feet)	Graphic Log	<b>Rig Type:</b> Hand Auger <b>Boring Type:</b> Hollow Stem Auger <b>Surface Elevation:</b> N/A	Sample Number	Depth of Sample	Natural Water Content (%)	In-place Dry Density (P.C.F.)	Penetration Resistance Blows per Foot
		Visual Classification					
0		4" Concrete					
		4" Aggregate Base					
		Brown LEAN CLAY with SAND (CL-Moist) with Gravel					
		Auger Refusal on Gravel					
5							

Boring Date: 7-11-16  
 Field Engineer/Technician: T. Wilmsen  
 Driller: R. Markley  
 Contractor: Speedie & Assoc.

Water Level		
Depth	Hour	Date
Free Water was Not Encountered		

NT = Not Tested

<b>SPEEDIE AND ASSOCIATES</b>
Log of Test Boring Number: <b>C-1</b>
<b>Landmark School-Building Distress</b>  <b>5730 West Myrtle Avenue</b>  <b>Glendale, Arizona</b>  <b>Project No.: 161212SA</b>

SPEEDIE 161212SA.GPJ GENGEO.GDT 7/28/16



# TABULATION OF TEST DATA

SOIL BORING or TEST PIT NUMBER	SAMPLE NUMBER	SAMPLE TYPE	SAMPLE INTERVAL (ft)	NATURAL WATER CONTENT (Percent of Dry Weight)	IN-PLACE DRY DENSITY (Pounds Per Cubic Foot)	PARTICLE SIZE DISTRIBUTION (Percent Finer)					ATTERBERG LIMITS			UNIFIED SOIL CLASSIFICATION	SPECIMEN DESCRIPTION
						#200 SIEVE	#40 SIEVE	#10 SIEVE	#4 SIEVE	3" SIEVE	LIQUID LIMIT	PLASTIC LIMIT	PLASTICITY INDEX		
B-1	RS-1	RING	1.0 - 2.0	12.4	74.2	91	100	100	100	100	30	23	7	ML	SILT
B-2	AS-1	AS	1.0 - 3.0	26.9	NT	NT	NT	NT	NT	NT	NT	NT	NT		
B-3	AS-1	AS	1.0 - 3.0	26.2	NT	NT	NT	NT	NT	NT	NT	NT	NT		
B-4	AS-1	AS	1.0 - 3.0	7.5	NT	76	85	93	96	100	36	23	13	CL	LEAN CLAY with SAND
B-5	AS-1	AS	1.0 - 3.0	17.3	NT	NT	NT	NT	NT	NT	NT	NT	NT		
B-6	AS-1	AS	1.0 - 3.0	3.7	NT	NT	NT	NT	NT	NT	NT	NT	NT		
B-7	AS-1	AS	1.0 - 3.0	10.4	NT	NT	NT	NT	NT	NT	NT	NT	NT		
B-8	AS-1	AS	1.5 - 3.0	23.5	NT	NT	NT	NT	NT	NT	NT	NT	NT		
B-9	AS-1	AS	2.0 - 3.5	14.3	NT	87	93	94	95	100	46	24	22	CL	LEAN CLAY
B-10	AS-1	AS	1.0 - 3.0	21.6	NT	NT	NT	NT	NT	NT	NT	NT	NT		
B-11	RS-1	RING	1.0 - 2.0	14.3	108.5	79	88	92	94	100	37	21	16	CL	LEAN CLAY with SAND
B-12	AS-1	AS	1.0 - 3.0	33.1	NT	NT	NT	NT	NT	NT	NT	NT	NT		
B-13	AS-1	AS	1.0 - 3.0	21.4	NT	NT	NT	NT	NT	NT	NT	NT	NT		
B-14	AS-1	AS	1.0 - 3.0	23.1	NT	NT	NT	NT	NT	NT	NT	NT	NT		
B-15	AS-1	AS	1.0 - 3.0	10.4	NT	94	99	100	100	100	41	24	17	CL	LEAN CLAY
B-16	RS-1	RING	1.0 - 2.0	11.3	85.6	NT	NT	NT	NT	NT	NT	NT	NT		

Sieve analysis results do not include material greater than 3". Refer to the actual boring logs for the possibility of cobble and boulder sized materials.

NT=Not Tested

Sheet 1 of 2

Landmark School-Building Distress  
5730 West Myrtle Avenue  
Glendale, Arizona  
Project No. 161212SA

**SPEEDIE  
AND ASSOCIATES**

# TABULATION OF TEST DATA

SOIL BORING or TEST PIT NUMBER	SAMPLE NUMBER	SAMPLE TYPE	SAMPLE INTERVAL (ft)	NATURAL WATER CONTENT (Percent of Dry Weight)	IN-PLACE DRY DENSITY (Pounds Per Cubic Foot)	PARTICLE SIZE DISTRIBUTION (Percent Finer)					ATTERBERG LIMITS			UNIFIED SOIL CLASSIFICATION	SPECIMEN DESCRIPTION
						#200 SIEVE	#40 SIEVE	#10 SIEVE	#4 SIEVE	3" SIEVE	LIQUID LIMIT	PLASTIC LIMIT	PLASTICITY INDEX		
B-18	BS-2	BULK	0.0 - 5.0	NT	NT	86	95	98	99	100	44	24	20	CL	LEAN CLAY
B-18	RS-1	RING	1.0 - 2.0	18.8	86.7	NT	NT	NT	NT	NT	NT	NT	NT		
B-18	RS-3	RING	5.0 - 6.0	17.6	90.2	NT	NT	NT	NT	NT	NT	NT	NT		
C-2	RS-1	RING	1.5 - 2.5	10.7	111.9	75	82	88	91	100	37	22	15	CL	LEAN CLAY with SAND

Sieve analysis results do not include material greater than 3". Refer to the actual boring logs for the possibility of cobble and boulder sized materials.

NT=Not Tested

Sheet 2 of 2

Landmark School-Building District  
5730 West Myrtle Avenue  
Glendale, Arizona  
Project No. 161212SA

**SPEEDIE  
AND ASSOCIATES**

# CONSOLIDATION TEST

PROJECT: Landmark School-Building Distress

PROJECT NO.: 161212SA

LOCATION: 5730 West Myrtle Avenue

DATE: 7/11/16

BORING NO.: C-2

SAMPLE NO.: RS-1

SAMPLE DEPTH: 1.5 to 2.5

LABORATORY NO.:

LIQUID LIMIT:

37

PLASTIC LIMIT:

22

PLASTICITY INDEX:


14

CLASSIFICATION:

CL

ASTM SOIL DESCRIPTION:

LEAN CLAY with SAND



**SPEEDIE  
AND ASSOCIATES**



# CONSOLIDATION TEST

PROJECT: Landmark School-Building Distress

PROJECT NO.: 161212SA

LOCATION: 5730 West Myrtle Avenue

DATE: 7/13/16

BORING NO.: B-18

SAMPLE NO.: RS-1

SAMPLE DEPTH: 1 to 2

LABORATORY NO.:


LIQUID LIMIT:

PLASTIC LIMIT:

PLASTICITY INDEX:

CLASSIFICATION:

ASTM SOIL DESCRIPTION:



Sample inundated at end of test at 3200 psf

**SPEEDIE  
AND ASSOCIATES**

# CONSOLIDATION TEST

PROJECT: Landmark School-Building Distress

PROJECT NO.: 161212SA

LOCATION: 5730 West Myrtle Avenue

DATE: 7/11/16

BORING NO.: B-11

SAMPLE NO.: RS-1

SAMPLE DEPTH: 1 to 2

LABORATORY NO.:

LIQUID LIMIT: 37


PLASTIC LIMIT: 21

PLASTICITY INDEX: 15

CLASSIFICATION: CL

ASTM SOIL DESCRIPTION:

LEAN CLAY with SAND



Sample inundated at end of test at 3200 psf

**SPEEDIE**  
AND ASSOCIATES

# MOISTURE-DENSITY RELATIONS

PROJECT: Landmark School-Building Distress

PROJECT NO.: 161212SA

LOCATION: 5730 West Myrtle Avenue

DATE: 7/13/16

BORING NO.: B-18

SAMPLE NO.: BS-2

SAMPLE DEPTH: 0 to 5

LABORATORY NO.:

METHOD OF COMPACTION: D698A

LIQUID LIMIT: 44

PLASTIC LIMIT: 24

PLASTICITY INDEX:

20


CLASSIFICATION: CL

ASTM SOIL DESCRIPTION:

LEAN CLAY

MAXIMUM DRY DENSITY: 100.0 PCF

OPTIMUM MOISTURE CONTENT: 21.6%



**SPEEDIE  
AND ASSOCIATES**

# SWELL TEST DATA

BORING or TEST PIT No.	SAMPLE DEPTH, ft	MAXIMUM DRY DENSITY (pcf)	OPTIMUM MOISTURE CONTENT (%)	REMOVED DRY DENSITY (pcf)	INITIAL MOISTURE CONTENT (%)	PERCENT COMPACTION	FINAL MOISTURE CONTENT (%)	CONFINING LOAD (psf)	TOTAL SWELL (%)
B-18, BS-2	5.0	100.0	21.6	95.3	19.4	95.3	30.1	100	5.4

Landmark School-Building Distress  
5730 West Myrtle Avenue  
Glendale, Arizona  
Project No. 161212SA

**SPEEDIE  
AND ASSOCIATES**





# GERVASIO INVESTIGATION REPORTS



# GERVASIO & ASSOC., INC.

## CONSULTING ENGINEERS

77 EAST THOMAS ROAD, SUITE 120

PHOENIX, ARIZONA 85012

(602) 285-1720 • (602) 285-1530 (FAX)

February 15, 2011

Mr. Mike Coppa  
ARIZONA SCHOOL RISK RETENTION TRUST, INC.  
333 East Osborn Road, Suite 300  
Phoenix, AZ 85012

RE: LANDMARK MIDDLE SCHOOL  
5730 West Myrtle, Glendale, Arizona  
MASONRY WALL CRACKS INVESTIGATION  
G&A Job No. 0250 F

Dear Mr. Coppa:

In accordance with your request, we have performed a limited investigation to evaluate the existing cracks in the masonry walls at the northeast corner of the Gym Building at the above referenced location. While viewing the Gym Building, we discovered masonry cracks at exterior steel canopy beam bearings; therefore, we will include these cracks in our report as well. The following letter report presents our findings, conclusions, and recommendations and includes:

- Appendix A: Field Notes & Photo Location Plans
- Appendix B: Partial Plumbing and Water & Sewer Plans of the NEC of the Gym Building by NBBJ Group/Gresham Larson dated 3/30/87

During our site visit by Marlene Betani, P.E., of Gervasio & Assoc., Inc. on December 2, 2010, we took forty-two (42) digital photos, one (1) copy each enclosed.

### FINDINGS, CONCLUSIONS & RECOMMENDATIONS

The Gym Building is a one-story concrete masonry structure built circa 1987. The roof structure is constructed with metal roof deck supported by steel joists that bear on the masonry walls. The roofing is built-up type roofing.

There are three different types of masonry cracks at the Gym Building. These are :

- Stair-step cracks
- Vertical cracks
- Cracks at beam bearings

#### Stair-Step Cracks:

There are stair-step cracks near the northeast corner of the building that generally follow the mortar joints in the east/west exterior wall and the east/west interior wall between the Janitor's Room and Storage Room and between the Boy's Locker Room and the Office (Photos A6-A14 & A31). Stair-step cracks of the type present here indicate foundation settlement. Settlement can occur when the foundation soils become wet. The soils outside the northeast

building corner appeared moist. There are numerous underground pipes in the vicinity of the building corner including the fire sprinkler check valve, and floor sink supply and drain piping (see Appendix B & Photos A32-A36). There is also a roof drain outlet nearby that directs rainwater into the planting area near the check valve piping. Water lines are required to be set on a bed of sand in the bottom of the trench prior to backfilling. This sand layer creates an easy pathway for water to migrate beyond the water source and into the foundation soils. The roof joists above this area bear on the east exterior masonry wall and remain adequately supported.

We conclude that the cracks are not a structural concern at this time, but may become a concern if additional foundation movement occurs.

We recommend that the cracks be monitored to determine if they are getting larger. If additional movement occurs, there is likely an underground water source that should be located and eliminated. If the School District wants to repair the cracks at this time, we recommend that the cracked mortar joints be repointed.

#### Vertical Cracks:

There is a vertical crack in the south wall of the Gym Building (Photos A17 & A39). This crack occurs near a step in the wall height and near a jamb of a door opening. This is an expansion/contraction crack and is located where the stiffness of the wall changes with the change in wall height. The original building drawings show a masonry control joint at the change in wall height, but the control joint was not installed.

There is also a vertical crack in the west wall of the Gym (Photos A25-A27). This crack is most likely also due to expansion/contraction. The original building drawings show masonry control joints at approximately 30 feet on center. The National Concrete Masonry Association (NCMA) technical note TEK 10-2C recommends control joint spacing of 25 feet on center maximum. It is likely that the longer than recommended joint spacing and restraint provided by nearby intersecting masonry walls contributed to this vertical crack.

We conclude that the cracks are not a structural concern.

We recommend that the cracks be caulked to prevent moisture from entering the building walls.

#### Cracks at Beam Bearings:

There is cracked and displaced masonry at three exterior steel canopy beam bearings. Two of the beams are located at the south entry to the Lobby of the Gym Building at the north end of the approximately 124 ft. long steel canopy structure (Photos A1-A5). The third beam is parallel to the west side of the Multi-Purpose Room at the north end of the 84 ft. long exterior steel canopy (Photos A41-A43). The original building drawings indicate that these three beams are welded to a steel bearing plate that is anchored to the masonry wall. These long steel canopies are exposed to daily and seasonal temperature swings that cause thermal expansion/contraction. Because the beams are rigidly attached to the walls, the brittle masonry material has cracked to relieve the induced thermal forces.

We conclude that the beams do not currently present a danger of sudden collapse, but could become dangerous in the future if not repaired. The potential for falling chunks of masonry presents a safety hazard.

Mr. Mike Coppa  
February 15, 2011  
G&A Job No. 0250 F  
Page 3

We recommend that the beam bearings be modified to allow for thermal movement. Conceptually, this can be accomplished by shoring each beam, removing the loose and broken masonry, and cutting the welds that connect the beam to the bearing plate. The masonry should then be repaired, leaving a gap around the beam so it can move. A shelf angle with a neoprene bearing pad should then be installed with epoxy anchors below the beam to the face of the masonry wall to provide bearing.

This letter is based on the facts and evidence known to us as of this date and may be amended if new facts and/or evidence are presented or discovered.

We appreciate the opportunity to provide this service and welcome any questions.

Sincerely,

GERVASIO & ASSOC., INC.



Marlene Betani, P.E.  
Forensic Structural Engineer


MB:blm

Enclosures




# APPENDIX A

FIELD NOTES &  
PHOTO LOCATION PLANS



Landmark Middle School  
5730 W. Myrtle Ave.

FIELD NOTES & PHOTO LOCATION PLAN ↑  
12/2/10 by MB




FIELD NOTES & PHOTOLOCATION PLAN. -N→

## APPENDIX B

PARTIAL PLUMBING AND WATER & SEWER PLANS  
OF THE NEC OF THE GYM BUILDING  
BY NBBJ GROUP/GRESHAM LARSON  
DATED 3/30/87

VERTICAL PUMPING PLAN



3.00' ON  
CONNECT  
THERM. B.O.  
ROOF  
(#5)

R.U.P.

UP  
OF

1.70



2



1. Conductor's Initials  
 2. Date

1. 6" FIRELINE TYPE C-900 OR APPROVED EQUAL.
2. 6" T.S. & V. WITH BOX AND COVER, MAG. ST. DETAIL 391-1-C.
3. 8" T.S. & V. WITH BOX AND COVER, MAG. ST. DETAIL 391-1-C.
4. INSTALL 6" V.C.P. SINKER LINE.
5. INSTALL 6" DIA. P.V.C. (SDR 35) SINKER.
6. INSTALL CLEANKUT, MAG. STD. DETAIL 431.
7. INSTALL SINKER MANHOLE, MAG. STD. DETAIL 421.
8. INSTALL 6" CHECK VALVE, CITY OF GLENDALE DETAIL 343. SEE SHEET 1.
9. INSTALL 8" A.C.P. WATER LINE.
10. INSTALL 6" X 8" TEE.
11. 8" V.B.E.C., MAG. STD. DETAIL 391-1 (TYPE 1).
12. INSTALL 22-1/2" BOD.
13. INSTALL COMPLETE FIRE HYDRANT ASSEMBLY CITY OF GLENDALE STD. DETAIL 340.
14. REMOVE EXISTING C.D.
15. CONSTRUCT SINKER MANHOLE MAG. STD. DETAIL 4.
16. INSTALL 6" V.C.P. SINKER LINE.
17. REMOVE EXISTING SINKER LINE.
18. CONNECT TO EXIST. SINKER LINE TO NORTH SINKER LINE TO SOUTH.
19. CONNECT TO EXIST. SINKER LINE TO SOUTH, SINKER LINE TO NORTH.
20. 6" X 8" REDUCER
21. 2" METER BOX MAG. STD. DETAIL 329
22. 4" PUMPER CONNECTION.
23. SHUTOUT, REMOVE & REPLACE FAULTY MAG. STD. DET. 200, 1/2" TYPE.
24. 43" L.F. OF 8" V.C.P. SINKER LINE @ 5% SLOPE.
25. 82" L.F. OF 8" V.C.P. SINKER LINE @ 5% SLOPE.

NOTE: CONTRACTOR SHALL USE THIS PLAN FOR REFERENCE OF





# GERVASIO & ASSOC., INC.

## CONSULTING ENGINEERS

77 EAST THOMAS ROAD, SUITE 120

PHOENIX, ARIZONA 85012

(602) 285-1720 • (602) 285-1530 (FAX)

May 27, 2014

Mr. David Frandsen  
ARIZONA SCHOOL RISK RETENTION TRUST, INC.  
333 East Osborn Road, Suite 300  
Phoenix, AZ 85012

via Email: [dfrandsen@the-trust.org](mailto:dfrandsen@the-trust.org)

RE: LANDMARK ELEMENTARY SCHOOL  
5730 West Myrtle, Glendale, Arizona  
MASONRY WALL CRACKS INVESTIGATION  
G&A Job No. 0250.1 F

Dear Mr. Frandsen:

In accordance with your request, we have performed a limited investigation to evaluate the existing vertical cracks at the control joints in the masonry piers at the entrance to the Administration Building at the above referenced location. The following letter report presents our findings, conclusions, and recommendations and includes:

- Appendix A: Field Notes & Photo Location Plans
- Appendix B: Natural Resources Conservation Service Soil Shrink/Swell Potential Map of the Greater Phoenix Area
- Appendix C: Selected Original Building Drawings by The NBBJ Group/Gresham Larson dated 3-30-87
- Appendix D: Parapet Repair Sketches prepared by Gervasio & Assoc., Inc. dated 5-27-14

During our site visit by Marlene Betani, P.E., of Gervasio & Assoc., Inc. on March 27, 2014, we took twenty-four (24) digital photos, one (1) copy each enclosed.

### FINDINGS, CONCLUSIONS & RECOMMENDATIONS

The Administration Building is a one-story concrete masonry structure built circa 1988. The roof structure is constructed with plywood deck supported by wood trusses with metal web members. The trusses bear on the interior and exterior masonry walls and interior glue-laminated wood beams. The roofing is built-up type roofing.

The entrance is located on the east side of the building. There is a 24 in. square masonry pier on each side of the doorway alcove that projects 16 in. past the face of the building. At the parapet, there is a brick faced parapet cap approximately 28 in. wide that covers the tops of the piers and the masonry walls above the entry openings between the piers. There is a full height masonry control joint where the piers abut the face of the building. At the south pier, the top of the pier has rotated outward approximately 3/4 in., leaving a large gap where rainwater can enter the entry alcove ceiling area below (Photos A5, A8, & A19). The gap is on the vertical face and has also opened the mortar joints in the horizontal parapet cap (Photos A8 - A10, & A20). There are signs that this rotation has been ongoing, based on the repair attempts made at both ends of the entry parapet (Photos A11 & A12), but it was reported to have gotten worse since the building was painted in October of 2013. The caulk in the joint is very thick with no visible backer rod. The caulk thickness into the wall creates a strong layer of caulk that will break or tear

rather than flex with small movements. A backer rod allows a thinner cross section of caulk to be installed so that it can stretch slightly like a thin rubber band and can accommodate small movements.

The outward rotation of the pier had not yet caused cracking in the masonry and ceiling material in the entry above itself and the damage was limited to the parapet area at the time of our inspection.

It was reported that the landscape areas adjacent to the entry were changed from grass to desert landscaping a few years ago. The irrigation system was modified to a drip system with water targeted at each plant. This landscaping change resulted in a significant drop in the moisture added to the soils adjacent to the masonry piers. We attempted to obtain a copy of the Soil Report for this building project from the Geotechnical Engineer, but were told that they do not keep records from that long ago. We located the site on the Natural Resources Conservation Service Soil Shrink/Swell Potential Map of the Greater Phoenix Area (Appendix B). The school is located in an area with a low swell/shrink potential. The Structural Notes indicate that the building foundations were to be built on 2 ft. of recompacted native soil. This reuse of native soils also suggests that the site soils have a low shrink/swell potential.

We reviewed the available building drawings while on site. There are 3 roof drains on the east side of the building, one of which is behind the entry parapet, but the available drawings did not indicate where they outlet. The drawings indicate regularly spaced ties in the masonry piers, but the manner in which the pier is rotating suggests that the ties were not installed (Appendix C, Detail 6/S36). The drawings show a control joint at the junction between the exterior wall and the pier, and one was installed there, but there is also a control joint between the pier and the wall parallel to the wall face. Horizontal joint reinforcement is usually not continued through a control joint, but horizontal bond beam steel at the roof line and top of parapet is typically continuous through the joint with the reinforcing steel bars taped with a bond breaking tape to allow for a small amount of movement. Based on the size of the gap at the parapet, it does not appear that there is reinforcing steel tying the end of the pier to the building wall.

Along the top of the brick faced parapet cap over the entry, there is a gap in the mortar joint between the bricks over the exterior or eastmost entry wall and the bricks that cover the top of the building wall parapet and the 8 in. gap between the two walls (Photos A10 & A20). This gap indicates that the two walls are not tied together at the top and are moving relative to each other. It also indicates that the bricks over the 8 in. space between the walls could lose support at one end and fall into the gap and onto the entry ceiling below.

We conclude that the pier movement may be due to the change in the amount of moisture in the soil adjacent to the pier foundations. The pier is lightly loaded and can safely carry the imposed dead loads and Code required live loads. The gaps in the parapet cap above the entry pose a safety concern due to the potential for bricks dislodging and falling, particularly through the entry ceiling. The gaps also allow rainwater to enter the building where it can damage interior finishes and provide moisture for mold growth.

We recommend the following:

1. That the two parapet walls over the entry be tied together at the top with a reinforced slab between the walls per Detail 2/SS-2 in Appendix D.

Mr. David Frandsen  
May 27, 2014  
G&A Job No. 0250.1 F  
Page 3

2. That the piers at each end of the entry be tied to the building wall per Detail 1/SS-2 in Appendix D.
3. That the control joints be recaulked, completely removing the old caulk by grinding and installing a paintable polyurethane sealant on a continuous closed cell backer rod per Detail 3/SS-3 in Appendix D.
4. After the repairs noted above are completed, the joint should be monitored approximately every 3 months to determine if it is getting larger. If additional movement occurs, then a Structural Engineer should be consulted for possible solutions such as underpinning of the pier foundation.

This letter is based on the facts and evidence known to us as of this date and may be amended if new facts and/or evidence are presented or discovered.

We appreciate the opportunity to provide this service and welcome any questions.

Sincerely,

GERVASIO & ASSOC., INC.



Marlene Betani, P.E.  
Forensic Structural Engineer

MB:rz

Enclosures



# APPENDIX A

FIELD NOTES & PHOTO LOCATION PLANS



Google earth



# Photo Location Plan

Landmark Middle School Bldg  
 2200 N. 1st St. S. 1st  
 1st St. S. 1st

Set A  
 Taken 3-27-14  
 by MB

GERVASIO & ASSOC. INC.  
CONSULTING ENGINEERS


(602) 265-1720 • 77 East Thomas Road, Suite 120  
PHOENIX, ARIZONA 85012-3115

Date 3-27-14

Job No. 0250.1


By AA/B

Sheet No. 1



## APPENDIX B

NATURAL RESOURCES CONSERVATION SERVICE  
SOIL SHRINK/SWELL POTENTIAL MAP OF THE  
GREATER PHOENIX AREA



# SOIL SHRINK/SWELL POTENTIAL GREATER PHOENIX AREA

- High
- Moderate
- Low
- U.S. Forest Service

**LEGEND**


THIS MAP WAS PREPARED BY THE U.S. DEPARTMENT OF AGRICULTURE, NATURAL RESOURCES CONSERVATION SERVICE, PHOENIX, ARIZONA, FOR ALIQUOTED TO THE PHOENIX AREA OF THE U.S. DEPARTMENT OF AGRICULTURE, NATURAL RESOURCES CONSERVATION SERVICE, PHOENIX, ARIZONA.

THE SOIL SHRINK/SWELL POTENTIAL AT A SCALE OF 1:250,000 IS BASED ON THE DATA OF THE U.S. DEPARTMENT OF AGRICULTURE, NATURAL RESOURCES CONSERVATION SERVICE, PHOENIX, ARIZONA, AND THE U.S. DEPARTMENT OF AGRICULTURE, NATURAL RESOURCES CONSERVATION SERVICE, PHOENIX, ARIZONA.

THE DATA FOR THIS MAP WAS OBTAINED FROM THE U.S. DEPARTMENT OF AGRICULTURE, NATURAL RESOURCES CONSERVATION SERVICE, PHOENIX, ARIZONA, AND THE U.S. DEPARTMENT OF AGRICULTURE, NATURAL RESOURCES CONSERVATION SERVICE, PHOENIX, ARIZONA.

THE DATA FOR THIS MAP WAS OBTAINED FROM THE U.S. DEPARTMENT OF AGRICULTURE, NATURAL RESOURCES CONSERVATION SERVICE, PHOENIX, ARIZONA, AND THE U.S. DEPARTMENT OF AGRICULTURE, NATURAL RESOURCES CONSERVATION SERVICE, PHOENIX, ARIZONA.

THE DATA FOR THIS MAP WAS OBTAINED FROM THE U.S. DEPARTMENT OF AGRICULTURE, NATURAL RESOURCES CONSERVATION SERVICE, PHOENIX, ARIZONA, AND THE U.S. DEPARTMENT OF AGRICULTURE, NATURAL RESOURCES CONSERVATION SERVICE, PHOENIX, ARIZONA.




Scale: 1:250,000  
Map prepared by: NRCS




## APPENDIX C

SELECTED ORIGINAL BUILDING DRAWINGS BY  
THE NBBJ GROUP/GRESHAM LARSON DATED 3-30-87




  
 BUILDING 'B' ADMINISTRATION/CLASSROOM  
 FOUNDATION PLAN




The NBBJ Group/Grasham Laman  
 561 East 1st Street, Suite 100, Portland, Oregon 97204-1000  
 503.226.1111 Fax 503.226.1112

Glendale Elementary School District #40  
 Landmark Site




NO.	REVISION	DATE	BY	CHKD.
1				
2				
3				
4				
5				
6				
7				
8				
9				
10				

FOUNDATION PLAN	S5
DATE: 11/11/01	
BY: [Signature]	
CHKD: [Signature]	
APP: [Signature]	



①  
☐ BUILDING "B" ADMINISTRATION/CLASSROOM  
 ROOF FRAMING PLAN

AS-BUILTS



① KEY PLAN

The NBBJ Group/Gresham Larson  
 1015 East 17th Avenue, Suite 100, Denver, Colorado 80202  
 303-733-1100

Glendale Elementary School District #40  
 Landmark Site






DATE	10/1/00
BY	...
CHECKED	...
APPROVED	...



PROJECT	GLD
DATE	10/1/00
BY	...
CHECKED	...
APPROVED	...

S6





### Return and Fostering Schedule



**The NBBJ Group/Gresham Larson**  
 600 East Packer Road, Suite 120, Chicago, Illinois 60611-1601  
 (312) 329-6000 • Telex: 250700 • Cable: 250703 • FAX: 312/329-6000


Glendale Elementary School District #40  
Landmark Site

AS-BUILTS

537







The NBBJ Group/Gresham Larson  
 1000 North 10th Street, Suite 100  
 Seattle, WA 98107-3500

Glendale Elementary School District #40  
 Landmark Site



DATE	REVISION	BY	CHKD
10/1/88	1	AS	AS
10/1/88	2	AS	AS
10/1/88	3	AS	AS
10/1/88	4	AS	AS
10/1/88	5	AS	AS
10/1/88	6	AS	AS
10/1/88	7	AS	AS
10/1/88	8	AS	AS
10/1/88	9	AS	AS
10/1/88	10	AS	AS
10/1/88	11	AS	AS
10/1/88	12	AS	AS
10/1/88	13	AS	AS
10/1/88	14	AS	AS
10/1/88	15	AS	AS
10/1/88	16	AS	AS
10/1/88	17	AS	AS
10/1/88	18	AS	AS
10/1/88	19	AS	AS
10/1/88	20	AS	AS

AS-BUILTS

\$39



## APPENDIX D

PARAPET REPAIR SKETCHES PREPARED BY  
GERVASIO & ASSOC., INC. DATED 5-27-14

PROJECT

### SCOPE OF STRUCTURAL WORK (GENERAL)

1. Remove brick parapet cap over office entry.
2. Epoxy horizontal dowels at each end of entry parapet per Det. 1/SS2.
3. Install ties & grout at top of parapet per Det. 2/SS2.
4. Replace brick parapet cap.
5. Repair existing masonry control joints per Det. 3/SS2.

### REPAIR GENERAL NOTES

1. All parties involved in the repair work shall visit the site, become familiar with the existing conditions and verify those existing conditions shown on the drawings.
2. Verify all dimensions and conditions prior to starting work. Notify the Engineer of any discrepancies or inconsistencies.
3. Any damage to existing ceilings, roofing, lights, fixtures or other materials caused by the repair work shall be repaired and/or replaced to match existing conditions. All painting and surface treatments shall also match existing conditions.
4. Provide all necessary temporary bracing, shoring, guying or other means to avoid excessive stresses and to hold structural elements in place during construction.
5. Any engineering design provided by others and submitted for review shall bear the seal and signature of an Engineer registered in Arizona.

### REINFORCING

1. ASTM A615, Grade 60, deformed bars. CRSI and ACI manuals apply.
2. Place reinforcing per ACI 318-05 and CRSI Standards.

### MASONRY

1. Brick units at parapet cap to match existing.
2. Mortar: Type S, 1800 psi.
3. Grout: 2000 psi. A maximum of 18% by weight of the total cementitious materials may be replaced by fly ash, provided the fly-ash conforms to ASTM A618, Type F.

### SPECIAL INSPECTION

Special Inspection is required for all repair work. Call Structural Engineer for inspection, phone number (602) 285-1720. Provide 48 hours notice.


Special inspection is to be provided in addition to the inspections conducted by the Department of Building Safety and shall not be construed to relieve the Owner or his authorized agent from requesting the periodic and called inspections required by Section 110 of the International Building Code. The special inspector shall be approved by the City Building Official prior to starting work.

**SPECIAL INSPECTION IS REQUIRED FOR THE FOLLOWING WORK:**  
(PER IBC SECTION 1705)

**EPOXY GROUTED ANCHORS:**  
During installation of epoxy grouted anchors.

### STRUCTURAL MASONRY:

1. During sampling and placing of all masonry units, placement of reinforcement, inspection of grout space, immediately prior to closing of cleanouts and during all grouting operations.
2. Special inspection for the placing of the units shall be performed in accordance with IBC Section 1705.4 on a periodic basis.



PLAN @ ADMIN BLDG ENTRY  
1/4" = 1'-0"

JOB No.	02552
Date	5/27/14
BY	EJK/AB
Sheet No.	55-1


REPAIR OF MASONRY PARAPET AT ADMINISTRATION BUILDING ENTRY.

LANDMARK ELEMENTARY SCHOOL  
5730 WEST MYRTLE AVE  
GLENDALE, ARIZONA

GERVASIO & ASSOC., INC.

CONSULTING ENGINEERS  
2115 N. THOMAS ROAD, SUITE 120  
PHOENIX, ARIZONA 85016  
(602) 285-1720 FAX 285-1533

This drawing is an instrument of service. It is the property of GERVASIO & ASSOCIATES, INC., and may not be reproduced or reproduction hereof used without permission.



Job No.	0252.1
Date	5/27/14
By	EHF/JAG
Sheet No.	15
SS-2	4

REPAIR OF MASONRY PARAPET AT ADMINISTRATION BUILDING ENTRY.

GERVASIO & ASSOC. INC.  
CONSULTING ENGINEERS  
1000 N. CENTRAL AVENUE, SUITE 100  
PHOENIX, ARIZONA 85022  
PHONE: 602-258-1750 FAX: 602-258-1520


LANDMARK ELEMENTARY SCHOOL  
5700 WEST MYRTLE AVE.  
GLENDALE, ARIZONA

This drawing is on instrument of service. It is the property of GERVASIO & ASSOCIATES, INC. and may not be reproduced or reproduction hereof used without permission.



PROJECT

JOINT WIDTH "w"	CAULK THICKNESS "t" = "w"/2	BACKER ROD DIAMETER = 1.25 x "w"
3/8"	3/16"	1/2"
1/2"	1/4"	5/8"
5/8"	5/16"	3/4"
3/4"	3/8"	1"
7/8"	3/8"-1/2" MAX	1 1/4"
1" OR GREATER	3/8"-1/2" MAX	1 1/4" OR 1.25 x "w" WHICHEVER IS GREATER



3 JOINT AT EXISTING CMU WALL

N.T.S.

## ADHESIVE ANCHOR INSTALLATION PROCEDURE

- 1. DRILL HOLE:** See details for anchor type (i.e., rebar or all-thread rod) and anchor diameter. Drill hole in existing masonry walls with a hand-held rotary hammer drill with a carbide drill bit, 1/8" larger diameter than anchor to be used. Embedment depth shall be as shown in details. Anchor must be embedded in solid grouted cells, with 8" grout around anchor.
- 2. CLEAN HOLE:** Clean hole with nylon brush and blow out hole using oil free and moisture-free compressed air. For wet-drilled holes, wash out hole to remove drilling slurry residue, remove free standing water and allow hole to dry thoroughly.
- 3. ADHESIVE:** Hilti HY-70 Adhesive Anchor System (ICC ESR 2682) or Simpson SET Anchoring Adhesive (ICC ESR 1772). Anchor installation per manufacturers recommendations. Other adhesive may be used if approved by the Structural Engineer.
- 4. TEMPERATURE REQUIREMENTS:** Base material temperature must be between 41°F and 110°F at the time of installation. Adhesive temperature must be between 41°F and 90°F at the time of installation.
- 5. PREPARE ANCHOR:** Clean, dry and wipe anchor free of all water, dirt, oil and grease, etc.
- 6. SET ANCHOR:** Fill hole 1/2 to 2/3 full with adhesive, insert anchor and twist during installation to insure complete embedment.
- 7. SET OR CURE TIME:** Do not displace or move anchor in any way after anchor is set. Allow adhesive to cure for 24 hours minimum before tightening nuts on anchor.
- 8. SPECIAL INSPECTION:** Adhesive anchor installations require special inspection in accordance with the Code. The special inspector records the drill bit compliance with ANSI B212.15-1994; hole depth and cleanliness; product description, including product name; rod diameter and length; adhesive expiration date; and verification of anchor installation with manufacturer's published instructions.

4 ADHESIVE ANCHOR INSTALLATION  
FOR MASONRY

NO SCALE

JOB No.	02501
Date	5/27/14
BY	ENR/MR
Sheet No.	SS-5



REPAIR OF MASONRY PARAPET AT ADMINISTRATION BUILDING ENTRY.

LANDMARK ELEMENTARY SCHOOL  
5730 WEST MYRTLE AVE.  
GLENDALE, ARIZONA

GERVASIO &amp; ASSOC. INC.

CONSULTING ENGINEERS  
122  
PHOENIX, ARIZONA 85016  
(602) 233-1720 FAX 233-1222

This drawing is an instrument of service. It is the property of GERVASIO &amp; ASSOCIATES, INC., and may not be reproduced or reproduction hereof used without permission.

# GERVASIO & ASSOC., INC.

CONSULTING ENGINEERS  
77 EAST THOMAS ROAD, SUITE 120  
PHOENIX, ARIZONA 85012  
(602) 285-1720 • (602) 285-1530 (FAX)

July 20, 2015

Ms. Sarafina Fornara  
ARIZONA SCHOOL RISK RETENTION TRUST, INC.  
333 East Osborn Road, Suite 300  
Phoenix, AZ 85012

Via email: [sfornara@the-trust.org](mailto:sfornara@the-trust.org)

RE: GLENDALE - LANDMARK ELEMENTARY SCHOOL  
5730 West Myrtle, Glendale, Arizona  
MEDIA CENTER WALL CRACKS INVESTIGATION  
Trust RMAR No. 2014-0044  
G&A Job No. 0250.2 F

Dear Ms. Fornara:

In accordance with your request, we have performed a limited investigation to evaluate the cracks at the exterior masonry walls and the interior librarian's office walls at the Media Center Building at the above referenced location. While on site, we observed unrelated structural concerns which are discussed in Appendix E. The following letter report presents our findings, conclusions, and recommendations and includes:

- Appendix A: Field Notes & Photo Location Plans
- Appendix B: Structural Rehabilitation Drawings by Magadini Associates dated 1/28/69
- Appendix C: Floor Elevation Survey by Gervasio & Assoc., Inc. dated 3/4/15
- Appendix D: Uniform Building Code Standard 21-8 "Pointing of Unreinforced Masonry Walls"
- Appendix E: Observations of Other Conditions

During our investigation by Marlene Betani, P.E., of Gervasio & Assoc., Inc. on March 2 & 4, May 14 & 28, 2015, we took one hundred eleven (111) digital photographs. A digital copy of the photographs has been provided.

Our assignment was limited to determining the cause of the wall cracking and to determine if the cracks represent a risk of structural instability.

## FINDINGS, CONCLUSIONS & RECOMMENDATIONS

The Media Center Building is a two-story brick masonry structure built circa 1917. The building has been remodeled numerous times, and incomplete original building drawings were available for a 1969 structural rehabilitation project and a 1983 building remodel. The roof structure is a wood system with large wood trusses and planed wood rafters. The second floor brick masonry walls and ceiling were removed and access to this unused floor was removed circa 1983. The lobby floor is constructed of concrete over metal form deck on steel joists spaced approximately 3 feet on center. This is not original construction, but it

is not known when the steel joists were installed. There is a crawl space that is approximately 5 feet high beneath the lobby floor. An access hole had to be installed in order for us to investigate the structure in the crawl space area. The floor of the Media Center Offices is concrete floor slab on ground.

In late February, a leak was discovered in an underground water pipe that runs along the south end of the building. Although the water valve was then shut off, water continued to leak under the building on the west end of the Lobby for a few more days until the valve was repaired (Photos A5 & A6). Wet soils at grade were present at a waterline valve/junction box on the west side of the building in a grass landscaped area in line with the broken water line (Photo B35). The water leak saturated the soils in the crawl space below the Lobby. In late February, large cracks developed in the drywall of the Media Center Offices, and the glass windows surrounding the offices began to shift in their frames. Also discovered were cracks in the west exterior wall of the building and the adjacent ramp wall. Smaller cracks were found in the east exterior wall.

The cracks in the Office walls were near the south wall of the Office, which is the north wall of the lobby. This wall supports the north half of the abandoned second level and Lobby floor. Below the Lobby floor, the wall is constructed of red clay brick on a concrete stem wall and foundation.

We reviewed the available building drawings. In 1969, Magadini Associates prepared structural rehabilitation drawings for the building. Included in the drawings is a Foundation Plan showing foundations to be stabilized by pressure grouting. All the foundations in the south part of the building are shown to require pressure grouting except the wall between the Offices and the Lobby. See Appendix B, Sheet F-1.

#### **Site Soils:**

Based on the appearance of the soil in the crawl space and our experience with a property located 0.2 mile directly south of the Media Center Building, the existing soils are clay with moderate to high swell potential and some to extensive additional compression following wetting. This means that the foundations could settle if the foundation soils become wet. We inserted a 4 ft. long fiberglass soil probe into the crawl space soil in 2 places. In one case, the probe could be easily inserted the full 4 ft. length, and in the other case, the probe was inserted 3 ft. 5 in. into the soil (Photo C25). This indicates very soft soils due to water infiltration to a depth below the foundations.

#### **Floor Elevation Survey:**

We performed a floor elevation survey of the Lobby and Office area of the Media Center (Appendix C). The high point of the floor slab in the area we investigated occurs on the slab on ground in the Media Center approximately 30 ft. north of the low spot. The low point was the area at the west entry from the Lobby into the Media Center. The difference in elevation between the low and high points was 1.7 in. We found that there was a 1.5 ft. Office wall crack along the retaining wall that had not been stabilized during the 1969 structural rehabilitation. The Office walls and ceiling near this low area had the most damage.

#### **Crawl Space:**

As noted above, we found wet to very moist soils throughout the crawl space area (Photos A4, A5, B46 - B48). There were numerous vertical and stair step cracks in the brick retaining wall between the Lobby area and the Office area (Photos C21, C24, C28 - C32). None of the cracks appear to be new, but additional movement has likely occurred at them.

#### **Exterior Wall Cracks:**

The cracks in the east and west building walls occur at the jambs of old window openings that were infilled with concrete masonry units during the 1987 remodel (Photos B27 - B30 & B41 - B43). Since the block was not toothed in or interlocked with the original brick units, there is effectively a masonry control joint that opened up when there was some additional settlement of the walls due to moisture infiltration under the foundations. The cracks most noticeable in the masonry ramp wall on the west side which is near the wet area around the junction/valve box (Photos B21 & B31). There are signs of past movement in the sidewalks in this area evidenced by a replaced sidewalk section and grind marks at the sidewalk joints (Photos B21 - B24 & B40).

#### **Interior Wall Cracks:**

There are numerous cracks in the drywall of the Office and Lobby areas of the building (Photos A12 - A17 & A20 - A23). The largest cracks occur in the Office walls that are perpendicular to the north wall of the Lobby. They are in the narrow section of wall at the top and bottom of the windows just a few feet north of the Lobby. The cracks indicate settlement of the north Lobby wall particularly at the west side near where the water line break was discovered. We looked above the ceiling in numerous areas in the Offices and at the surrounding soffits. We looked for, but did not see, signs of structural distress in the roof or unused upper level floor structure at this time.

We conclude that the exterior and interior wall cracking is due to the change in the amount of moisture in the soil under and surrounding the foundations. The water source is the broken water line that runs under the building along the south side. The cracks are not structurally significant.

#### **We recommend the following:**

1. That the soils in the crawl space area be allowed to dry out until a soil probe cannot be inserted into the soil more than a few inches. This could take many months.
2. That after the soil has been allowed to dry out, if settlement of this lightly loaded wall has stopped, then the interior drywall be patched and the window frames be plumbed and leveled before reinstalling the glass. If settlement continues after the walls have dried out, then the walls should be reinforced with steel reinforcement.

Ms. Sarafina Fornara  
July 20, 2015  
G&A Job No. 0250.2 F  
Page 4

3. That the cracks in the north clay brick retaining wall in the crawl space under the Lobby be repointed per Uniform Building Code Standard 21-8 "Pointing of Unreinforced Masonry Walls" (Appendix D).
4. That cracks in the exterior building wall be patched to prevent moisture from entering the building envelope.

This letter is based on the facts and evidence known to us as of this date and may be amended if new facts and/or evidence are presented or discovered.

We appreciate the opportunity to provide this service and welcome any questions.

Sincerely,

GERVASIO & ASSOC., INC.



Marlene Betani, P.E.  
Forensic Structural Engineer

MB:rz


Enclosures

cc: Mike Coppa - Arizona Schools Risk Retention Trust, Inc., via email: [mcoppa@ashtontiffany.com](mailto:mcoppa@ashtontiffany.com)

# APPENDIX A

## FIELD NOTES & PHOTO LOCATION PLANS





GERVASIO & ASSOC. INC.  
CONSULTING ENGINEERS

(602) 285-1720 • 77 East Thomas Road, Suite 120  
PHOENIX, ARIZONA 85012-3115


Date 5-11-15

Job No. 09507

By MB

Sheet No. 1

FIELD NOTES



GERVASIO & ASSOC. INC.  
CONSULTING ENGINEERS

(602) 285-1720 • 77 East Thomas Road, Suite 120  
PHOENIX, ARIZONA 85012-3115


Date 5-14-15

Job No. 07501

By AA-B

Sheet No. 2


FIELD NOTES




(3)




(2)



(1)



(6)



(5)



(4)

GERVASIO & ASSOC. INC.  
CONSULTING ENGINEERS

(602) 285-1720 • 77 East Thomas Road, Suite 120  
PHOENIX, ARIZONA 85012-3115

Date 5-28-15


Job No. 075077

By MPB

Sheet No. 1

FIELD NOTES

Joist brg depth =  $2\frac{1}{2}$



## APPENDIX B

STRUCTURAL REHABILITATION DRAWINGS  
BY MAGADINI ASSOCIATES DATED 1/28/69

# SECTION 4 FOUNDATION STABILIZATION

1. The purpose of this section is to provide for the stabilization of the foundation of the building shown on the drawings. The foundation shall be stabilized by the use of the following methods:

1. The foundation shall be stabilized by the use of the following methods:
2. The foundation shall be stabilized by the use of the following methods:
3. The foundation shall be stabilized by the use of the following methods:

2. The foundation shall be stabilized by the use of the following methods:

1. The foundation shall be stabilized by the use of the following methods:
2. The foundation shall be stabilized by the use of the following methods:
3. The foundation shall be stabilized by the use of the following methods:

3. The foundation shall be stabilized by the use of the following methods:

1. The foundation shall be stabilized by the use of the following methods:
2. The foundation shall be stabilized by the use of the following methods:
3. The foundation shall be stabilized by the use of the following methods:

4. The foundation shall be stabilized by the use of the following methods:

1. The foundation shall be stabilized by the use of the following methods:
2. The foundation shall be stabilized by the use of the following methods:
3. The foundation shall be stabilized by the use of the following methods:

5. The foundation shall be stabilized by the use of the following methods:

1. The foundation shall be stabilized by the use of the following methods:
2. The foundation shall be stabilized by the use of the following methods:
3. The foundation shall be stabilized by the use of the following methods:

6. The foundation shall be stabilized by the use of the following methods:

1. The foundation shall be stabilized by the use of the following methods:
2. The foundation shall be stabilized by the use of the following methods:
3. The foundation shall be stabilized by the use of the following methods:

7. The foundation shall be stabilized by the use of the following methods:

1. The foundation shall be stabilized by the use of the following methods:
2. The foundation shall be stabilized by the use of the following methods:
3. The foundation shall be stabilized by the use of the following methods:

8. The foundation shall be stabilized by the use of the following methods:

1. The foundation shall be stabilized by the use of the following methods:
2. The foundation shall be stabilized by the use of the following methods:
3. The foundation shall be stabilized by the use of the following methods:

9. The foundation shall be stabilized by the use of the following methods:

1. The foundation shall be stabilized by the use of the following methods:
2. The foundation shall be stabilized by the use of the following methods:
3. The foundation shall be stabilized by the use of the following methods:

10. The foundation shall be stabilized by the use of the following methods:

1. The foundation shall be stabilized by the use of the following methods:
2. The foundation shall be stabilized by the use of the following methods:
3. The foundation shall be stabilized by the use of the following methods:

11. The foundation shall be stabilized by the use of the following methods:

1. The foundation shall be stabilized by the use of the following methods:
2. The foundation shall be stabilized by the use of the following methods:
3. The foundation shall be stabilized by the use of the following methods:

12. The foundation shall be stabilized by the use of the following methods:

1. The foundation shall be stabilized by the use of the following methods:
2. The foundation shall be stabilized by the use of the following methods:
3. The foundation shall be stabilized by the use of the following methods:


13. The foundation shall be stabilized by the use of the following methods:

1. The foundation shall be stabilized by the use of the following methods:
2. The foundation shall be stabilized by the use of the following methods:
3. The foundation shall be stabilized by the use of the following methods:

14. The foundation shall be stabilized by the use of the following methods:

1. The foundation shall be stabilized by the use of the following methods:
2. The foundation shall be stabilized by the use of the following methods:
3. The foundation shall be stabilized by the use of the following methods:

15. The foundation shall be stabilized by the use of the following methods:



FOUNDATION PLAN  
SCALE: 1/8" = 1'-0"


1. The foundation shall be stabilized by the use of the following methods:
2. The foundation shall be stabilized by the use of the following methods:
3. The foundation shall be stabilized by the use of the following methods:
4. The foundation shall be stabilized by the use of the following methods:
5. The foundation shall be stabilized by the use of the following methods:
6. The foundation shall be stabilized by the use of the following methods:
7. The foundation shall be stabilized by the use of the following methods:
8. The foundation shall be stabilized by the use of the following methods:
9. The foundation shall be stabilized by the use of the following methods:
10. The foundation shall be stabilized by the use of the following methods:
11. The foundation shall be stabilized by the use of the following methods:
12. The foundation shall be stabilized by the use of the following methods:
13. The foundation shall be stabilized by the use of the following methods:
14. The foundation shall be stabilized by the use of the following methods:
15. The foundation shall be stabilized by the use of the following methods:



M. MAGADINI ASSOCIATES  
CONSULTING ENGINEERS  
PHOENIX, ARIZONA


STRUCTURAL REHABILITATION FOR  
AUTOTRUCK & BUS GARAGE  
ALUMINUM VEHICLE LIFT, DRIVE, STAY, DO  
PHOENIX, ARIZONA






SEE DRAWING US 2-4 FOR GENERAL STRUCTURAL NOTES.



1200F PLAN  
SCALE - 1/8" = 1'-0"



200D NAILING SCHEDULE



SECTION THRU 4/5-1



BASE BID - SOUTH WALL BEAM

STRUCTURAL REHABILITATION FOR  
AUDITORIUM AT UNIT 1 SCHOOL  
ORIGINAL BLDG. 2000, DOW 40

CANADIAN  
ARCHITECTS


VARNNEY, BOSTON & SYDOROK ASSOCIATES  
CONSULTING ARCHITECTS I.A.A.  
TORONTO

S-1

# APPENDIX C

FLOOR ELEVATION SURVEY  
BY GERVASIO & ASSOC., INC. DATED 3/4/15

# Floor Elevation Survey



Landmark Elem. School - Media Center  
G&A Job No. 0250.2  
Floor Elevation Survey by MB on 3/4/11  
Units = inches

Manometer reading  
Location Indicated by

NOTE

# APPENDIX D

UNIFORM BUILDING CODE STANDARD 21-8  
"POINTING OF UNREINFORCED MASONRY WALLS"

UNIFORM BUILDING CODE STANDARD 21-8  
POINTING OF UNREINFORCED MASONRY WALLS

Construction Specification of the International Conference of Building Officials

See Appendix Chapter 1, Section A106.3.3.2,  
*Uniform Code for Building Conservation*

**SECTION 21.001 — SCOPE**

Pointing of deteriorated mortar joints when required by the *Uniform Code for Building Conservation* shall be in accordance with this standard.

**SECTION 21.002 — JOINT PREPARATION**

The old or deteriorated mortar joint shall be cut out, by means of a toothing chisel or nonimpact power tool, to a uniform depth of  $\frac{3}{4}$  inch (19 mm) until sound mortar is reached. Care shall be taken not to damage the brick edges. After cutting is complete, all loose material shall be removed with a brush, air or water stream.

**SECTION 21.003 — MORTAR PREPARATION**

The mortar mix shall be Type N or Type S proportioned as required by the construction specifications. The pointing mortar

shall be prehydrated by first thoroughly mixing all ingredients dry and then mixing again, adding only enough water to produce a damp unworkable mix which will retain its form when pressed into a ball. The mortar shall be kept in a damp condition for one and one-half hours; then sufficient water shall be added to bring it to a consistency that is somewhat drier than conventional masonry mortar.

**SECTION 21.004 — PACKING**

The joint into which the mortar is to be packed shall be damp but without freestanding water. The mortar shall be tightly packed into the joint in layers not exceeding  $\frac{1}{4}$  inch (6.4 mm) in depth until it is filled; then it shall be tooled to a smooth surface to match the original profile.

# APPENDIX E

## OBSERVATIONS OF OTHER CONDITIONS



## OBSERVATIONS OF OTHER CONDITIONS

While at the Landmark Elementary School Media Center, we observed some conditions in the crawl space area below the Lobby that are structural concerns, but unrelated to the purpose of our site investigation and not included in our scope of work. These conditions include:

### 1. Deteriorating Concrete Piers:

At the south wall of the Lobby, the floor joists are supported on a narrow concrete beam that has been poured against the original brick retaining wall. The concrete beam is supported at approximately 10 ft. on center by narrow concrete piers. The edges of the lower part of these piers are cracked due to corroded reinforcing steel. The corrosion will accelerate and can lead to loss of support of the concrete beam. The corrosion indicates that the piers are absorbing moisture from the crawl space soil. The amount of corrosion and subsequent concrete cracking indicates that the crawl space soils have been moist for a long time.

**We recommend** that the narrow concrete beam be supported by steel posts installed adjacent to the existing concrete piers between the existing beam and continuous wall footing. These support posts and their connections should be designed by a qualified Structural Engineer.

### 2. Corroded Metal Deck:

The existing metal deck under the Lobby floor slab is corroded throughout. This metal deck is likely a form only because welded wire fabric reinforcing was found in the floor slab.

**We recommend** that the crawl space be ventilated to reduce the humidity in the space. The Building Code requires that all crawl spaces be ventilated.

### 3. Steel Joists Bearing on Wood Blocks:

Many of the existing steel joists that support the Lobby floor are bearing on wood shim blocks rather than on cementitious material such as drypack or non-shrink grout. At present, the wood does not show signs of decay, or excessive compression.

**We recommend** that the joists be shored, the wood shim blocks removed, and that the joist bearings be drypacked.



Glendale Elementary School District SFB Projects: Construction Cost Estimates

BRG: Project: Scope: Updated 9/1/16 Cost Estimate:

070440101-1001-009-BRG	Landmark Structural		
	Phase 2	Gervasio report regarding media center cracks	\$ 150,000.00
		Gervasio report regarding gym cracks	\$ 20,000.00
		Gervasio report regarding column cracks	\$ 25,000.00
		Estimated Phase 2 Subtotal	\$ 195,000.00
		Estimated Total Repair:	\$ 195,000.00



# Glendale Elementary School District SFB Projects: Construction Cost Estimates

BRG: Project: Scope: Updated 9/1/16 Cost Estimate:

070440111-9999-004-BRG	Challenger Reseal		
	<b>Phase 1</b>	Sister wall: this is inclusive of footings, spoil removal, backfill, drilling, doweling, install and everything in the details and put back like we were never there.	\$ 870,756.00
		Adjustments required for sister wall installation; extend electrical, downspouts, relocate irrigation boxes and other conflicts	\$ 225,296.00
		<b>Estimated Phase 1 Subtotal</b>	<b>\$ 1,096,052.00</b>
	<b>Phase 2</b>	Installation of masonry control joints/repair CMU	\$ 60,000.00
		Beam bearing cracks	\$ 30,000.00
		Riddle blockfill of new masonry and coating of Drylok extreme at exposed footing	\$ 11,000.00
		<b>Estimated Phase 2 Subtotal</b>	<b>\$ 101,000.00</b>
		<b>Estimated Total Repair:</b>	<b>\$ 1,197,052.00</b>

August 26, 2016



Mr. Greg Gilliam  
Director of Maintenance & Operations  
Glendale Elementary School District #40  
Support Services  
7015 W. Maryland Avenue  
Glendale, AZ 85303

Robert L Pian, AIA  
William R Pittenger, RA, CSI  
Mark A Davenport, AIA, LEED AP  
Herb W Schneider, FAIA  
Howell Lewis Shay, AIA

**RE: Glendale Elementary School District #40  
SFB Corrections at Challenger School – Additional Services Request**  
SPS+ Architects Fee Proposal 1535B.2  
GESD Purchase Order 3601552  
**SFB Project # 070440111-999-004-BRG**

Dear Mr. Gilliam:

Thank you for the opportunity to work with you on your SFB Corrections at the above referenced School. We understand this will be an SFB funded project using Building Renewal Grants. Thank you in advance for your consideration of our additional services request.

Additional Services Scope of work:

Structural remediation in accordance with the attached coversheet from our structural engineer Bixler and associates. Please see below for an executive summary:

- Structural: Our engineer agrees with the Gervasio reports for CMU cracking and structural repairs. This includes painting at areas of repair.
- Weatherization project conditions: There was a significant amount of damage discovered for the reinforcing steel near the bottom of the walls. When you add the moisture conditions present, the amount of cracking, the fact that basically all the holes that had reinforcing, the reinforcing was approximately 33% to 66% rusted. In essence, at all those cracks along grade, the CMU face shells are basically delaminated, so the old 8" wall is now 5-6" or 4" at that point and then obviously the wall that is not close to current code now, is much worse. The engineer is unable to perform calculations without knowing to what extent the steel has delaminated. Therefore, I concur with the engineer and recommend to move forward with these repairs as soon as possible and brace immediately. In addition to civil projects that may be happening at these sites, we recommend removing grass and irrigation within 5 feet of the buildings.

Fee Proposal: \$41,088

Fee includes Architectural and Structural services for the following:

- Coordination of immediate implementation of wall bracing.
- Construction documents and construction administration utilizing a district procured contractor of the scope of work described above and attached.
- Special structural inspections during construction administration.
- Reimbursable expenses for printing, travel, etc.

Please let me know if you have any comments regarding our proposal. We are anticipating this proposal being approved at the September 7<sup>th</sup>, 2016 SFB board meeting.

Sincerely,



SPS+ ARCHITECTS, LLP

A handwritten signature in black ink, consisting of a stylized 'M' followed by a long horizontal stroke that curves slightly upwards at the end.

Mark Davenport, AIA, LEED AP BD&C  
Partner

enclosure

Cc: Mike Barragan, David Kennon, Terry Tower, Jennifer Bowen



# DAVID BIXLER & ASSOCIATES

## Structural Engineering

August 23, 2016

### VISION

Our vision is  
to be recognized  
throughout the  
Southwest as the  
leader in structural  
engineering.

Mark Davenport AIA, CEFPI, LEED AP, BD+C  
SPS+ ARCHITECTS LLP  
8681 E. Via de Negocio  
Scottsdale, AZ 85258

**Re: Challenger Middle School  
Glendale, AZ**

### COMMITMENT

Dear Mr. Davenport:

We are committed to  
■ technological  
leadership  
■ innovative and cost-  
effective solutions  
■ quality work  
■ client satisfaction.

Per your request, we have visited the Challenger Middle School site on several occasions. We have also reviewed the reports from both Speedie and Associates, and Gervasio and Associates attached to the end of this report, along with pictures from our site visits during the CMU removal to investigate the reinforcing and typical pictures of the type of cracking along the buildings. We have also reviewed the existing plans of the buildings which we have received. The purpose of this report is to review the conditions of the existing buildings along with the reports prepared by other consultants and to recommend a plan of action going forward on the best course of action to remedy the deficient areas.

The buildings are typically steel and wood framed roofs bearing on CMU exterior walls and concrete spread footings.

### VALUES

Our team delivers  
integrity  
service  
collaboration  
quality  
efficiency

Based on the surface penetrating radar investigations Speedie and Associates performed the vertical reinforcing appears to be installed for the most part correctly, however there are a few areas where you can see from the pictures that the reinforcing appears to stop in the middle of the wall and then sometimes starts again. This could be due to a faulty reading or it could be that is the way it was installed but based off of their radar findings there is nothing that is significantly different than what we would expect.

Based on the soils investigations performed by Speedie and Associates, there does not appear to be a specific cause of the masonry distress due to the soils themselves, except the fact that the soil is very moist. The moisture fluctuations in the soils will have a tendency to cause continuous movement, which will induce stresses on the buildings and this sometimes will



# DAVID BIXLER & ASSOCIATES

## Structural Engineering

result in cracks in the CMU. My understanding is that there is currently a project in place that will solve or reduce the amount of moisture in the soil and will divert the water away from the buildings.

There was a report done by Gervasio and Associates that we received dated on October 17, 2014, dealing mostly with cracks in the east exterior of Building D at the vestibule. Gervasio maintains that the cracks are due mostly to misplaced masonry control joints. Based on the additional information we have ascertained, I would agree with their conclusion. The repairs that they recommended were to saw-cut new masonry control joints into the walls and tuck point and repair/replace the cracked masonry. This is the repair method I would recommend in this area as well.

From our review of the CMU demolition and our cursory review of the buildings in general, we discovered numerous cracking and rusted reinforcing. The footings in these locations however appeared to be in good condition

From the four holes that were opened up to expose the reinforcing we found rusted and deteriorated vertical and horizontal reinforcing in each location. There was also standing water in the holes showing the amount of saturation these walls are going through along with a picture of sand bags next to a doorway further showing the extent of the moisture issues at this school.

From our visual inspection we noticed several different types of cracks and too many to document all of them however. They basically fall into 3 categories:

1. There were several areas where there are shrinkage cracks most likely due to insufficient or improper locations of masonry control joints or improperly installed masonry control joints (see photographs 1, 2, 4 and 7 on building 1, photos 1, 5 and 12 on building 2, photo 6 on building 6 and photo 4 on building 7). While these are not structural in nature they will affect the water tightness of the building and therefore I recommend that new masonry control joints be installed and for the CMU in these areas to be tuck pointed and repaired or replaced as applicable. There were approximately 10-15 locations throughout the school where this occurred.
2. There were some cracks at beam bearing locations where it appears that the beam was not allowed thermal movement and has cracked the CMU at the bearing locations (see photo 7 on building 6 and photo 3 on building 7). These cracks are structural in nature due to the fact they are supporting the beam ends and therefore should be repaired in a timely manner. The repair for these would be a combination of adding a masonry control joints and removing and reinstalling the beam and bearing plate in a manner that would allow it to move as the temperature changes such as a neoprene pad beneath the beam. There are approximately 6 locations that this would be required.





# DAVID BIXLER & ASSOCIATES

## Structural Engineering

3. The remaining photos appear to be related to moisture and the rusting of the reinforcing in the CMU. Since reinforcing when it rusts can grow to over 400% of its original size, it appears that the reinforcing has rusted and expanded and has cracked the CMU. This causes the face shells to delaminate and then the CMU is essentially reduced in size and therefore reduced in strength. There is no real way to determine the loss in strength without knowing the exact thickness of the delaminated CMU. This is a very old building that does not comply with the current building codes, and additionally, there is reduced strength of the existing wall. The reduction in strength could easily range from 33%-90%. In addition, there is no real way to eliminate moisture from entering into the cracks in the CMU, which will continue to make the condition worse. There is no easy or accurate way to determine the extents of the rusting in the CMU without removing the face shells and investigating the reinforcing, as we did in those four locations. The repair for these locations would be extremely expensive, but would entail removing the CMU at the cracked locations, and then removing and replacing the rusted reinforcing with new reinforcing, grout and CMU. This would need to be done in an explorative manner, where you start at each of the cracks, and then expand outward until you get to undamaged CMU and reinforcing. Therefore, there is no real way to determine the damage extents, but due to the moisture conditions and the amount of cracking, I would not be surprised if 50%-75% of the length of the walls are damaged at grade in this manner. Therefore, the CMU walls should be braced immediately until the repairs are complete.

If the decision is to repair the school, then this should start immediately, and we should brace the CMU walls until the repairs are completed. Without knowing the extent of the damage, it is extremely difficult to determine how the walls will perform as the reinforcing continues to rust and the walls continue to worsen.

While it is extremely difficult to provide any budgetary numbers due to the uncertainty of the full scope and amount of damage, we estimate the following corresponding to the item numbers above:

1) Bracing of CMU walls:	\$70,000
2) Installation of masonry control joints and repair of damaged CMU:	\$60,000
3) Beam bearing cracks:	\$30,000
4) Repair of the cracked CMU and rusted reinforcing:	\$400,000
5) Gervasio crack repair:	\$20,000

Please understand that this report represents a professional opinion based upon the results of our limited observations, and past experience with similar conditions. Our study was strictly limited to visual observations as stated above. This report is not intended to be a complete or comprehensive study of the structure. We have not reviewed, nor have we been asked to review, the capacity of the existing structure per the current code. Our work has been performed in accordance with generally accepted principles and practices of structural engineering.



# DAVID BIXLER & ASSOCIATES

## Structural Engineering


We cannot be responsible for any future changes in the condition of the structure. No warranty is provided, either expressed or implied.


If there are any additional concerns or questions, please feel free to contact our office. Thank you for the opportunity to assist you on this project.

Sincerely,

*David Bixler*

David Bixler, PE, SE President  
David Bixler & Associates, PLLC





**NOTES:**

1. EXISTING MASONRY WALL.
2. EXISTING CONCRETE FOOTING.
3. EXISTING CONCRETE SLAB.
4. CONCRETE SLAB OR FINISHED GRADE AS OCCURS.
5. CONTINUOUS FULLY GROUTED BOND BEAM REINFORCED W/1-#4 CONTINUOUS.
6. 6" CONCRETE MASONRY WALL.
7. CAP BLOCK PER ARCHITECTURAL DRAWINGS.
8. WHERE "H" IS 12'-0" OR LESS, REINFORCE W/#4 VERTICALS @ 32"O.C. WHERE "H" IS GREATER THAN 12'-0", REINFORCE W/#4 VERTICALS @ 16"O.C.
9. #4 DOWELS WITH STD. 90° HOOK @ 48"O.C. MAX. DRILL AND EPOXY INTO EXISTING FULLY GROUTED CELL W/4" MIN. EMBED.
10. REMOVE DELAMINATED & CRACKED CMU & GROUT SOLID.
11. MORTAR COLLAR JOINT SOLID.
12. CONCRETE FOOTING.
13. 1-#4 CONTINUOUS.
14. #4 DOWELS WITH STD. 90° HOOK @ 18"O.C. MAX. DRILL AND EPOXY INTO EXISTING FOOTING W/4" MIN. EMBED.

1

SECTION

N.T.S.



**David Bixler & Associates**  
Structural Engineering

8360 East Raintree Drive, Suite 110  
Scottsdale, Arizona 85260

Office: (480) 219-2886 Fax: (480) 588-8584  
www.dbaaeng.com

UNLESS THIS DRAWING IS SIGNED AND SEALED BY A LICENSED STRUCTURAL ENGINEER, IT IS A PRELIMINARY DESIGN AND SHALL NOT BE USED FOR CONSTRUCTION.

**CHALLENGER SCHOOL**  
6095 WEST MARYLAND AVENUE  
GLENDALE, AZ 85303




DRAWN BY:	ERB
CHECKED BY:	WDB
JOB NO:	16.096
PRINTED:	08.31.2016

**SSK1**







**NOTES:**

1. EXISTING MASONRY WALL.
2. EXISTING CONCRETE FOOTING.
3. EXISTING CONCRETE SLAB.
4. CONCRETE SLAB OR FINISHED GRADE AS OCCURS.
5. CONTINUOUS FULLY GROUTED BOND BEAM REINFORCED W/1-#4 CONTINUOUS.
6. 6" CONCRETE MASONRY WALL.
7. CAP BLOCK PER ARCHITECTURAL DRAWINGS.
8. WHERE "H" IS 12'-0" OR LESS, REINFORCE W/#4 VERTICALS @ 32"O.C. WHERE "H" IS GREATER THAN 12'-0", REINFORCE W/#4 VERTICALS @ 16"O.C.
9. #4 DOWELS WITH STD. 90° HOOK @ 48"O.C. MAX. DRILL AND EPOXY INTO EXISTING FULLY GROUTED CELL W/4" MIN. EMBED.
10. REMOVE DELAMINATED & CRACKED CMU & GROUT SOLID.
11. MORTAR COLLAR JOINT SOLID.

2

SECTION

N.T.S.




**David Bixler & Associates**  
Structural Engineering

8360 East Raintree Drive, Suite 110  
Scottsdale, Arizona 85260  
Office: (480) 219-2886 Fax: (480) 588-8584  
www.dbaaeng.com

UNLESS THIS DRAWING IS SIGNED AND SEALED BY A LICENSED STRUCTURAL ENGINEER, IT IS A PRELIMINARY DESIGN AND SHALL NOT BE USED FOR CONSTRUCTION.

**CHALLENGER SCHOOL**  
6095 WEST MARYLAND AVENUE  
GLENDALE, AZ 85303



DRAWN BY:	ERB
CHECKED BY:	WDB
JOB NO:	16.096
PRINTED:	08.31.2016

**SSK2**





# STRUCTURAL CALCULATIONS FOR CHALLENGER ELEMENTARY SCHOOL WALL REPAIRS

DBAA Job No. 16.096

August 31, 2016


## PREPARED FOR:

Jennifer Bowen, Director of Design

SPS+ Architects LLP

[Jbowen@spsplusarchitects.com](mailto:Jbowen@spsplusarchitects.com)


480.544.5851



## PREPARED BY:

DAVID BIXLER & ASSOCIATES  
STRUCTURAL ENGINEERING  
8360 E. RAINTREE DR., SUITE 110  
SCOTTSDALE, AZ 85260  
PHONE: (480) 219-2886  
[david.bixler@dbaaeng.com](mailto:david.bixler@dbaaeng.com)  
[www.dbaaeng.com](http://www.dbaaeng.com)





DAVID  
**BIXLER**  
& ASSOCIATES

$$> 12' \\ 34PSP(24' / 2) = 360'$$

$$n = 360' (3' - 4') = 1198'$$

$$Mu = 1.2 (1198') = 1438'$$

Project

Project #:

Prepared by:

Date:

Subject:

Sheet: of:

> 12' 0"

12' 0" MAX

DRILL & GROUT  
#4 DOWN WITH SPD  
90° HOSE (4" DIA)  
= 4' 8" OK MAX

CAD BLOCK  
2' 0" TO 1' 0"

3' - 4" STRIP

CONT. BOVA BORN W/

6" CONU W/

#4 @ 32"

#4 @ 16"

#5 SD  
90° HOSE  
5' 0" DIA

34PSP

$$34PSP(12' / 2) = 204'$$

$$204' (3' - 4') = 680'$$

$$680' (1.2) = 816'$$

REMOVE DECKING  
& CRACKED CONCR  
\* GROUT SAND

FIN COLLAR  
IT SAND

18" MAX


CONT #4

SPD

#4 DOWN W/ SPD  
90° HOSE @ 18" OK








DAVID  
**BIXLER**  
& ASSOCIATES

Project: \_\_\_\_\_  
Project #: \_\_\_\_\_  
Prepared by: \_\_\_\_\_  
Date: \_\_\_\_\_  
Subject: \_\_\_\_\_

Sheet:    of:





# Wind Analysis for Low-rise Building, Based on ASCE 7-2010

## INPUT DATA

Exposure category (B, C or D, ASCE 7-10 26.7.3)

Importance factor (ASCE 7-10 Table 1.5-2)

Basic wind speed (ASCE 7-10 26.5.1 or 2012 IBC)

Topographic factor (ASCE 7-10 26.8 & Table 26.8-1)

Building height to eave


Building height to ridge

Building length

Building width

Effective area of components (or Solar Panel area)

C  
I<sub>w</sub> = 1.00 for all Category  
V = 120 mph  
K<sub>zt</sub> = 1 Flat  
h<sub>e</sub> = 10 ft  
h<sub>r</sub> = 10 ft  
L = 100 ft  
B = 50 ft  
A = 33 ft<sup>2</sup>



## DESIGN SUMMARY

Max horizontal force normal to building length, L, face

Max horizontal force normal to building length, B, face

Max total horizontal torsional load

Max total upward force

= 19.12 kips, SD level (LRFD level), Typ.  
= 9.93 kips  
= 222.03 ft-kips  
= 97.43 kips

## ANALYSIS

### Velocity pressure

$$q_h = 0.00256 K_h K_{zt} K_d V^2 = 26.63 \text{ psf}$$

where:  $q_h$  = velocity pressure at mean roof height, h. (Eq. 28.3-1 page 298 & Eq. 30.3-1 page 316)

$K_h$  = velocity pressure exposure coefficient evaluated at height, h, (Tab. 28.3-1, pg 299)

= 0.85

$K_d$  = wind directionality factor. (Tab. 26.6-1, for building, page 250)

= 0.85

h = mean roof height

= 10.00 ft

< 60 ft, [Satisfactory]

(ASCE 7-10 26.2.1)

< Min (L, B), [Satisfactory]

(ASCE 7-10 26.2.2)

### Design pressures for MWFRS

$$p = q_h [(G C_{pf}) - (G C_{pi})]$$

where: p = pressure in appropriate zone. (Eq. 28.4-1, page 298).

$p_{min} = 16 \text{ psf}$  (ASCE 7-10 28.4.4)

$G C_{pf}$  = product of gust effect factor and external pressure coefficient, see table below. (Fig. 28.4-1, page 300 & 301)

$G C_{pi}$  = product of gust effect factor and internal pressure coefficient. (Tab. 26.11-1, Enclosed Building, page 258)

= 0.18 or -0.18


a = width of edge strips, Fig 28.4-1, note 9, page 301,  $\text{MAX}[\text{MIN}(0.1B, 0.1L, 0.4h), \text{MIN}(0.04B, 0.04L), 3] = 4.00 \text{ ft}$

### Net Pressures (psf), Basic Load Cases


Surface	Roof angle $\theta = 0.00$			Roof angle $\theta = 0.00$		
	$G C_{pf}$	Net Pressure with		$G C_{pf}$	Net Pressure with	
		(+ $G C_{pi}$ )	(- $G C_{pi}$ )		(+ $G C_{pi}$ )	(- $G C_{pi}$ )
1	0.40	5.86	15.45	-0.45	-16.78	-7.19
2	-0.69	-23.17	-13.58	-0.69	-23.17	-13.58
3	-0.37	-14.65	-5.06	-0.37	-14.65	-5.06
4	-0.29	-12.52	-2.93	-0.45	-16.78	-7.19
5				0.40	5.86	15.45
6				-0.29	-12.52	-2.93
1E	0.61	11.45	21.04	-0.48	-17.58	-7.99
2E	-1.07	-33.29	-23.70	-1.07	-33.29	-23.70
3E	-0.53	-18.91	-9.32	-0.53	-18.91	-9.32
4E	-0.43	-16.25	-6.66	-0.48	-17.58	-7.99
5E				0.61	11.45	21.04
6E				-0.43	-16.25	-6.66

### Net Pressures (psf), Torsional Load Cases

Surface	Roof angle $\theta = 0.00$		
	$G C_{pf}$	Net Pressure with	
		(+ $G C_{pi}$ )	(- $G C_{pi}$ )
1T	0.40	1.46	3.86
2T	-0.69	-5.79	-3.40
3T	-0.37	-3.66	-1.27
4T	-0.29	-3.13	-0.73
Surface	Roof angle $\theta = 0.00$		
	$G C_{pf}$	Net Pressure with	
		(+ $G C_{pi}$ )	(- $G C_{pi}$ )
5T	0.40	1.46	3.86
6T	-0.29	-3.13	-0.73




Load Case A (Transverse)




Load Case B (Longitudinal)

### Basic Load Cases



Load Case A (Transverse)



Load Case B (Longitudinal)

### Torsional Load Cases



Title Block Line 1  
 You can change this area  
 using the "Settings" menu item  
 and then using the "Printing &  
 Title Block" selection.  
 Title Block Line 6

Project Title:  
 Engineer:  
 Project Descr:

Project ID:

Printed 31 AUG 2016 1:45PM

File = \\dbaa-sv2\projects\16096 Challenger Middle School\Engineering\16096 challenger.ec6  
 ENERCALC, INC. 1983-2016, Build 6.16.6.7, Ver:6.16.6.7

## Masonry Slender Wall

Lic. #: KW-06009174

Licensee: DAVID BIXLER AND ASSOCIATES

Description: equivalent cantilevered wall in front of existing wall

### Code References

Calculations per ACI 530-11, IBC 2012, CBC 2013, ASCE 7-10

Load Combinations Used: ASCE 7-10

### General Information

Calculations per ACI 530-11, IBC 2012, CBC 2013, ASCE 7-10


Construction Type: Grouted Hollow Concrete Masonry

F'm	=	1.50 ksi	Nom. Wall Thickness	6 in	Temp Diff across thickness	=	deg F
Fy - Yield	=	60.0 ksi	Actual Thickness	5.625 in	Min Allow Out-of-plane Defl Ratio	=	0
Fr - Rupture	=	61.0 psi	Rebar "d" distance	3.8125 in	Minimum Vertical Steel %	=	0.0020
Em = f'm *	=	900.0	Lower Level Rebar . . .				
Max % of ρ bal.	=	0.1106	Bar Size	# 4			
Grout Density	=	140 pcf	Bar Spacing	32.0 in			
Block Weight		Normal Weight					
Wall Weight	=	47.0 psf					
Wall is grouted at rebar cells only							

### One-Story Wall Dimensions

A Clear Height	=	4.660 ft
B Parapet height	=	0.0 ft

Wall Support Condition Top & Bottom Pinned



### Lateral Loads

Wind Loads:

Full area WIND load 34.0 psf

Seismic Loads:

Wall Weight Seismic Load Input Method:

Direct entry of Lateral Wall Weight

Seismic Wall Lateral Load

0.0 psf

Fp 1.0 = 0.0 psf

(Applied to full "STRIP Width")

	D	Lr	L	E	W	Endpoints from Base top bottom	
Distributed Lateral Load	0.0	0.0	0.0	0.0	4.0 k/ft	4.660 3.660 k/ft	





Title Block Line 1  
 You can change this area  
 using the "Settings" menu item  
 and then using the "Printing &  
 Title Block" selection.  
 Title Block Line 6

Project Title:  
 Engineer:  
 Project Descr:

Project ID:

Printed: 31 AUG 2016 1:45PM

## Masonry Slender Wall

File = \\dbaa-sv2\projects\16096 Challenger Middle School\Engineering\16096 challenger.ec6

ENERCALC, INC. 1983-2016, Build:6.16.6.7, Ver:6.16.6.7

Lic. # : KW-06009174

Licensee : DAVID BIXLER AND ASSOCIATES

Description : equivalent cantilevered wall in front of existing wall

### Design Maximum Combinations - Deflections

Results reported for "Strip Width" = 12 in.

Load Combination	Axial Load	Moment Values		Stiffness		Deflections	
	Pu k	Mcr k-ft	Mactual k-ft	I gross in <sup>4</sup>	I cracked in <sup>4</sup>	I effective in <sup>4</sup>	Deflection in
	0.000	0.00	0.00	0.00	0.00	0.000	0.0
W Only at 2.64 to 2.80	0.000	0.26	0.92	142.30	16.58	16.657	0.138
	0.000	0.00	0.00	0.00	0.00	0.000	0.0
	0.000	0.00	0.00	0.00	0.00	0.000	0.0

### Reactions - Vertical & Horizontal

Results reported for "Strip Width" = 12 in.

Load Combination	Base Horizontal	Top Horizontal	Vertical @ Wall Base
+D+H	0.0 k	0.00 k	0.219 k
+D+L+H	0.0 k	0.00 k	0.219 k
+D+Lr+H	0.0 k	0.00 k	0.219 k
+D+S+H	0.0 k	0.00 k	0.219 k
+D+0.750Lr+0.750L+H	0.0 k	0.00 k	0.219 k
+D+0.750L+0.750S+H	0.0 k	0.00 k	0.219 k
+D+0.60W+H	0.2 k	1.89 k	0.219 k
+D+0.70E+H	0.0 k	0.00 k	0.219 k
+D+0.750Lr+0.750L+0.450W+H	0.2 k	1.42 k	0.219 k
+D+0.750L+0.750S+0.450W+H	0.2 k	1.42 k	0.219 k
+D+0.750L+0.750S+0.5250E+H	0.0 k	0.00 k	0.219 k
+0.60D+0.60W+0.60H	0.2 k	1.89 k	0.131 k
+0.60D+0.70E+0.60H	0.0 k	0.00 k	0.131 k
D Only	0.0 k	0.00 k	0.219 k
Lr Only	0.0 k	0.00 k	0.000 k
L Only	0.0 k	0.00 k	0.000 k
S Only	0.0 k	0.00 k	0.000 k
W Only	0.4 k	3.15 k	0.000 k
E Only	0.0 k	0.00 k	0.000 k
H Only	0.0 k	0.00 k	0.000 k



# Wind Analysis for Low-rise Building, Based on ASCE 7-2010

## INPUT DATA

Exposure category (B, C or D, ASCE 7-10 26.7.3)

Importance factor (ASCE 7-10 Table 1.5-2)

Basic wind speed (ASCE 7-10 26.5.1 or 2012 IBC)

Topographic factor (ASCE 7-10 26.8 & Table 26.8-1)

Building height to eave


Building height to ridge

Building length

Building width

Effective area of components (or Solar Panel area)

C  
 $I_w = 1.00$  for all Category  
 $V = 120$  mph  
 $K_{zt} = 1$  Flat  
 $h_e = 20$  ft  
 $h_r = 20$  ft  
 $L = 100$  ft  
 $B = 50$  ft  
 $A = 140$  ft<sup>2</sup>



## DESIGN SUMMARY

Max horizontal force normal to building length, L, face

Max horizontal force normal to building length, B, face

Max total horizontal torsional load

Max total upward force

= 40.89 kips, SD level (LRFD level), Typ.  
= 21.43 kips  
= 492.60 ft-kips  
= 103.92 kips

## ANALYSIS

### Velocity pressure

$$q_h = 0.00256 K_h K_{zt} K_d V^2 = 28.20 \text{ psf}$$

where:  $q_h$  = velocity pressure at mean roof height, h. (Eq. 28.3-1 page 298 & Eq. 30.3-1 page 316)

$K_h$  = velocity pressure exposure coefficient evaluated at height, h, (Tab 28.3-1, pg 299)

$K_d$  = wind directionality factor. (Tab. 26.6-1, for building, page 250)

h = mean roof height

= 0.90

= 0.85

= 20.00 ft

< 60 ft, [Satisfactory]

(ASCE 7-10 26.2.1)

< Min (L, B), [Satisfactory]

(ASCE 7-10 26.2.2)

### Design pressures for MWFRS

$$p = q_h [(G C_{pf}) - (G C_{pi})]$$

where: p = pressure in appropriate zone. (Eq. 28.4-1, page 298).

$p_{min} = 16$  psf (ASCE 7-10 28.4.4)

$G C_{pf}$  = product of gust effect factor and external pressure coefficient, see table below. (Fig. 28.4-1, page 300 & 301)

$G C_{pi}$  = product of gust effect factor and internal pressure coefficient. (Tab. 26.11-1, Enclosed Building, page 258)

= 0.18 or -0.18


a = width of edge strips, Fig 28.4-1, note 9, page 301, MAX[ MIN(0.1B, 0.1L, 0.4h), MIN(0.04B, 0.04L), 3] = 5.00 ft

### Net Pressures (psf), Basic Load Cases


Surface	Roof angle $\theta = 0.00$			Roof angle $\theta = 0.00$		
	$G C_{pf}$	Net Pressure with		$G C_{pf}$	Net Pressure with	
		(+GC <sub>pi</sub> )	(-GC <sub>pi</sub> )		(+GC <sub>pi</sub> )	(-GC <sub>pi</sub> )
1	0.40	6.20	16.36	-0.45	-17.77	-7.61
2	-0.69	-24.53	-14.38	-0.69	-24.53	-14.38
3	-0.37	-15.51	-5.36	-0.37	-15.51	-5.36
4	-0.29	-13.25	-3.10	-0.45	-17.77	-7.61
5				0.40	6.20	16.36
6				-0.29	-13.25	-3.10
1E	0.61	12.13	22.28	-0.48	-18.61	-8.46
2E	-1.07	-35.25	-25.10	-1.07	-35.25	-25.10
3E	-0.53	-20.02	-9.87	-0.53	-20.02	-9.87
4E	-0.43	-17.20	-7.05	-0.48	-18.61	-8.46
5E				0.61	12.13	22.28
6E				-0.43	-17.20	-7.05

### Net Pressures (psf), Torsional Load Cases

Surface	Roof angle $\theta = 0.00$		
	$G C_{pf}$	Net Pressure with	
		(+GC <sub>pi</sub> )	(-GC <sub>pi</sub> )
1T	0.40	1.55	4.09
2T	-0.69	-6.13	-3.60
3T	-0.37	-3.88	-1.34
4T	-0.29	-3.31	-0.78
Surface	Roof angle $\theta = 0.00$		
	$G C_{pf}$	Net Pressure with	
		(+GC <sub>pi</sub> )	(-GC <sub>pi</sub> )
5T	0.40	1.55	4.09
6T	-0.29	-3.31	-0.78




Load Case A (Transverse)




Load Case B (Longitudinal)

### Basic Load Cases



Load Case A (Transverse)



Load Case B (Longitudinal)

### Torsional Load Cases



Title Block Line 1  
You can change this area  
using the "Settings" menu item  
and then using the "Printing &  
Title Block" selection.  
Title Block Line 6

Project Title:  
Engineer:  
Project Descr:

Project ID:

Printed: 31 AUG 2016, 2:07PM

## Masonry Slender Wall

File = \\dbaa-sv2\projects\16096 Challenger Middle School\Engineering\16096 challenger.ec6  
ENERCALC, INC. 1983-2016, Build 6.16.6.7, Ver:6.16.6.7

Lic. #: KW-06009174

Licensee: DAVID BIXLER AND ASSOCIATES

Description: equivalent cantilevered wall in front of existing wall

### Code References

Calculations per ACI 530-11, IBC 2012, CBC 2013, ASCE 7-10

Load Combinations Used: ASCE 7-10

### General Information

Calculations per ACI 530-11, IBC 2012, CBC 2013, ASCE 7-10

Construction Type: Grouted Hollow Concrete Masonry


F'm	=	1.50 ksi	Nom. Wall Thickness	6 in	Temp Diff across thickness	=	deg F
Fy - Yield	=	60.0 ksi	Actual Thickness	5.625 in	Min Allow Out-of-plane Defl Ratio	=	0
Fr - Rupture	=	61.0 psi	Rebar "d" distance	3.813 in	Minimum Vertical Steel %	=	0.0020
Em = f'm *	=	900.0	Lower Level Rebar				
Max % of ρ bal.	=	0.1455	Bar Size	# 4			
Grout Density	=	140 pcf	Bar Spacing	16.0 in			
Block Weight		Normal Weight					
Wall Weight	=	52.0 psf					

Wall is grouted at rebar cells only

### One-Story Wall Dimensions

A Clear Height	=	4.660 ft
B Parapet height	=	ft

Wall Support Condition Top & Bottom Pinned



### Lateral Loads

Wind Loads:

Full area WIND load 34.0 psf

Seismic Loads:

Wall Weight Seismic Load Input Method:  
Seismic Wall Lateral Load

Direct entry of Lateral Wall Weight  
psf

Fp 1.0 = 0.0 psf

(Applied to full "STRIP Width")

D	Lr	L	E	W	Endpoints from Base top bottom
				7.0 k/ft	4.660 3.660 k/ft

Distributed Lateral Load





Title Block Line 1  
 You can change this area  
 using the "Settings" menu item  
 and then using the "Printing &  
 Title Block" selection.  
 Title Block Line 6

Project Title:  
 Engineer:  
 Project Descr:

Project ID:

Printed 31 AUG 2016 2:07PM

## Masonry Slender Wall

File = \\dbaa-sv2\projects\16096 Challenger Middle School\Engineering\16096 challenger.ec6

ENERCALC, INC. 1983-2016, Build 6.16.6.7, Ver.6.16.6.7

Lic. # : KW-06009174

Licensee : DAVID BIXLER AND ASSOCIATES

Description : equivalent cantilevered wall in front of existing wall

### Design Maximum Combinations - Deflections

Results reported for "Strip Width" = 12 in.

Load Combination	Axial Load	Moment Values		Stiffness		Deflections	
	Pu k	Mcr k-ft	Mactual k-ft	I gross in <sup>4</sup>	I cracked in <sup>4</sup>	I effective in <sup>4</sup>	Deflection in
W Only at 2.64 to 2.80	0.000	0.00	0.00	0.00	0.00	0.000	0.0
	0.000	0.28	1.55	154.20	28.91	28.941	0.146
	0.000	0.00	0.00	0.00	0.00	0.000	0.0
	0.000	0.00	0.00	0.00	0.00	0.000	0.0

### Reactions - Vertical & Horizontal

Results reported for "Strip Width" = 12 in.

Load Combination	Base Horizontal	Top Horizontal	Vertical @ Wall Base
+D+H	0.0 k	0.00 k	0.242 k
+D+L+H	0.0 k	0.00 k	0.242 k
+D+Lr+H	0.0 k	0.00 k	0.242 k
+D+S+H	0.0 k	0.00 k	0.242 k
+D+0.750Lr+0.750L+H	0.0 k	0.00 k	0.242 k
+D+0.750L+0.750S+H	0.0 k	0.00 k	0.242 k
+D+0.60W+H	0.4 k	3.27 k	0.242 k
+D+0.70E+H	0.0 k	0.00 k	0.242 k
+D+0.750Lr+0.750L+0.450W+H	0.3 k	2.46 k	0.242 k
+D+0.750L+0.750S+0.450W+H	0.3 k	2.46 k	0.242 k
+D+0.750L+0.750S+0.5250E+H	0.0 k	0.00 k	0.242 k
+0.60D+0.60W+0.60H	0.4 k	3.27 k	0.145 k
+0.60D+0.70E+0.60H	0.0 k	0.00 k	0.145 k
D Only	0.0 k	0.00 k	0.242 k
Lr Only	0.0 k	0.00 k	0.000 k
L Only	0.0 k	0.00 k	0.000 k
S Only	0.0 k	0.00 k	0.000 k
W Only	0.6 k	5.46 k	0.000 k
E Only	0.0 k	0.00 k	0.000 k
H Only	0.0 k	0.00 k	0.000 k





# DAVID BIXLER & ASSOCIATES

## Structural Engineering

August 23, 2016

### VISION

Our vision is  
to be recognized  
throughout the  
Southwest as the  
leader in structural  
engineering.

Mark Davenport AIA, CEFPI, LEED AP, BD+C  
SPS+ ARCHITECTS LLP  
8681 E. Via de Negocio  
Scottsdale, AZ 85258

**Re: Challenger Middle School  
Glendale, AZ**

### COMMITMENT

Dear Mr. Davenport:

We are committed to  
■ technological  
leadership  
■ innovative and cost-  
effective solutions  
■ quality work  
■ client satisfaction.

Per your request, we have visited the Challenger Middle School site on several occasions. We have also reviewed the reports from both Speedie and Associates, and Gervasio and Associates attached to the end of this report, along with pictures from our site visits during the CMU removal to investigate the reinforcing and typical pictures of the type of cracking along the buildings. We have also reviewed the existing plans of the buildings which we have received. The purpose of this report is to review the conditions of the existing buildings along with the reports prepared by other consultants and to recommend a plan of action going forward on the best course of action to remedy the deficient areas.

The buildings are typically steel and wood framed roofs bearing on CMU exterior walls and concrete spread footings.

### VALUES

Based on the surface penetrating radar investigations Speedie and Associates performed the vertical reinforcing appears to be installed for the most part correctly, however there are a few areas where you can see from the pictures that the reinforcing appears to stop in the middle of the wall and then sometimes starts again. This could be due to a faulty reading or it could be that is the way it was installed but based off of their radar findings there is nothing that is significantly different than what we would expect.

Our team delivers  
integrity  
service  
collaboration  
quality  
efficiency

Based on the soils investigations performed by Speedie and Associates, there does not appear to be a specific cause of the masonry distress due to the soils themselves, except the fact that the soil is very moist. The moisture fluctuations in the soils will have a tendency to cause continuous movement, which will induce stresses on the buildings and this sometimes will



# DAVID BIXLER & ASSOCIATES

## Structural Engineering

result in cracks in the CMU. My understanding is that there is currently a project in place that will solve or reduce the amount of moisture in the soil and will divert the water away from the buildings.

There was a report done by Gervasio and Associates that we received dated on October 17, 2014, dealing mostly with cracks in the east exterior of Building D at the vestibule. Gervasio maintains that the cracks are due mostly to misplaced masonry control joints. Based on the additional information we have ascertained, I would agree with their conclusion. The repairs that they recommended were to saw-cut new masonry control joints into the walls and tuck point and repair/replace the cracked masonry. This is the repair method I would recommend in this area as well.

From our review of the CMU demolition and our cursory review of the buildings in general, we discovered numerous cracking and rusted reinforcing. The footings in these locations however appeared to be in good condition

From the four holes that were opened up to expose the reinforcing we found rusted and deteriorated vertical and horizontal reinforcing in each location. There was also standing water in the holes showing the amount of saturation these walls are going through along with a picture of sand bags next to a doorway further showing the extent of the moisture issues at this school.

From our visual inspection we noticed several different types of cracks and too many to document all of them however. They basically fall into 3 categories:

1. There were several areas where there are shrinkage cracks most likely due to insufficient or improper locations of masonry control joints or improperly installed masonry control joints (see photographs 1, 2, 4 and 7 on building 1, photos 1, 5 and 12 on building 2, photo 6 on building 6 and photo 4 on building 7). While these are not structural in nature they will affect the water tightness of the building and therefore I recommend that new masonry control joints be installed and for the CMU in these areas to be tuck pointed and repaired or replaced as applicable. There were approximately 10-15 locations throughout the school where this occurred.
2. There were some cracks at beam bearing locations where it appears that the beam was not allowed thermal movement and has cracked the CMU at the bearing locations (see photo 7 on building 6 and photo 3 on building 7). These cracks are structural in nature due to the fact they are supporting the beam ends and therefore should be repaired in a timely manner. The repair for these would be a combination of adding a masonry control joints and removing and reinstalling the beam and bearing plate in a manner that would allow it to move as the temperature changes such as a neoprene pad beneath the beam. There are approximately 6 locations that this would be required.





# DAVID BIXLER & ASSOCIATES

## Structural Engineering

3. The remaining photos appear to be related to moisture and the rusting of the reinforcing in the CMU. Since reinforcing when it rusts can grow to over 400% of its original size, it appears that the reinforcing has rusted and expanded and has cracked the CMU. This causes the face shells to delaminate and then the CMU is essentially reduced in size and therefore reduced in strength. There is no real way to determine the loss in strength without knowing the exact thickness of the delaminated CMU. This is a very old building that does not comply with the current building codes, and additionally, there is reduced strength of the existing wall. The reduction in strength could easily range from 33%-90%. In addition, there is no real way to eliminate moisture from entering into the cracks in the CMU, which will continue to make the condition worse. There is no easy or accurate way to determine the extents of the rusting in the CMU without removing the face shells and investigating the reinforcing, as we did in those four locations. The repair for these locations would be extremely expensive, but would entail removing the CMU at the cracked locations, and then removing and replacing the rusted reinforcing with new reinforcing, grout and CMU. This would need to be done in an explorative manner, where you start at each of the cracks, and then expand outward until you get to undamaged CMU and reinforcing. Therefore, there is no real way to determine the damage extents, but due to the moisture conditions and the amount of cracking, I would not be surprised if 50%-75% of the length of the walls are damaged at grade in this manner. Therefore, the CMU walls should be braced immediately until the repairs are complete.

If the decision is to repair the school, then this should start immediately, and we should brace the CMU walls until the repairs are completed. Without knowing the extent of the damage, it is extremely difficult to determine how the walls will perform as the reinforcing continues to rust and the walls continue to worsen.

While it is extremely difficult to provide any budgetary numbers due to the uncertainty of the full scope and amount of damage, we estimate the following corresponding to the item numbers above:

1) Bracing of CMU walls:	\$70,000
2) Installation of masonry control joints and repair of damaged CMU:	\$60,000
3) Beam bearing cracks:	\$30,000
4) Repair of the cracked CMU and rusted reinforcing:	\$400,000
5) Gervasio crack repair:	\$20,000

Please understand that this report represents a professional opinion based upon the results of our limited observations, and past experience with similar conditions. Our study was strictly limited to visual observations as stated above. This report is not intended to be a complete or comprehensive study of the structure. We have not reviewed, nor have we been asked to review, the capacity of the existing structure per the current code. Our work has been performed in accordance with generally accepted principles and practices of structural engineering.





# DAVID BIXLER & ASSOCIATES

## Structural Engineering


We cannot be responsible for any future changes in the condition of the structure. No warranty is provided, either expressed or implied.

If there are any additional concerns or questions, please feel free to contact our office. Thank you for the opportunity to assist you on this project.


Sincerely,

*David Bixler*

David Bixler, PE, SE President  
David Bixler & Associates, PLLC



# CMU REMOVAL AND INVESTIGATION PICTURES



1 SITE PLAN  
SCALE: 1" = 30'-0"

A100

DATE: 3/1/2011  
JOB NO: 1408  
SHEET

REVIEWED BY:  
DRAWN BY:  
PRELIMINARY  
NOT FOR  
CONSTRUCTION

CHALLENGER MIDDLE SCHOOL  
GLENDALE ELEMENTARY SCHOOL DISTRICT NO. 40  
6905 WEST MARYLAND AVENUE  
GLENDALE, AZ 85303

CHALLENGER MIDDLE SCHOOL  
GLENDALE ELEMENTARY SCHOOL DISTRICT NO. 40  
6905 WEST MARYLAND AVENUE  
GLENDALE, AZ 85303

CHALLENGER SITE PLAN

SPS+ ARCHITECTS LLP  
10000 N. CENTRAL AVENUE, SUITE 100  
SCOTTSDALE, AZ 85258  
TEL: 480.991.2033  
FAX: 480.991.2033  
www.spsarchitects.com

**SPS+**  
ARCHITECTS



## CHALLENGER – BLDG. 1 - MARKER #1



PICTURE NO. 1



PICTURE NO. 2



**CHALLENGER – BLDG. 1 - MARKER #1**



**PICTURE NO. 3**



**PICTURE NO. 4**



**CHALLENGER – BLDG. 1 - MARKER #1**



**PICTURE NO. 5**



**PICTURE NO. 6**



**CHALLENGER – BLDG. 1 - MARKER #1**



**PICTURE NO. 7**

**CHALLENGER – BLDG. 2 - MARKER #2**



**PICTURE NO. 1**




**PICTURE NO. 2**



**CHALLENGER – BLDG. 2 - MARKER #3**



**PICTURE NO. 1**



**PICTURE NO. 2**



**CHALLENGER – BLDG. 2 - MARKER #3**



**PICTURE NO. 3**



**CHALLENGER – BLDG. 2 - MARKER #3**

**PICTURE NO. 4**

SITE

INVESTIGATION


PICTURES



**CHALLENGER – BLDG. 6 - MARKER #4**



**PICTURE NO. 1**



**CHALLENGER MIDDLE SCHOOL**  
 GLENDALE ELEMENTARY SCHOOL DISTRICT NO. 40  
 6905 WEST MARYLAND AVENUE  
 GLENDALE, AZ 85303

CHALLENGER SITE PLAN

SPS+ ARCHITECTS LLP  
 15010 N. 19TH AVENUE, SUITE 100  
 SCOTTSDALE, AZ 85258  
 FAX: 480.991.1223  
[www.spsarchitects.com](http://www.spsarchitects.com)

**SPS+**  
 ARCHITECTS

THIS PLAN IS THE PROPERTY OF SPS+ ARCHITECTS LLP. IT IS TO BE USED ONLY FOR THE PROJECT AND SITE SPECIFICALLY IDENTIFIED HEREON. IT IS NOT TO BE REPRODUCED, COPIED, OR TRANSMITTED IN ANY FORM OR BY ANY MEANS, ELECTRONIC OR MECHANICAL, WITHOUT THE WRITTEN PERMISSION OF SPS+ ARCHITECTS LLP.

REVIEWED BY:  
 DRAWN BY:


**PRELIMINARY  
 NOT FOR  
 CONSTRUCTION**

DATE: 3/18/2015


JOB NO: 14040

SHEET  
**A100**

2 BUILDING E FLOOR PLAN  
SCALE 1/8" = 1'-0"



1 BUILDING C + D FLOOR PLANS  
SCALE 1/8" = 1'-0"



A202

DATE: 3/18/2015  
JOB NO: 1408  
SHEET:

PRELIMINARY  
NOT FOR  
CONSTRUCTION

REVIEWED BY:  
DRAWN BY:


CHALLENGER MIDDLE SCHOOL  
GLENDAL E ELEMENTARY SCHOOL DISTRICT NO. 40  
6905 WEST MARYLAND AVENUE  
GLENDAL E, AZ 85303

BUILDING C, D, + E FLOOR PLANS

SPS+ ARCHITECTS  
3555 ARCHITECTURE  
10000 N. 19TH AVENUE, SUITE 100  
DENVER, CO 80202  
TEL: 480.971.1800  
FAX: 480.971.1823  
www.spsarchitects.com

**SPS+**  
ARCHITECTS





1 BUILDING A FLOOR PLAN  
SCALE: 1/8" = 1'-0"



A200

SHEET

DATE 3/1/2011  
JOB NO. 1040

PRELIMINARY  
NOT FOR  
CONSTRUCTION

REVIEWED BY

DRAWN BY


ALL DRAWINGS ARE THE PROPERTY OF SPS+ ARCHITECTS LLP. NO PART OF THIS DRAWING MAY BE REPRODUCED OR TRANSMITTED IN ANY FORM OR BY ANY MEANS, ELECTRONIC OR MECHANICAL, WITHOUT PERMISSION IN WRITING FROM SPS+ ARCHITECTS LLP.

**CHALLENGER MIDDLE SCHOOL**  
GLENDALE ELEMENTARY SCHOOL DISTRICT NO. 40  
6905 WEST MARYLAND AVENUE  
GLENDALE, AZ 85303

BUILDING A FLOOR PLAN

SPS+ ARCHITECTS LLP  
SCOTTSDALE, AZ 85258  
TEL: 480.991.1223  
FAX: 480.991.1223  
www.spsarchitects.com

**SPS+ ARCHITECTS**



1 BUILDING H FLOOR PLAN  
SCALE 3/16" = 1'-0"



A204

SHEET

DATE: 3/18/2015

JOB NO: 1408

PRELIMINARY  
NOT FOR  
CONSTRUCTION

REVIEWED BY:

DRAWN BY:


NO.	DATE	DESCRIPTION
1	3/18/2015	ISSUED FOR PERMIT

**CHALLENGER MIDDLE SCHOOL**  
**GLENDALE ELEMENTARY SCHOOL DISTRICT NO. 40**  
 6905 WEST MARYLAND AVENUE  
 GLENDALE, AZ 85303

BUILDING H FLOOR PLAN

SPS+ ARCHITECTS LLP  
 3000 N. CENTRAL AVENUE, SUITE 200  
 PHOENIX, AZ 85012  
 P: 602.991.2023  
 F: 602.991.2023  
 www.spsarchitects.com





1 BUILDING F FLOOR PLAN  
SCALE 3/32" = 1'-0"

A203

DATE: 3/18/2015  
JOB NO: 1408  
SHEET: 3/11  
REVIEWED BY:  
DRAWN BY:  
PRELIMINARY  
NOT FOR  
CONSTRUCTION

THIS DOCUMENT IS THE PROPERTY OF SPS+ ARCHITECTS. IT IS TO BE USED ONLY FOR THE PROJECT AND SITE SPECIFICALLY IDENTIFIED HEREON. IT IS NOT TO BE REPRODUCED, COPIED, OR TRANSMITTED IN ANY FORM OR BY ANY MEANS, ELECTRONIC OR MECHANICAL, WITHOUT THE WRITTEN PERMISSION OF SPS+ ARCHITECTS.

**CHALLENGER MIDDLE SCHOOL**  
GLENDALE ELEMENTARY SCHOOL DISTRICT NO. 40  
6905 WEST MARYLAND AVENUE  
GLENDALE, AZ 85303  
BUILDING F FLOOR PLAN

SPS+ ARCHITECTS LLP  
5555 N. CENTRAL AVENUE, SUITE 200  
GLANDALE, AZ 85303  
TEL: 480.991.0000  
FAX: 480.991.2423  
www.spsarchitects.com





## CHALLENGER – BUILDING 1



MARKER NO. 1

## CHALLENGER – BUILDING 1



**MARKER NO. 2**



**MARKER NO. 3**



**CHALLENGER – BUILDING 1**



**MARKER NO. 4**



**MARKER NO. 5**

## CHALLENGER – BUILDING 1



**MARKER NO. 6**



**MARKER NO. 7**



## CHALLENGER – BUILDING 2




**MARKER NO. 1**



**MARKER NO. 2**



**CHALLENGER – BUILDING 2**



**MARKER NO. 3**



**MARKER NO. 4**



**CHALLENGER – BUILDING 2**



**MARKER NO. 5**

**CHALLENGER – BUILDING 2**



**MARKER NO. 6**



**MARKER NO. 7**



**CHALLENGER – BUILDING 2**



**MARKER NO. 8**



**MARKER NO. 9**



## CHALLENGER – BUILDING 2



**MARKER NO. 10**




**MARKER NO. 11**



**CHALLENGER – BUILDING 2**



**MARKER NO. 12**



**MARKER NO. 13**



## CHALLENGER – BUILDING 3



**MARKER NO. 1**



**MARKER NO. 2**



### CHALLENGER – BUILDING 3



**MARKER NO. 3**



**MARKER NO. 4**



**CHALLENGER – BUILDING 3**



**MARKER NO. 5**



**CHALLENGER – BUILDING 4**



**MARKER NO. 1**



**MARKER NO. 2**



## CHALLENGER – BUILDING 4



**MARKER NO. 3**



**MARKER NO. 4**



CHALLENGER STRUCTURAL

Glendale Elementary School District SFB Projects: Construction Cost Estimates

BRG: Project: Scope: Updated 9/1/16 Cost Estimate:

070440111-1003-002-BRG	Challenger Structural		
	Phase 2	Gervasio crack repair	\$ 20,000.00
		Estimated Phase 2 Subtotal	\$ 20,000.00
		Estimated Total Repair:	\$ 20,000.00



Glendale Elementary School District SFB Projects: Construction Cost Estimates

BRG: Project: Scope: Updated 9/1/16 Cost Estimate:

070440111-9999-005-BRG	Challenger Drainage		
	Phase2	Chasse Estimate	\$ 273,966.25
		Estimated Phase 2 Subtotal	\$ 273,966.25
		Estimated Total Repair:	\$ 273,966.25

GENERAL NOTES FOR CONSTRUCTION:

- A. ALL CONSTRUCTION SHALL CONFORM TO THE LATEST MAG STANDARD DETAILS AND SPECIFICATIONS AND THE CITY'S CURRENT ENGINEERING DESIGN AND CONSTRUCTION STANDARDS.
- B. THIS SET OF PLANS HAS BEEN REVIEWED FOR COMPLIANCE WITH CITY REQUIREMENTS PRIOR TO ISSUANCE OF CONSTRUCTION PERMITS. HOWEVER, SUCH REVIEW AND ACCEPTANCE SHALL NOT PREVENT THE CITY FROM REQUIRING CORRECTION OF ERRORS IN SAID PLANS AND/OR CONSTRUCTION WHEN IN VIOLATION OF ANY LAWS, ORDINANCES, CODES OR STANDARDS THAT ARE IN EFFECT. REVIEW AND ACCEPTANCE OF PLANS DOES NOT RELEASE A DEVELOPER OR ENGINEER FROM RESPONSIBILITY FOR ERRORS OR OMISSIONS ON SAID PLANS.
- C. THE CITY DOES NOT WARRANT ANY QUANTITIES SHOWN ON THESE PLANS.
- D. THE CITY PLANS ACCEPTANCE IS FOR GENERAL LAYOUT IN THE RIGHT-OF-WAY ONLY. THIS ACCEPTANCE IS VALID FOR A PERIOD OF SIX MONTHS. CONSTRUCTION PERMITS SHALL BE OBTAINED DURING THIS PERIOD OR THE PLANS SHALL BE RESUBMITTED FOR REVIEW.
- E. A CITY ACCEPTED SET OF PLANS SHALL BE AVAILABLE ON THE JOB SITE AT ALL TIMES.
- F. THE CITY SHALL BE NOTIFIED 48 HOURS PRIOR TO ANY CONSTRUCTION WORK. CONSTRUCTION WORK CONCEALED WITHOUT INSPECTION BY THE CITY SHALL BE SUBJECT TO EXPOSURE AT THE CONTRACTOR'S EXPENSE.
- G. A RIGHT-OF-WAY CONSTRUCTION PERMIT IS REQUIRED FOR ALL WORK WITHIN THE PUBLIC RIGHT-OF-WAY OR WITHIN A CITY EASEMENT. A 100% PERFORMANCE BOND OR EQUIVALENT FORM OF FINANCIAL SURETY MAY BE REQUIRED FOR ALL WORK WITHIN THE RIGHT-OF-WAY PRIOR TO THE ISSUANCE OF ANY RIGHT-OF-WAY CONSTRUCTION PERMIT(S). ALL WORK WITHIN THE RIGHT-OF-WAY SHALL BE INSPECTED AND APPROVED BY THE CITY'S ENGINEERING DIVISION.
- H. IMPROVEMENTS SHALL NOT BE ACCEPTED UNTIL "AS-BUILT" PLANS AND ELECTRONIC (AUTOCAD) FILES HAVE BEEN SUBMITTED AND APPROVED BY THE CITY.
- I. THE DEVELOPER IS RESPONSIBLE FOR ALL COSTS AND WORK RELATED TO THE REMOVAL, RELOCATION OR ABANDONMENT OF ALL OBSTRUCTIONS AND/OR UTILITIES WITHIN THE RIGHT-OF-WAY THAT CONFLICT WITH THE NEW IMPROVEMENTS.
- J. THE DEVELOPER IS RESPONSIBLE FOR OBTAINING OR DEDICATING ALL REQUIRED RIGHTS-OF-WAY AND EASEMENTS TO THE CITY PRIOR TO ISSUANCE OF THE BUILDING'S CERTIFICATE OF OCCUPANCY.
- K. THE CONTRACTOR SHALL CONTACT BLUE STAKE (602-263-1100) 48 HOURS PRIOR TO CONSTRUCTION.
- L. THE CONTRACTOR SHALL BARRICADE CONSTRUCTION SITES AT ALL TIMES PER THE CITY OF PHOENIX TRAFFIC BARRICADE MANUAL. WHEN REQUIRED BY THE CITY, A TRAFFIC CONTROL PLAN SHALL BE SUBMITTED FOR APPROVAL A MINIMUM OF 72 HOURS IN ADVANCE OF CONSTRUCTION.
- M. THE CONTRACTOR MAY OBTAIN A FIRE HYDRANT METER FOR CONSTRUCTION WATER FROM THE CITY WATER SERVICES DEPARTMENT. THE UNLAWFUL REMOVAL OF WATER FROM A FIRE HYDRANT IS A VIOLATION OF THE MUNICIPAL CODE, PUNISHABLE BY FINE AND/OR IMPRISONMENT.
- N. DAMAGE CAUSED BY THE DEVELOPER DURING CONSTRUCTION TO CITY INFRASTRUCTURE OR FACILITIES SHALL BE REPAIRED OR REPLACED BY THE DEVELOPER, AT HIS EXPENSE, IN A MANNER ACCEPTABLE TO THE CITY.
- O. THERE SHALL BE NO DIRT RAMPS OVER SIDEWALKS DURING CONSTRUCTION.
- P. AN AZPDES PERMIT IS REQUIRED FOR ALL CONSTRUCTION THAT DISTURBS LAND OVER ONE (1) ACRE IN SIZE. PRIOR TO START OF ANY CONSTRUCTION, THE CONTRACTOR SHALL SUBMIT A NOTICE OF INTENT (NOI) TO THE ARIZONA DEPARTMENT OF ENVIRONMENTAL QUALITY (ADEQ) AND A COPY TO THE CITY OF GLENDALE AND HAVE A COPY OF THE SWPPP ON SITE AT ALL TIMES.

UTILITY UNDERGROUND STATEMENT:

"PURSUANT TO CHAPTER 32.5 OF THE GLENDALE CITY CODE, ALL NEW AND EXISTING UTILITIES WITHIN OR CONTIGUOUS TO THIS STATE SHALL BE PLACED UNDERGROUND IN CONDUIT."

NOTE:

THESE DRAWINGS ARE AN INSTRUMENT OF SERVICE ONLY AND ARE AND SHALL REMAIN THE EXCLUSIVE PROPERTY OF HESS-ROUNTREE, INC. NO REPRODUCTION OR OTHER USE SHALL BE MADE BY ANY PERSON OR FIRM OTHER THAN HESS-ROUNTREE, INC. OR THE CITY OF PHOENIX WITHOUT EXPRESS PERMISSION OF HESS-ROUNTREE, INC. ANY UNAUTHORIZED USE SHALL VOID THE ENGINEER'S SEAL AND SIGNATURE HEREON AND NO PROFESSIONAL RESPONSIBILITY WILL REMAIN.

THESE PLANS HAVE BEEN SUBMITTED TO THE FOLLOWING UTILITY COMPANIES AND THE WORK CONTAINED IN THESE PLANS HAS BEEN APPROVED BY THESE COMPANIES WITHIN THEIR AREA OF INTEREST. THE SIZE AND LOCATIONS, AS SHOWN OF THE GAS, TELEPHONE AND POWER LINES, AND CONNECTIONS AGREE WITH THE INFORMATION CONTAINED IN THE UTILITY COMPANY'S RECORDS. WHERE THE WORK TO BE DONE CONFLICTS WITH ANY OF THESE UTILITIES, THE CONFLICTS WILL BE RESOLVED AS SPECIFIED IN THE SPECIAL PROVISIONS AND/OR AS OTHERWISE NOTED ON THESE PLANS. CONFLICTS ARISING DURING THE COURSE OF CONSTRUCTION FROM UNFORSEEN CIRCUMSTANCES SHALL BE REPORTED TO THE INTERESTED UTILITY COMPANY AND BE RESOLVED BY THEM AND THE DESIGN ENGINEER.

SPRINT COMMUNICATIONS	COLIN SWORD	CO. REPRESENTATIVE CONTACTED	DATE SUBMITTED
COX COMMUNICATIONS	TMC-DV2-01	CO. REPRESENTATIVE CONTACTED	DATE SUBMITTED
SALT RIVER PROJECT DISTRICT	BECKY THOMAS	CO. REPRESENTATIVE CONTACTED	DATE SUBMITTED
S R V W U A	SUSANA ORTEGA	CO. REPRESENTATIVE CONTACTED	DATE SUBMITTED
ARIZONA PUBLIC SERVICE	VIRGINIA NISKALA	CO. REPRESENTATIVE CONTACTED	DATE SUBMITTED
QWEST COMMUNICATIONS	CONFLICT LIAISON DEPT.	CO. REPRESENTATIVE CONTACTED	DATE SUBMITTED
EL PASO NATURAL GAS COMPANY	DENNIS SEGARS	CO. REPRESENTATIVE CONTACTED	DATE SUBMITTED
KINDER MORGAN	D. TARANGO	CO. REPRESENTATIVE CONTACTED	DATE SUBMITTED
SOUTHWEST GAS CORPORATION	FRANCHISE DEPT. 420-586	CO. REPRESENTATIVE CONTACTED	DATE SUBMITTED

ACREAGE

GROSS SITE AREA =19.79 ACRES  
NET SITE AREA =19.43 ACRES  
CONSTRUCTION AREA =2.42 ACRES

GENERAL NOTES FOR GRADING AND DRAINAGE CONSTRUCTION:

- A. THE DEVELOPER/CONTRACTOR IS RESPONSIBLE FOR PAYING PERMIT FEES PRIOR TO CONSTRUCTION.
- B. A SEPARATE PERMIT IS NECESSARY FOR ANY CONSTRUCTION IN THE RIGHT-OF-WAY.
- C. PRIOR TO THE START OF ANY ON-SITE GRADING OPERATIONS, THE CONTRACTOR SHALL NOTIFY THE CITY ENGINEERING DIVISION AT LEAST 48 HOURS PRIOR TO COMMENCING WORK BY CALLING 623-930-3630.
- D. STAKING PAD AND/OR FINISHED FLOOR ELEVATIONS ARE THE RESPONSIBILITY OF THE DEVELOPER OR HIS ENGINEER. IN NON-CRITICAL AREAS, THE DEVELOPER'S ENGINEER SHALL SUBMIT CERTIFICATIONS OF CONSTRUCTED BUILDING PAD ELEVATIONS PRIOR TO THE CITY'S ACCEPTANCE OF PROJECT. IN A CRITICAL DRAINAGE AREA, CERTIFICATION OF THE FINISHED BUILDING FLOOR OR STEM WALL ELEVATION SHALL BE SUBMITTED AND APPROVED PRIOR TO ANY VERTICAL CONSTRUCTION.
- E. AN APPROVED GRADING AND DRAINAGE PLAN SHALL BE ON THE JOB SITE AT ALL TIMES. DEVIATIONS FROM THE PLAN MUST BE PRECEDED BY AN APPROVED PLAN REVISION.
- F. ACCEPTANCE OF GRADING AND DRAINAGE IMPROVEMENTS SHALL INCLUDE, BUT NOT BE LIMITED TO, THE CONSTRUCTION OF RETENTION BASINS, CATCH BASINS, CURB FOR OTHER DRAINAGE FACILITIES, SITE GRADING, DRYWELLS, STORM DRAIN PIPES, UNDERGROUND STORAGE TANKS AND ASPHALT PAVEMENT.
- G. DRYWELLS MUST BE DRILLED A MINIMUM OF 10 FEET INTO PERMEABLE POROUS STRATA.
- H. THE CONTRACTOR SHALL CONSTRUCT ALL RETENTION BASINS TO THE ELEVATIONS AND SLOPES SHOWN ON THE PLANS.
- I. THE CONTRACTOR IS RESPONSIBLE FOR LOCATING AND CONFIRMING DEPTH OF ALL THE EXISTING UTILITY LINES WITHIN PROPOSED RETENTION BASIN AREAS. IF THE BASIN CANNOT BE CONSTRUCTED PER PLAN AS A RESULT OF CONFLICT WITH UNDERGROUND UTILITIES, THE CONTRACTOR SHOULD CONTACT THE CITY AND DESIGN ENGINEER AND REQUEST MODIFICATION OF THE BASIN DESIGN.
- J. THIS SET OF PLANS HAS BEEN REVIEWED FOR COMPLIANCE WITH CITY REQUIREMENTS PRIOR TO ISSUANCE OF CONSTRUCTION PERMITS AND SHALL BE KEPT AT THE CONSTRUCTION SITE. SUCH REVIEW SHALL NOT PREVENT THE CITY FROM REQUIRING CORRECTIONS TO ERRORS ON THE PLANS, WHICH ARE FOUND TO BE IN VIOLATION OF ANY LAW OR ORDINANCE.
- K. NO PERSON SHALL USE ANY MECHANICAL EQUIPMENT FOR CLEARING, GRUBBING, ROAD CONSTRUCTION, TRENCHING, EXCAVATING, DEMOLITION OR ENGAGE IN ANY EARTHMOVING ACTIVITY WITHOUT FIRST OBTAINING A DUST CONTROL PERMIT FROM MARICOPA COUNTY DEPARTMENT OF ENVIRONMENTAL SERVICES.

DRAINAGE CORRECTIONS


AT  
CHALLENGER MIDDLE SCHOOL

SITE ADDRESS: 6905 W. MARYLAND AVENUE  
GLENDALE, ARIZONA 85303



FOR

GLENDALE ELEMENTARY SCHOOL DISTRICT NO. 40 (OWNER)

7301 N. 58TH AVENUE  
GLENDALE, ARIZONA 85303  
PHONE: (623) 842-8100  
CONTACT: GREG GILLIAM









HESS - ROUNTREE, INC.  
CONSULTING ENGINEERS & LAND SURVEYORS  
9831 SOUTH 51ST STREET, SUITE C110  
PHOENIX, ARIZONA 85044 (480)496-0244


DES. **DRO** DRN. **JCW** CKD. **DRO** JOB NO. **1510-04**




**SECTION A-A**  
NOT TO SCALE




**SECTION B-B**  
NOT TO SCALE




**SECTION C-C**  
NOT TO SCALE



**SECTION D-D**  
NOT TO SCALE




**SECTION E-E**  
NOT TO SCALE




**AREA DRAIN**  
NOT TO SCALE

GREEN PLASTIC IRRIGATION BOX (10" DIA.) WITH BOLT LOCK COVER IN LANDSCAPED AREAS. USE TAN COLORED BOX IN GRANITE AREAS. IN PAVED AREAS BOX AND COVER SHALL BE CAST IRON PER MAG S.D. 270 W/ CHAIN ATTACHMENT



**STORM DRAIN CLEANOUT**  
NOT TO SCALE



NOTE:  
CONCRETE ADJACENT TO GRATE SHALL BE APPROXIMATELY 1/8" HIGHER THAN THE PROPOSED RIM ELEVATION.

**TRENCH DRAIN DETAIL**  
NOT TO SCALE

**LEGEND**

- BC 1120.45 EXISTING BACK OF CURB ELEVATION
- G 1119.94 EXISTING GUTTER ELEVATION
- P 1120.50 EXISTING PAVEMENT ELEVATION
- C 1120.18 EXISTING CONCRETE ELEVATION
- SW 1120.51 EXISTING SIDEWALK ELEVATION
- TW 1125.39 TOP OF WALL ELEVATION
- PL 1120.34 EXISTING PLANTER ELEVATION
- FL 1119.53 EXISTING FLOWLINE ELEVATION
- NG 1121.32 EXISTING GROUND ELEVATION
- TB 1119.95 EXISTING TOP OF BERM ELEVATION
- TS 1119.73 EXISTING TOE OF SLOPE ELEVATION
- FF 1120.70 EXISTING FINISH FLOOR ELEVATION
- DG 1120.30 EXISTING DECOMPOSED GRANITE
- SC EXISTING COLUMN
- ED EXISTING AREA DRAIN
- EW EXISTING DRY WELL
- FDC EXISTING FIRE DEPARTMENT CONNECTION
- FH EXISTING FIRE HYDRANT
- WMB EXISTING WATER METER BOX
- WV EXISTING WATER VALVE
- ICV EXISTING CHECK VALVE
- EB EXISTING ELECTRIC BOX
- RD EXISTING ROOF DRAIN
- ES EXISTING SIGN
- SSCO EXISTING SANITARY SEWER CLEANOUT
- BFP EXISTING BACKFLOW PREVENTER
- IRRG EXISTING WATER LINE PIPE & SIZE
- E EXISTING GAS LINE
- COMM EXISTING COMMUNICATION LINE
- SD EXISTING STORM DRAIN LINE
- TR EXISTING TREE

**NOTES, LEGEND, AND DETAILS SHEET**



**GLENDALE ELEMENTARY SCHOOL DISTRICT NO. 40**

**DRAINAGE CORRECTIONS AT  
GLENDALE CHALLENGER MIDDLE SCHOOL**

DRAWING STATUS	SHEET	OF	
1ST CITY SUBMITTAL			
	2	6	C-2
DATE:	8-10-16		



151004C02.DWG



**HESS - ROUNTREE, INC.**  
CONSULTING ENGINEERS & LAND SURVEYORS  
9831 SOUTH 51ST STREET, SUITE C110  
PHOENIX, ARIZONA 85044 (480)496-0244


DES. **DRO** DRN. **JCW** CKD. **DRO** JOB NO. **1510-04**

### GRADING AND DRAINAGE CONSTRUCTION NOTES:

- 1 REGRADE EXISTING LANDSCAPE AREA TO FINISH GRADE ELEVATIONS INDICATED.
- 2 CAP ALL SPRINKLER IRRIGATION LATERALS AND HEADS, REMOVE TURF AND INSTALL 2" OF DECOMPOSED GRANITE (1/4" MINUS MADISON GOLD).
- 3 CONNECT TO EXISTING PVC STORM DRAIN PIPE WITH INSERTA-TEE OR APPROVED EQUAL.
- 4 INSTALL NEW AREA DRAIN (SEE DETAIL SHEET C-2).
- 5 INSTALL 10" PVC DRAINAGE PIPE (ASTM D3034, SDR-35).
- 6 INSTALL 12" PVC DRAINAGE PIPE (ASTM D3034, SDR-35).
- 7 INSTALL TRENCH DRAIN (SEE DETAIL ON SHEET C-2).
- 8 PROTECT EXISTING TREE FROM DAMAGE. MODIFY GRADING SO THE ROOTS DO NOT GET DAMAGED.
- 9 REMOVE EXISTING AREA DRAIN AND CONNECT TO EXISTING 12" PVC PIPE. FIELD VERIFY LOCATION AND ELEVATION.
- 10 INSTALL NEW CONCRETE SIDEWALK (MAG STANDARD DETAIL 230) MAXIMUM JOINT SPACING SHALL BE 10' ON CENTER. JOINTS SHALL HAVE 1/2" RADIUS TO MATCH EXISTING SIDEWALKS.
- 11 REMOVE EXISTING 12"-90° BEND OR 45° BEND AND INSTALL WYE AND CLEANOUT (SEE DETAIL ON SHEET C-2).
- 12 CONNECT TO EXISTING 6" PVC PIPE WITH NEW 6" WYE.
- 13 INSTALL 6" PVC DRAINAGE PIPE (ASTM D3034, SDR-35).
- 14 CONNECT TO EXISTING PVC PIPE WITH NEW WYE AND CLEANOUT.
- 15 REPAIR OR REPLACE GRANITE IRRIGATION AND LANDSCAPING DISTURBED BY THE NEW STORM DRAIN INSTALLATION AND GRADING.
- 16 SAWCUT AND REMOVE EXISTING CONCRETE SIDEWALK.
- 17 HYDROVAC ALL EXISTING STORM DRAIN LINES TO REMOVE DIRT AND DEBRIS FROM ALL CATCH BASINS AND DRYWELLS.
- 18 INSTALL 4" PVC DRAINAGE PIPE (ASTM D3034, SDR-35).
- 19 EXISTING PLANTER TO REMAIN. PROTECT FROM DAMAGE.
- 20 ADJUST EXISTING AREA DRAIN TO FINISH GRADE SHOWN.
- 21 POTHOLE AND FIELD VERIFY ELEVATION AND LOCATION OF EXISTING UTILITY LINES PRIOR TO CONSTRUCTION. PROTECT FROM DAMAGE.
- 22 CONVERT EXISTING SPRINKLER IRRIGATION VALVE THAT SERVED THE AREA, TO A DROP IRRIGATION VALVE. PROVIDE WATER TO EXISTING TREES WITH POLY-TUBING AND 4 EMITTERS TO EACH TREE.

### NOTE:

SPRAY AREA WHERE LANDSCAPING IS BEING CONVERTED FROM TURF TO DECOMPOSED GRANITE WITH TWO APPLICATIONS OF TURF KILLER PRIOR TO PLACEMENT OF GRANITE.



### GRADING AND DRAINAGE PLAN



**GLENDALE ELEMENTARY SCHOOL DISTRICT NO. 40**

**DRAINAGE CORRECTIONS AT  
GLENDALE CHALLENGER MIDDLE SCHOOL**

DRAWING STATUS	SHEET	OF	
1ST CITY SUBMITTAL	3	6	C-3
DATE:	8-10-16		







**HESS - ROUNTREE, INC.**  
CONSULTING ENGINEERS & LAND SURVEYORS  
9831 SOUTH 51ST STREET, SUITE C110  
PHOENIX, ARIZONA 85044 (480)496-0244


DES. **DRO** DRN. **JCW** CKD. **DRO** JOB NO. **1510-04**

**GRADING AND DRAINAGE CONSTRUCTION NOTES:**

- 1 REGRADE EXISTING LANDSCAPE AREA TO FINISH GRADE ELEVATIONS INDICATED.
- 2 CAP ALL SPRINKLER IRRIGATION LATERALS AND HEADS, REMOVE TURF AND INSTALL 2" OF DECOMPOSED GRANITE (1/4" MINUS MADISON GOLD).
- 3 CONNECT TO EXISTING PVC STORM DRAIN PIPE WITH INSERTA-TEE OR APPROVED EQUAL.
- 4 INSTALL NEW AREA DRAIN (SEE DETAIL SHEET C-2).
- 5 INSTALL 10" PVC DRAINAGE PIPE (ASTM D3034, SDR-35).
- 6 INSTALL 12" PVC DRAINAGE PIPE (ASTM D3034, SDR-35).
- 7 INSTALL TRENCH DRAIN (SEE DETAIL ON SHEET C-2).
- 8 PROTECT EXISTING TREE FROM DAMAGE. MODIFY GRADING SO THE ROOTS DO NOT GET DAMAGED.
- 9 REMOVE EXISTING AREA DRAIN AND CONNECT TO EXISTING 12" PVC PIPE. FIELD VERIFY LOCATION AND ELEVATION.
- 10 INSTALL NEW CONCRETE SIDEWALK (MAG STANDARD DETAIL 230) MAXIMUM JOINT SPACING SHALL BE 10' ON CENTER. JOINTS SHALL HAVE 1/2" RADIUS TO MATCH EXISTING SIDEWALKS.
- 11 REMOVE EXISTING 12"-90° BEND OR 45° BEND AND INSTALL WYE AND CLEANOUT (SEE DETAIL ON SHEET C-2).
- 12 CONNECT TO EXISTING 6" PVC PIPE WITH NEW 6" WYE.
- 13 INSTALL 6" PVC DRAINAGE PIPE (ASTM D3034, SDR-35).
- 14 CONNECT TO EXISTING PVC PIPE WITH NEW WYE AND CLEANOUT.
- 15 REPAIR OR REPLACE GRANITE IRRIGATION AND LANDSCAPING DISTURBED BY THE NEW STORM DRAIN INSTALLATION AND GRADING.
- 16 SAWCUT AND REMOVE EXISTING CONCRETE SIDEWALK.
- 17 HYDROVAC ALL EXISTING STORM DRAIN LINES TO REMOVE DIRT AND DEBRIS FROM ALL CATCH BASINS AND DRYWELLS.
- 18 INSTALL 4" PVC DRAINAGE PIPE (ASTM D3034, SDR-35).
- 19 EXISTING PLANTER TO REMAIN. PROTECT FROM DAMAGE.
- 20 ADJUST EXISTING AREA DRAIN TO FINISH GRADE SHOWN.
- 21 POTHOLE AND FIELD VERIFY ELEVATION AND LOCATION OF EXISTING UTILITY LINES PRIOR TO CONSTRUCTION. PROTECT FROM DAMAGE.
- 22 CONVERT EXISTING SPRINKLER IRRIGATION VALVE THAT SERVED THE AREA, TO A DROP IRRIGATION VALVE. PROVIDE WATER TO EXISTING TREES WITH POLY-TUBING AND 4 EMITTERS TO EACH TREE.

**NOTE:**

SPRAY AREA WHERE LANDSCAPING IS BEING CONVERTED FROM TURF TO DECOMPOSED GRANITE WITH TWO APPLICATIONS OF TURF KILLER PRIOR TO PLACEMENT OF GRANITE.





**GRADING AND DRAINAGE PLAN**



**GLENDAL ELEMNTARY SCHOOL DISTRICT NO. 40**

**DRAINAGE CORRECTIONS AT  
GLENDAL CHALLENGER MIDDLE SCHOOL**

DRAWING STATUS	SHEET	OF	
1ST CITY SUBMITTAL			
	4	6	C-4
DATE:	8-10-16		








**HESS - ROUNTREE, INC.**  
CONSULTING ENGINEERS & LAND SURVEYORS  
9831 SOUTH 51ST STREET, SUITE C110  
PHOENIX, ARIZONA 85044 (480)496-0244

DES. **DRO** DRN. **JCW** CKD. **DRO** JOB NO. **1510-04**




**GRADING AND DRAINAGE CONSTRUCTION NOTES:**

- 1 REGRADE EXISTING LANDSCAPE AREA TO FINISH GRADE ELEVATIONS INDICATED.
- 2 CAP ALL SPRINKLER IRRIGATION LATERALS AND HEADS, REMOVE TURF AND INSTALL 2" OF DECOMPOSED GRANITE (1/4" MINUS MADISON GOLD).
- 3 CONNECT TO EXISTING PVC STORM DRAIN PIPE WITH INSERTA-TEE OR APPROVED EQUAL.
- 4 INSTALL NEW AREA DRAIN (SEE DETAIL SHEET C-2).
- 5 INSTALL 10" PVC DRAINAGE PIPE (ASTM D3034, SDR-35).
- 6 INSTALL 12" PVC DRAINAGE PIPE (ASTM D3034, SDR-35).
- 7 INSTALL TRENCH DRAIN (SEE DETAIL ON SHEET C-2).
- 8 PROTECT EXISTING TREE FROM DAMAGE. MODIFY GRADING SO THE ROOTS DO NOT GET DAMAGED.
- 9 REMOVE EXISTING AREA DRAIN AND CONNECT TO EXISTING 12" PVC PIPE. FIELD VERIFY LOCATION AND ELEVATION.
- 10 INSTALL NEW CONCRETE SIDEWALK (MAG STANDARD DETAIL 230) MAXIMUM CONTROL JOINT SPACING SHALL BE 10' ON CENTER. JOINTS SHALL HAVE 1/2" RADIUS TO MATCH EXISTING SIDEWALKS.
- 11 REMOVE EXISTING 12"-90" BEND OR 45" BEND AND INSTALL WYE AND CLEANOUT (SEE DETAIL ON SHEET C-2).
- 12 CONNECT TO EXISTING 6" PVC PIPE WITH NEW 6" WYE.
- 13 INSTALL 6" PVC DRAINAGE PIPE (ASTM D3034, SDR-35).
- 14 CONNECT TO EXISTING PVC PIPE WITH NEW WYE AND CLEANOUT.
- 15 REPAIR OR REPLACE GRANITE IRRIGATION AND LANDSCAPING DISTURBED BY THE NEW STORM DRAIN INSTALLATION AND GRADING.
- 16 SAWCUT AND REMOVE EXISTING CONCRETE SIDEWALK.
- 17 HYDROVAC ALL EXISTING STORM DRAIN LINES TO REMOVE DIRT AND DEBRIS FROM ALL CATCH BASINS AND DRYWELLS.
- 18 INSTALL 4" PVC DRAINAGE PIPE (ASTM D3034, SDR-35).
- 19 EXISTING PLANTER TO REMAIN. PROTECT FROM DAMAGE.
- 20 ADJUST EXISTING AREA DRAIN TO FINISH GRADE SHOWN.
- 21 POTHOLE AND FIELD VERIFY ELEVATION AND LOCATION OF EXISTING UTILITY LINES PRIOR TO CONSTRUCTION. PROTECT FROM DAMAGE.
- 22 CONVERT EXISTING SPRINKLER IRRIGATION VALVE THAT SERVED THE AREA, TO A DROP IRRIGATION VALVE. PROVIDE WATER TO EXISTING TREES WITH POLY-TUBING AND 4 EMITTERS TO EACH TREE.

**NOTE:**



SPRAY AREA WHERE LANDSCAPING IS BEING CONVERTED FROM TURF TO DECOMPOSED GRANITE WITH TWO APPLICATIONS OF TURF KILLER PRIOR TO PLACEMENT OF GRANITE.



**GRADING AND DRAINAGE PLAN**


GLENDALE ELEMENTARY SCHOOL DISTRICT NO. 40			
DRAINAGE CORRECTIONS AT GLENDALE CHALLENGER MIDDLE SCHOOL			
DRAWING STATUS	SHEET	OF	
1ST CITY SUBMITTAL	5	6	C-5
DATE:	8-10-16		






HESS - ROUNTREE, INC.  
CONSULTING ENGINEERS & LAND SURVEYORS  
9831 SOUTH 51ST STREET, SUITE C110  
PHOENIX, ARIZONA 85044 (480)496-0244

DES. **DRO** DRN. **JCW** CKD. **DRO** JOB NO. **1510-04**



**GRADING AND DRAINAGE CONSTRUCTION NOTES:**

- 1 REGRADE EXISTING LANDSCAPE AREA TO FINISH GRADE ELEVATIONS INDICATED.
- 2 CAP ALL SPRINKLER IRRIGATION LATERALS AND HEADS, REMOVE TURF AND INSTALL 2" OF DECOMPOSED GRANITE (1/4" MINUS MADISON GOLD).
- 3 CONNECT TO EXISTING PVC STORM DRAIN PIPE WITH INSERTA-TEE OR APPROVED EQUAL.
- 4 INSTALL NEW AREA DRAIN (SEE DETAIL SHEET C-2).
- 5 INSTALL 10" PVC DRAINAGE PIPE (ASTM D3034, SDR-35).
- 6 INSTALL 12" PVC DRAINAGE PIPE (ASTM D3034, SDR-35).
- 7 INSTALL TRENCH DRAIN (SEE DETAIL ON SHEET C-2).
- 8 PROTECT EXISTING TREE FROM DAMAGE. MODIFY GRADING SO THE ROOTS DO NOT GET DAMAGED.
- 9 REMOVE EXISTING AREA DRAIN AND CONNECT TO EXISTING 12" PVC PIPE. FIELD VERIFY LOCATION AND ELEVATION
- 10 INSTALL NEW CONCRETE SIDEWALK (MAG STANDARD DETAIL 230) MAXIMUM JOINT SPACING SHALL BE 10' ON CENTER. JOINTS SHALL HAVE 1/2" RADIUS TO MATCH EXISTING SIDEWALKS
- 11 REMOVE EXISTING 12"-90° BEND OR 45° BEND AND INSTALL WYE AND CLEANOUT (SEE DETAIL ON SHEET C-2).
- 12 CONNECT TO EXISTING 6" PVC PIPE WITH NEW 6" WYE.
- 13 INSTALL 6" PVC DRAINAGE PIPE (ASTM D3034, SDR-35).
- 14 CONNECT TO EXISTING PVC PIPE WITH NEW WYE AND CLEANOUT.
- 15 REPAIR OR REPLACE GRANITE IRRIGATION AND LANDSCAPING DISTURBED BY THE NEW STORM DRAIN INSTALLATION AND GRADING.
- 16 SAWCUT AND REMOVE EXISTING CONCRETE SIDEWALK.
- 17 HYDROVAC ALL EXISTING STORM DRAIN LINES TO REMOVE DIRT AND DEBRIS FROM ALL CATCH BASINS AND DRYWELLS.
- 18 INSTALL 4" PVC DRAINAGE PIPE (ASTM D3034, SDR-35).
- 19 EXISTING PLANTER TO REMAIN. PROTECT FROM DAMAGE.
- 20 ADJUST EXISTING AREA DRAIN TO FINISH GRADE SHOWN.
- 21 POTHOLE AND FIELD VERIFY ELEVATION AND LOCATION OF EXISTING UTILITY LINES PRIOR TO CONSTRUCTION. PROTECT FROM DAMAGE.
- 22 CONVERT EXISTING SPRINKLER IRRIGATION VALVE THAT SERVED THE AREA, TO A DROP IRRIGATION VALVE. PROVIDE WATER TO EXISTING TREES WITH POLY-TUBING AND 4 EMITTERS TO EACH TREE.



**GRADING AND DRAINAGE PLAN**

**GLENDALE ELEMENTARY SCHOOL DISTRICT NO. 40**

**DRAINAGE CORRECTIONS AT  
GLENDALE CHALLENGER MIDDLE SCHOOL**

DRAWING STATUS	SHEET	OF	
1ST CITY SUBMITTAL			
	6	6	C-6
DATE:	8-10-16		



151004085.DWG



## PROJECT DESCRIPTION

- A. PROPOSED CONSTRUCTION ACTIVITY:  
THIS PROJECT CONSISTS OF CONSTRUCTING NEW SIDEWALK, REMOVING AND REPLACING EXISTING SIDEWALK, CONSTRUCTION OF NEW RETENTION BASIN AND LANDSCAPING ON AN EXISTING MIDDLE SCHOOL CAMPUS. SOIL DISTURBING ACTIVITIES WILL INCLUDE CLEARING, GRADING, TRENCHING AND BACKFILLING FOR UTILITIES, CONCRETE INSTALLATION AND LANDSCAPING.
- B. SEQUENCE OF CONSTRUCTION ACTIVITY:  
THE SEQUENCE OF EVENTS IS ANTICIPATED TO BE AS FOLLOWS:  
1) CLEARING AND GRUBBING  
2) ROUGH GRADING  
3) INSTALLATION OF UTILITIES  
4) FINAL GRADING  
5) CONCRETE AND IMPROVEMENTS  
6) LANDSCAPING IMPROVEMENTS
- C. AREA OF SOIL DISTURBANCE:  
SOIL: SILTY SAND  
ERODABILITY: MODERATE  
IT IS ESTIMATED THAT THE TOTAL AREA OF SOIL DISTURBANCE IS APPROXIMATELY 2.42 ACRES.
- D. RUN-OFF COEFFICIENTS:  
THE ESTIMATED RUN-OFF COEFFICIENTS FOR THE PROJECT ARE AS FOLLOWS:  
1) PRE-DEVELOPMENT RUN-OFF COEFFICIENT = 0.80  
2) POST-DEVELOPMENT RUN-OFF COEFFICIENT = 0.81
- E. QUALITY OF SITE STORM WATER DISCHARGE:  
PRIMARY POLLUTANT: SITE SOIL  
IT IS NOT ANTICIPATED THAT ANY HAZARDOUS MATERIALS WILL TYPICALLY BE CONTAINED WITHIN STORM WATER DISCHARGE. THE EXCEPTION TO THIS WOULD BE ANY FUELS OR LUBRICANTS LEAKED FROM VEHICLES OR EQUIPMENT AND ANY FERTILIZERS OR HERBICIDES USED DURING THE LANDSCAPE IMPROVEMENTS.
- F. RECEIVING BODY OF WATER:  
THE ULTIMATE RECEIVING BODY OF WATER, WHICH WOULD RECEIVE ANY STORM WATER IN EXCESS OF THAT CONTAINED WITHIN THE PROPOSED AND EXISTING RETENTION BASINS, IS SALT RIVER.
- G. GRADING AND DRAINAGE PLAN:  
THE GRADING AND DRAINAGE PLAN AS PREPARED BY HESS-ROUNTREE, INC., PROJECT #1510-04 SHALL BE CONSIDERED A PART OF THE STORMWATER MANAGEMENT PLAN, AND ALL FINAL GRADING AND IMPROVEMENTS SHALL BE IN ACCORDANCE WITH THAT PLAN
- H. NO WATER BODIES ARE ON SITE.

## EROSION AND SEDIMENT CONTROLS

- A. IMMEDIATELY FOLLOWING CLEARING AND GRUBBING, AND AS PART OF THE INITIAL ROUGH GRADING, ALL RETENTION BASINS SHALL BE CUT TO GRADE AND PERIMETER BERMS CONSTRUCTED. THE BASINS AND BERMS SHALL CONSTITUTE THE REQUIRED SEDIMENT BASINS. GRADES SHALL BE CUT (OR BERMING OR STRAW BALES SHALL BE PROVIDED) TO ASSURE THAT RUNOFF IS CONVEYED TO THE BASINS.
- B. A STABILIZED CONSTRUCTION ENTRANCE CONSISTING OF A MINIMUM OF 6" OF 1"-3" COARSE AGGREGATE SHALL BE INSTALLED AS SHOWN. ALL CONSTRUCTION TRAFFIC SHALL ENTER THROUGH THIS ENTRANCE. THE STABILIZED CONSTRUCTION ENTRANCE SHALL BE GRADED OR REPLACED WHEN IT BECOMES SATURATED OR MATTED WITH SITE SOILS. THE PAVED STREET ADJACENT TO THE SITE ENTRANCE SHALL BE SWEEPED ON A REGULAR BASIS TO REMOVE ANY EXCESS MUD OR DIRT TRACKED FROM THE SITE.
- C. ANY DISTURBED AREAS WHERE CONSTRUCTION HAS PERMANENTLY OR TEMPORARILY CEASED SHALL BE STABILIZED TO PREVENT EROSION. AN ACCEPTABLE STABILIZATION METHOD IS HYDROSEEDING. AREAS WHICH WILL BE REDISTURBED WITHIN 21 DAYS DO NOT HAVE TO BE STABILIZED.
- D. THE RETENTION BASINS WHICH ARE SIZED TO CONTAIN THE 100-YR STORM EVENT SHALL ALSO ACT AS THE REQUIRED SEDIMENT BASINS FOR THE PROJECT AND SHALL BE INSPECTED ON A MONTHLY BASIS AND AFTER EVERY HEAVY RAINFALL. NO FLOOD WATER AND THUS NO SEDIMENT CARRIED BY FLOOD WATER ESCAPES THESE BASINS. AS SUCH SEDIMENT SHALL BE REMOVED FROM THE BASINS AS NECESSARY TO MAINTAIN 100% OF THE REQUIRED CAPACITY OF THE BASIN DURING CONSTRUCTION.

### NOTE:

ALL BUBBLER BOXES, AREA DRAINS, CATCH BASINS, TRENCH DRAINS, ETC. SHALL HAVE TWO LAYERS OF MIRAFI 100X FABRIC INSTALLED BENEATH THE GRATE. FABRIC SHALL NOT BE REMOVED UNTIL PAVING AND LANDSCAPING ARE COMPLETE.

THESE PLANS HAVE BEEN SUBMITTED TO THE FOLLOWING UTILITY COMPANIES AND THE WORK CONTAINED IN THESE PLANS HAS BEEN APPROVED BY THESE COMPANIES WITHIN THEIR AREA OF INTEREST. THE SIZE AND LOCATIONS, AS SHOWN OF THE GAS, TELEPHONE AND POWER LINES, AND CONNECTIONS AGREE WITH THE INFORMATION CONTAINED IN THE UTILITY COMPANY'S RECORDS. WHERE THE WORK TO BE DONE CONFLICTS WITH ANY OF THESE UTILITIES, THE CONFLICTS WILL BE RESOLVED AS SPECIFIED IN THE SPECIAL PROVISIONS AND/OR AS OTHERWISE NOTED ON THESE PLANS. CONFLICTS ARISING DURING THE COURSE OF CONSTRUCTION FROM UNFORSEEN CIRCUMSTANCES SHALL BE REPORTED TO THE INTERESTED UTILITY COMPANY AND BE RESOLVED BY THEM AND THE DESIGN ENGINEER.

U S SPRINT COMMUNICATIONS	COLIN SWORD	CO. REPRESENTATIVE CONTACTED	DATE SUBMITTED
COX COMMUNICATIONS	TRAFFIC MANAGEMENT CENTER - DV 64	CO. REPRESENTATIVE CONTACTED	DATE SUBMITTED
SALT RIVER PROJECT DISTRICT	SYLVIA ALVARADO	CO. REPRESENTATIVE CONTACTED	DATE SUBMITTED
S R V W U A	SUZANA ORTEGA	CO. REPRESENTATIVE CONTACTED	DATE SUBMITTED
ARIZONA PUBLIC SERVICE	VIRGINIA NISKALA	CO. REPRESENTATIVE CONTACTED	DATE SUBMITTED
QWEST COMMUNICATIONS	CONFLICT LIAISON DEPARTMENT	CO. REPRESENTATIVE CONTACTED	DATE SUBMITTED
EL PASO NATURAL GAS COMPANY	DENNIS SEGARS	CO. REPRESENTATIVE CONTACTED	DATE SUBMITTED
KINDER MORGAN	D. TARANGO	CO. REPRESENTATIVE CONTACTED	DATE SUBMITTED
SOUTHWEST GAS COMPANY	G. LOPEZ	CO. REPRESENTATIVE CONTACTED	DATE SUBMITTED

## STORM WATER MANAGEMENT PLAN

### FOR THE DRAINAGE CORRECTIONS

## AT CHALLENGER MIDDLE SCHOOL

SITE ADDRESS: 6905 W. MARYLAND AVENUE  
GLENDALE, ARIZONA 85303

### FOR GLENDALE ELEMENTARY SCHOOL DISTRICT NO. 40 (OWNER)

7301 N. 58TH AVENUE  
GLENDALE, ARIZONA 85303  
PHONE: (623) 842-8100  
CONTACT: GREG GILLIAM

### OWNER/DEVELOPER:

GLENDALE ELEMENTARY SCHOOL DISTRICT NO. 40  
7301 NORTH 58TH AVENUE  
GLENDALE, ARIZONA 85303  
PHONE: (623) 842-8100  
CONTACT: GREG GILLIAM

### ENGINEER:

HESS-ROUNTREE, INC.  
9831 S. 51ST STREET, SUITE C110  
PHOENIX, ARIZONA 85044  
PHONE: (480) 496-0244  
FAX: (480) 496-0094  
CONTACT: PERCY MYRON JR., P.E.

### SHEET INDEX:

C-7 COVER SHEET  
C-8 STORM WATER MANAGEMENT PLAN

### PLANS ACCEPTANCE

THE CITY OF GLENDALE ACCEPTS THESE PLANS FOR CONSTRUCTION, AS BEING IN GENERAL COMPLIANCE WITH PLAN PREPARATION REQUIREMENTS OF THE CITY. RESPONSIBILITY FOR THE COMPLETENESS AND ACCURACY OF THE PLANS AND RELATED DESIGNS RESIDES WITH THE ENGINEER AND THE ENGINEERING FIRM OF RECORD.

LAND DEVELOPMENT ENGINEER \_\_\_\_\_ DATE \_\_\_\_\_  
TRANSPORTATION ENGINEER \_\_\_\_\_ DATE \_\_\_\_\_

### RECORD DRAWING

I CERTIFY THAT THE LOCATIONS, ELEVATIONS, DEPTHS, AND RECORD DRAWING COMMENTS ACCURATELY REFLECT THE EXISTING FIELD CONDITIONS AND MATERIALS ACTUALLY USED DURING CONSTRUCTION. THIS CERTIFICATION IS BASED ON INFORMATION OBTAINED UNDER BY DIRECT SUPERVISION AND IS CORRECT AND COMPLETE TO THE BEST OF MY KNOWLEDGE AND BELIEF.

NAME \_\_\_\_\_ DATE \_\_\_\_\_

REGISTRATION NO. \_\_\_\_\_ EXP. DATE \_\_\_\_\_

REV'D BY: \_\_\_\_\_  
ENGINEERING DEPARTMENT

### REVIEWED BY:

LAND DEVELOPMENT ENGINEER \_\_\_\_\_ DATE \_\_\_\_\_

### DRYWELL CERTIFICATION

I CERTIFY THAT ALL DRYWELLS HAVE BEEN REGISTERED WITH AND CONFORM TO ALL REQUIREMENTS OF THE ARIZONA DEPARTMENT OF ENVIRONMENTAL QUALITY (ADEQ).

NAME \_\_\_\_\_ DATE \_\_\_\_\_

COMPANY \_\_\_\_\_

### ACREAGE


GROSS SITE AREA = 19.79 ACRES  
NET SITE AREA = 19.43 ACRES  
CONSTRUCTION AREA = 2.42 ACRES

## STORMWATER MANAGEMENT CONTROL

- A. THE CONTRACTOR, TOGETHER WITH THE OWNER AS COPERMITTEES, SHALL SUBMIT A NOTICE OF INTENT AT LEAST TWO (2) DAYS PRIOR TO THE COMMENCEMENT OF CONSTRUCTION ACTIVITIES TO THE EPA.
- B. THE CONTRACTOR SHALL OBTAIN A DUST CONTROL PERMIT FROM THE MARICOPA COUNTY HEALTH DEPARTMENT AND SHALL WATER THE SITE AT AN ADEQUATE FREQUENCY TO MINIMIZE AIRBORNE PARTICLES.
- C. THE CONTRACTOR SHALL MAINTAIN A COPY OF THE STORMWATER POLLUTION PREVENTION PLAN AND ALL RECORDS AT THE CONSTRUCTION SITE.
- D. THE CONTRACTOR SHALL INSPECT THE CONSTRUCTION SITE AT LEAST ONCE EVERY SEVEN (7) DAYS AND WITHIN TWENTY-FOUR (24) HOURS OF A RAINFALL OF 0.5" OR MORE. THE CONTRACTOR SHALL PREPARE A REPORT DOCUMENTING THEIR FINDINGS ON THE CONDITIONS OF THE CONTROLS AND ANY STABILIZED AREAS. THE CONTRACTOR SHALL MODIFY THE STORMWATER POLLUTION PREVENTION PLAN AS NECESSARY TO CORRECT ANY OBSERVED SEDIMENT OR EROSION PROBLEMS.
- E. PERMANENT LANDSCAPING AND PLACEMENT OF FINAL COVER MATERIALS SHALL OCCUR AS SOON AS PRACTICAL AFTER COMPLETION OF GRADING.
- F. THE CONTRACTOR, TOGETHER WITH THE OWNER, SHALL FILE A NOTICE OF TERMINATION WITH THE EPA AFTER COMPLETION OF ALL CONSTRUCTION AND LANDSCAPING ACTIVITIES.
- G. THE TERMS & CONDITION OF THIS PERMIT WILL BE MET.


### NOTE:

1. ACTUAL LAYOUT DETERMINED IN FIELD.




### CONCRETE WASHOUT (BMP-99)

NOT TO SCALE



### VICINITY MAP



NOT TO SCALE



### SHEET INDEX MAP

NOT TO SCALE

ARIZONA PUBLIC SERVICE-ELECTRICAL SOUTHWEST GAS CORPORATION - GAS SALT RIVER PROJECT - IRRIGATION SALT RIVER PROJECT - ELECTRICAL QWEST COMMUNICATIONS - CABLE TV (OTHER) **AGENCIES ALSO REQUIRING PERMITS WHEN INVOLVED ARE: MARICOPA COUNTY HIGHWAY DEPT., A.D.O.T., CITY OF PHOENIX, CITY OF PEORIA, SANTA FE RAILROAD, EL PASO NATURAL GAS, & MARICOPA COUNTY FLOOD CONTROL DISTRICT.	PLANS SUBMITTED TO (NAME)	PLANS REVIEWED BY (NAME)	PERMIT RECEIVED DATE



HESS - ROUNTREE, INC.

CONSULTING ENGINEERS & LAND SURVEYORS

9831 SOUTH 51ST STREET, SUITE C110  
PHOENIX, ARIZONA 85044 (480)496-0244

DES. **DRO** DRN. **JCW** CKD. **DRO** JOB NO. **1510-04**

## GENERAL NOTES FOR STORM WATER POLLUTION PREVENTION:

- A. A COPY OF THE CONTRACTOR'S NOI AND TWO (2) COPIES OF THE REVIEWED AND SIGNED SWPPP MUST BE RECEIVED BY THE CITY'S DEVELOPMENT SERVICES CENTER PRIOR TO ANY PERMIT BEING ISSUED. A COPY OF THE APPROVED GRADING AND DRAINAGE PLAN, TOGETHER WITH A COPY OF THE NOTICE OF INTENT (NOI) AND THE STORM WATER POLLUTION PREVENTION PLAN (SWPPP), SHALL BE MAINTAINED ON THE SITE AND AVAILABLE FOR REVIEW. THOSE ELEMENTS OF THE GRADING AND DRAINAGE PLAN PERTINENT TO OR REFERENCED ON THE SWPPP SHALL BE CONSIDERED A PART OF THE SWPPP. ALL STORM WATER POLLUTION PREVENTION PLANS SHALL FOLLOW THE DRAINAGE DESIGN MANUAL FOR MARICOPA COUNTY, ARIZONA, VOLUME III, EROSION CONTROL.
- B. THE CITY'S REVIEW OF ALL AZPDES SUBMITTALS INCLUDING NOI, NOT & SWPPP IS INTENDED AS REVIEW ONLY, AND DOES NOT CONSTITUTE APPROVAL OF THE METHODS OR PLANS FOR MANAGING THE STORM WATER AND PROTECTING THE WATERS OF THE UNITED STATES. THE CONTRACTOR IS SOLELY RESPONSIBLE FOR ENSURING THAT ALL REQUIREMENTS OF THE CLEAN WATER ACT ARE ADHERED TO.
- C. THE CITY'S ENGINEERING DIVISION SHALL BE NOTIFIED 48 HOURS BEFORE ANY ON-SITE AND/OR OFF-SITE CONSTRUCTION BEGINS. PHONE: 623-390-3630.
- D. THE OPERATOR SHALL OBTAIN A DUST CONTROL PERMIT FROM MARICOPA COUNTY DEPARTMENT OF ENVIRONMENTAL SERVICES AND PERFORM MEASURES TO PREVENT EXCESS DUST.
- E. THE OPERATOR SHALL PERFORM, AT A MINIMUM, A VISUAL INSPECTION OF THE CONSTRUCTION SITE ONCE EVERY MONTH AND WITHIN 24 HOURS OF RAINFALL GREATER THAN OR EQUAL TO ONE-HALF INCH. THE OPERATOR SHALL PREPARE A REPORT DOCUMENTING HIS/HER FINDINGS ON THE CONDITIONS OF THE SWPPP CONTROLS AND NOTE ANY EROSION PROBLEMS.
- F. THE OPERATOR'S REPORT IS TO BE SUBMITTED TO THE CITY'S INSPECTOR FOR REVIEW. FACILITIES SHALL BE MAINTAINED AS NECESSARY TO ENSURE THEIR CONTINUED FUNCTIONING. IN ADDITION, ALL TEMPORARY SILTATION CONTROLS SHALL BE MAINTAINED IN A SATISFACTORY CONDITION UNTIL SUCH TIME THAT CLEARING AND/OR CONSTRUCTION IS COMPLETED, PERMANENT DRAINAGE FACILITIES ARE OPERATIONAL, AND THE POTENTIAL FOR EROSION HAS PASSED.
- G. THE OPERATOR SHALL AMEND THIS PLAN AS NECESSARY DURING THE COURSE OF CONSTRUCTION TO RESOLVE ANY PROBLEM AREAS, WHICH BECOME EVIDENT DURING THE CONSTRUCTION AND/OR DURING RAINFALLS. ALL CHANGES TO THE SWPPP MUST CONFORM TO THE DRAINAGE DESIGN MANUAL FOR MARICOPA COUNTY-VOLUME III, EROSION CONTROL.
- H. THE PERMIT TEE SHALL FILE A NOTICE OF TERMINATION (NOT) AFTER COMPLETION OF CONSTRUCTION AND PLACEMENT OF FINAL LANDSCAPE MATERIALS. A COPY OF THE NOT IS TO BE SUBMITTED TO THE CITY'S ENGINEERING DIVISION TO CLOSE THE SWPPP PERMIT.
- I. THE PERMIT TEE SHALL SAVE ALL RECORDS, INCLUDING THE NOI, SWPPP, NOT, AND INSPECTION REPORTS, ON FILE FOR MINIMUM OF THREE YEARS FROM THE DATE OF FILING THE NOT.
- J. THE IMPLEMENTATION OF THESE PLANS AND THE CONSTRUCTION, MAINTENANCE, REPLACEMENT, AND UPGRADING OF THESE FACILITIES IS THE RESPONSIBILITY OF THE PERMIT TEE/CONTRACTOR UNTIL ALL CONSTRUCTION IS APPROVED AND THE NOT IS SUBMITTED TO THE CITY'S ENGINEERING DIVISION.
- K. THE FACILITIES SHOWN ON THIS PLAN MUST BE CONSTRUCTED IN CONJUNCTION WITH ALL CLEARING AND GRADING ACTIVITIES IN SUCH A MANNER AS TO INSURE THAT SEDIMENT-LADEN WATER DOES NOT ENTER THE CITY'S DRAINAGE SYSTEM OR VIOLATE APPLICABLE WATER STANDARDS. THE FACILITIES MUST BE INSTALLED AND IN OPERATION PRIOR TO ANY GRADING OR LAND CLEARING

### LEGEND:

- ☐ CATCH BASIN  
● AREA DRAIN OR IN LINE DRAIN  
☐ CONCRETE WASHOUT  
— STORM DRAIN PIPE  
— DRAINAGE DIRECTION

## COVER SHEET



### GLENDALE ELEMENTARY SCHOOL DISTRICT NO. 40

### DRAINAGE CORRECTIONS AT GLENDALE CHALLENGER MIDDLE SCHOOL

DRAWING STATUS	SHEET	OF
1ST CITY SUBMITTAL	1	2
DATE: 8-10-16		C-7









HESS - ROUNTREE, INC.  
CONSULTING ENGINEERS & LAND SURVEYORS  
9831 SOUTH 51ST STREET, SUITE C110  
PHOENIX, ARIZONA 85044 (480)496-0244

DES. **DRO** DRN. **JCW** CKD **DRO** JOB NO. **1510-04**

**CONSTRUCTION NOTES:**


- ① INSTALL MIRAFI FABRIC INLET PROTECTION (BMP-69).
- ② INSTALL CONCRETE WASHOUT BASIN (BMP-69). EXACT LOCATION OF INSTALLATION PER CONTRACTOR



STORM WATER MANAGEMENT PLAN			
GLENDALE ELEMENTARY SCHOOL DISTRICT NO. 40			
DRAINAGE CORRECTIONS AT			
GLENDALE CHALLENGER MIDDLE SCHOOL			
DRAWING STATUS	SHEET	OF	C-8
1ST CITY SUBMITTAL			
	2	2	
DATE:	8-10-16		



151004SW2.DWG



## SECTION 02 21 13

### CONSTRUCTION STAKING

Construction staking shall be performed by a licensed Surveyor acceptable to the Architect. Staking will be paid from the Construction Staking Allowance in the Contract.


Stakes: A minimum one set of construction grade stakes or "blue-tops" if possible of the following kind and at the stated interval shall be set. Blue-tops shall be set for all finish grading, sidewalk, curbing, concrete valley gutters, paving subgrade and A.B.C. and shall be left in place until checked and certified by the Civil Engineer.

1. Field staking control.
2. Two site benchmarks.
3. Mark out demo/sawcuts.
4. Rough grading cut and fill for onsite: at 50-foot intervals and grade breaks.
5. Concrete sidewalk: line and grade at 25-foot intervals and grade breaks.
6. Storm drain: 25-foot intervals and grade breaks.
7. As-builts finish grade.
8. Storm drain area drains/catch basins: location and elevation.
9. Prepare and submit as-built drawings to Contractor for submittal.
10. Office computer calculation for above staking.

**END OF SECTION**

## SECTION 31 01 00

### EARTHWORK



#### PART 1 GENERAL

##### 1.01 SUMMARY

- A. Section Includes: Perform earthwork as shown on the Drawing and as specified herein.

##### 1.02 QUALITY ASSURANCE

- A. Regulatory Requirements: Procure necessary permits or certificates required by City of Phoenix, State of Arizona and Maricopa County. Comply with applicable federal, state and local ordinances, including MAG Standard Specifications and Details. Owner to pay for permits.
- B. Layout of all Work under this Section shall be made by a licensed Engineer/Surveyor acceptable to the Architect.
- C. General Contractor shall give the Work his personal supervision. In his absence, he shall leave a responsible representative in charge who shall have the authority to receive and execute orders from the Architect and/or his representative.

##### 1.03 PROJECT/SITE CONDITIONS

- A. Environmental Requirements: No fill materials shall be placed, spread or rolled during unfavorable weather conditions. When the Work is interrupted by rain, fill operations shall not be resumed until it can be shown to the Civil Engineers/Architect's satisfaction that the moisture content and density of the previously placed fill are as specified.
- B. Visit the site. Examine and note conditions as to the character and extent of Work involved.

#### PART 2 PRODUCTS

##### 2.01 FILL

- A. Cleaned onsite soils may be used for fills in all areas of the site.
- B. Fill materials shall be approved by the Geotechnical Engineer and Civil Engineer and shall have low swell potential and be free of organic or deleterious material.
- C. Imported fill of low or non-expansive soils shall conform with the following requirements:

Maximum Percent Passing	
No. 200 Sieve	15 percent
Maximum Particle Size	6 inches (1 inch in landscape or turf areas)
Maximum Swell Potential	1.5 percent *
Within exterior concrete slabs	

\*Based on a sample which is remolded to 95% of the ASTM D698 maximum dry density at a moisture content of 2 percent below optimum, placed under a surcharge load of 100 psf and wetted.

## **PART 3 EXECUTION**

### **3.01 PREPARATION**

- A. Existing Utilities:
  - 1. Where existing utilities not shown on the Drawings are encountered, support, shore up, protect same and immediately notify Engineer and General Contractor. Allow entrance, opportunity and ample time for measures necessary for continuance and/or relocation of such services.
  - 2. Where noted on Drawings, cut and cap all street connections encountered in the excavating along curb line and mark location so they can subsequently be located and reconnected as required.
- B. Protection:
  - 1. Keep all excavations, pits, trenches, etc. entirely free from water.
  - 2. Protect excavations from rain or water from any source during construction. Use suitable pumping equipment or other means as required by conditions. Continue pumping as necessary until completion of project or until released by Engineer.
  - 3. Conduct Work in an orderly manner so as not to create a nuisance. Dirt shall not be permitted to accumulate on streets or sidewalks nor to be washed into sewers.
  - 4. During construction operations and after building construction, buildings shall be protected from surface water run-off and drainage from surrounding heights. Run-off water shall be diverted around buildings and construction operations.
- C. Layout:
  - 1. Maintain all bench marks, control monuments and stakes, whether newly established by Surveyor or previously existing. Protect from damage and dislocation. If necessary to disturb existing bench marks, have Surveyor reestablish in a safe place.
  - 2. If any discrepancies are found by Surveyor between the Drawings and actual conditions at the site, Engineer reserves the right to make such minor adjustments in Work specified as necessary to accomplish the intent of the contract Documents, without increased cost to Owner.

### **3.02 EXCAVATABILITY**

- A. The excavatability of site materials is difficult to evaluate based only on the exploration equipment used during the geotechnical design report. Therefore, the Geotechnical Engineer recommends that the Contractor evaluate the excavatability of site materials by performing test excavations with the size and type of equipment that Contractor plans on using at the site.
- B. The near surface and underlying soils can probably be removed with conventional excavating equipment. Deeper excavations may be slower and more difficult to accomplish due to caving and presence of oversized material. Caving should be expected in the non-cohesive granular soils encountered. OSHA requires all excavations over five feet in depth, in which personnel are to enter, be either braced or sloped in accordance with OSHA regulations.



### 3.03 WORKABILITY

- A. Wetting site soils such that moisture contents are at or above optimum could result in some soil pumping under dynamic loadings such as heavy construction equipment driving over the area. In the building area, some pumping is not detrimental to foundation or floor slabs provided the specified percent compaction is achieved. However, in flexible pavement areas where pumping has occurred, and in building areas where severe pumping has damaged subgrade conditions, the area shall be allowed to dry until soils are workable without pumping or the wetted areas removed and replaced with drier site soils.

### 3.04 GRADING

- A. General Contractor shall provide personal supervision for the Work. Leaving a responsible representative in charge, when absent, who shall have the authority to receive and execute instructions from the Architect or his representative.
- B. Grading tolerance shall be +0.00 feet and -0.10 feet.
- C. The following requirements are for site grading under, within and extending five feet beyond the sidewalks, exterior concrete slabs, and concrete fire lanes.
- D. Strip the entire site of all existing fill zones, any backfill zones and any unstable soils. During stripping observe the surface for evidence of buried debris, vegetation or disturbed materials which will require additional removal. If encountered, these materials shall be removed. Areas steeper than 5H to 1V should be benched and any depressions widened to accommodate compaction equipment.
- E. Widen any resulting depressions as necessary to accommodate compaction equipment and provide a level base for placing fill.
- F. Prepare the ground surface in fill areas and in areas cut to grade by scarifying, moisture conditioning and compacting the exposed surface soils to a minimum 10-inch depth. Moisture conditioning and compaction shall meet requirements under Section 3.07, Compaction.
- G. Moisture condition and place engineering fill material required to elevate areas to specified subgrade elevations.
- H. Placing, Spreading and Compacting Fill Materials: Fill materials shall be placed and compacted in horizontal lifts of thickness compatible with the compaction equipment used. Each layer shall be spread evenly, moisture conditioned and compacted per Section 3.7, Compaction. The Contractor shall widen any depressions as necessary to accommodate compaction equipment and provide a level base for placing fill. Compaction of each layer shall be continuous over its entire area and the compaction equipment shall make sufficient trips to insure that the required density has been obtained. No lift shall be placed until the previous lift has been approved. Fill operation shall be continued until the fill has been brought to the finished slopes and elevations shown on the Drawings. Imported fill shall conform to the requirements previously defined.
- I. Compacted subgrade shall be maintained in a moist state and shall not be allowed to significantly dry prior to placing more fill or base course.

### 3.05 EXCAVATION

- A. Excavation consists of removal and disposal of materials encountered to obtain required subgrade elevations.
- B. Excavation for foundations and footings shall have clean vertical walls, all corners squared up. Keep entire excavation free from any loose material. Excavation shall conform to dimensions and elevations indicated with allowance for erection of forms, shoring and inspection of footings.
- C. Material to be excavated shall be non-classified and shall include all earth or other materials encountered in excavating and grading. Where material encountered within the limits of Work is considered unsuitable by the Architect, such material shall be excavated below the grade shown on the Drawings as directed, and replaced with suitable material.
- D. Earth forms for footings may be permitted provided the earth is suitable and self-supporting as approved by the Architect or Geotechnical Engineer. Earthbank forms for foundation walls will not be permitted.
- E. Unauthorized excavation consists of materials beyond indicated subgrade elevations or dimensions without specific direction of the Architect. Under footing, foundation bases, or retaining walls, fill unauthorized excavations by extending the indicated bottom elevations of footing or base at the excavation bottom, without altering required top elevation. Clean concrete fill may be used to bring elevations to proper position, only when acceptable to the Architect. Elsewhere, backfill and compact unauthorized excavation as specified for authorized excavations, unless otherwise directed by the Architect. Costs for testing, if required, shall be borne by the Contractor.
- F. Stockpile satisfactory materials where directed, until required for backfill or fill. Locate and retain materials away from edge of excavations, even though such excavations are sheeted and braced to prevent such material falling or sliding into the excavations.
- G. Maintain sides and slopes of excavations in a safe condition until completion of backfilling, by scaling, benching, shelving or bracing. Take precautions to prevent slide or cave-ins.

### 3.06 BACKFILLING

- A. Place backfill about the buildings and structures as far as practical, as the Work of construction progresses. Backfilling against concrete work shall be done only when approved and directed. Backfill shall be deposited in layers of not more than six inches (6") in depth, and for the full width of the cross section. The material shall be carefully watered during placing by means of a fine spray or other approved method, so that each layer shall be thoroughly and uniformly wetted as directed by the Architect. The moisture content of all the material shall be carefully controlled at all times, and shall be checked at proper intervals to insure correct moisture content for compaction specified.

Each layer of fill material shall be compacted by hand and machine tampers to the density required in Section 3.07 COMPACTION when forming subgrade for concrete areas or supporting concrete floor slabs or supporting building footings.

- J. Backfilling of trenches shall progress as rapidly as the construction and testing of the Work will permit. In back-filling pipe trenches, approved fill shall first be compacted on both sides of the pipe in eight inch (8") layers to a depth of one foot over the top of the pipe. The remainder of the trenches shall be backfilled in compacted one-foot layers, except that fill in trenches in paved areas shall be compacted in six inch (6") layers to required grade.

### 3.07 COMPACTION

Compaction of cleaned exposed soil, imported soils, each lift of backfill, subbase fill, imported fill and base course materials shall be accomplished to the following density criteria:

<u>Material</u>	<u>Percent Compaction</u> <u>(ASTM D698)</u>
Cleaned exposed soil, imported soils, backfill and subbase fill:	
Below concrete sidewalk/slabs	90 max
Below pavement sections	95 min
Top soil in playfields and landscape areas	85-90 min
Miscellaneous Backfill not under buildings, concrete or paved areas	90 min

Compaction of clean, exposed site soils or fills of cleaned site soils within sidewalks and exterior concrete slab areas shall be accomplished with soils uniformly mixed at a moisture content of optimum to optimum plus three percent (+3%).

Compaction of imported soils within sidewalks and exterior concrete slab areas shall be accomplished with soils uniformly mixed at a moisture content of optimum plus or minus three percent ( $\pm 3\%$ ).

Natural undisturbed soils or compacted soils subsequently disturbed or removed by construction operations shall be replaced with materials compacted as specified above.

### 3.08 FINISH GRADING

- A. Perform finish grading required as indicated or reasonably inferred to permit installation of Work of others as shown on Drawings. After final clean-up of exterior and removal of trash and construction of the buildings, the site shall be graded to slopes and elevations as indicated on the Drawings and as directed by the Architect. Additional material required for finish grading shall be of topsoil quality, provided, placed and graded by the Contractor. Lawn areas around walks shall provide good slope drainage away from buildings as indicated. Rake indicated site and lawn areas smooth and level to a tolerance of plus or minus 0.1 foot from elevations indicated.
- B. Existing clean site soils free of debris and rocks over 1 inch in diameter may be used for fills in landscape areas.

### 3.09 FIELD QUALITY CONTROL

- A. Test: Field density tests shall be made by an approved independent soils testing laboratory, as defined herein, or at the request of the Architect and paid for with the testing allowance. When these tests indicate that the density of any area(s) is below the required density, that particular area(s) shall be reworked until the required density has been obtained.
- B. Restore any damage to adjacent properties, street and the like, caused by operations of this Section to original condition without additional cost to Owner.


### 3.10 CLEANING

- A. Conduct Work in an orderly and workmanlike manner and so as not to create a nuisance. Dirt shall not be permitted to accumulate on streets or sidewalks nor to be washed into sewers.
- B. During the course of the Work and on completion of the Work, remove excess materials, equipment and debris and dispose of away from premises. Leave Work in clean condition.

### **3.11 AS-BUILT DRAWINGS**

- A. The Surveyor shall provide certified, signed and sealed as-builts for all finish grade elevations indicated on the Drawings on 4 mil mylar and AutoCAD disk (2011 version or later). The Contractor shall schedule the Work to allow the Surveyor to obtain the as-builts. This Work will not be accepted until as-builts are approved by the Design Civil Engineer and City of Glendale.

**END OF SECTION**



## SECTION 32 16 00

### CONCRETE CURBS, GUTTERS, SIDEWALKS, AND DRIVEWAYS

#### PART 1 GENERAL

##### 1.01 SUMMARY

- A. Section includes: Installation of concrete curbs, gutters, sidewalks, and driveways as shown on the Drawings and as specified herein.

##### 1.02 REFERENCE STANDARDS

- A. MAG Specifications Section 340: Concrete curb, gutter, sidewalk, driveways and alley entrances.
- B. City of Glendale and MAG Standard Details.

##### 1.03 SUBMITTALS

- A. Mix design to Architect a minimum of seven (7) days prior to start of construction.
- B. Tests: Submit three certified copies of test results, samples and suppliers certification that materials conform to specified criteria.

##### 1.04 QUALITY ASSURANCE

- A. Contractor shall obtain, at his expense, all necessary construction permits and shall coordinate all necessary inspections with City of Glendale.

#### PART 2 PRODUCTS

##### 2.01 MATERIALS

- A. Concrete Curb, Gutter (where not next to driveway) and Sidewalk:  
Concrete: 2,500 psi (28 day strength), MAG Section 725
- B. Concrete Driveway and Curb and Gutter (where next to driveway):  
Concrete: 4,000 psi (28 day strength), MAG Section 725

#### PART 3 EXECUTION

##### 3.01 CONSTRUCTION METHODS FOR CONCRETE CURB, GUTTER, SIDEWALK AND DRIVEWAY

- A. Execute Work in accordance with MAG Specifications Section 340 and MAG Details and City of Glendale specifications and details.
- B. Sawcut existing pavements and concrete joined by new construction to a true line with straight vertical edges free from irregularities.
- C. Construct and compact true to grades and line shown on the Drawings.
- D. Curb machines may not be used.



- E. Do not place material displaced in the construction on the base and/or surfacing material already in place on the roadway nor the excavated material in such a manner as to interfere with access to property or traffic flow in the street.

### **3.02 TESTING**

- A. Inspection and testing will be performed by an independent testing agency employed and paid for in accordance with Section 01 43 26.
- B. Provide free access to Work and cooperate with appointed firm.
- C. Submit 3 copies of proposed mix design of each class of concrete including water/cement/strength and all supporting data to testing agency and Architect for review a minimum seven (7) days prior to commencement of Work.
- D. Tests of cement and aggregates may be performed to ensure conformance with requirements stated herein.
- E. Four (4) concrete test cylinders will be taken for every 100 or less cubic yards of each class of concrete placed. Make and cure concrete compressive strength test specimens in accordance with ASTM C31. Construct storage box of sufficient size and design to provide protection required by paragraph 7(a).
- F. One (1) additional test cylinder will be taken during cold weather concreting, and be cured on job site under same conditions as concrete it represents.
- G. One (1) slump test will be taken in accordance with ASTM C-143 of each set of compressive strength test cylinders taken.
- H. Where concrete is placed by pumping, tests shall be taken at the truck before concrete is placed in the pump.
- I. Tests to be performed by testing agency personnel in accordance with ASTM C39.

### **3.03 CLEANING**

- A. During the course of the Work and on completion of the Work, remove excess materials, equipment and debris and dispose of away from premises. Leave Work in clean condition.

### **END OF SECTION**

**SECTION 32 71 00**  
**STORM DRAIN SYSTEM**



**PART 1 GENERAL**

**1.01 SUMMARY**

- A. Section includes: Storm Drain Construction as shown on the Drawings and as specified herein.

**1.02 SUBMITTALS**

- A. General: Submittal requirements are specified in Section 01300 - Submittals.
- B. Quality Control Submittals:
1. Storm drainage pipe, fittings, cleanouts, etc.
  2. Area drains, catch basins
  3. Dry well
  4. Oil grease interceptor

**1.03 PROJECT/SITE CONDITIONS**

- A. Visit the site. Examine and note conditions as to the character and extent of Work involved.

**1.04 QUALITY ASSURANCE**

- A. Contractor shall obtain all necessary construction permits and shall coordinate all necessary inspections with the City of Glendale. Owner to pay for permits.
- B. Construction staking shall be performed by a State of Arizona licensed Surveyor acceptable to the Architect and Owner.

**PART 2 PRODUCTS**

**2.01 MATERIALS**

- A. As specified on the Drawings and as allowed per MAG Specifications and City of Glendale codes and requirements and as indicated on Drawings.

**PART 3 EXECUTION**

**3.01 EXAMINATION**

- A. Verification of Conditions: Failure to observe this requirement constitutes a waiver to subsequent claims to the contrary and holds Contractor responsible for correction(s) Architect may require. Commencement of Work will be construed as acceptance of subsurfaces.
- B. Coordination with other work: Coordinate with other work which affects, connects with, or will be concealed by this Work.

### **3.02 STORM DRAIN CONSTRUCTION**

- A. Storm drain construction shall conform to the applicable requirements of MAG Specifications, Section 601, Trench Excavation, Backfilling and Compaction, Section 745, P.V.C. Sewer Pipe and Fittings and Section 603, Installation for High Density Polyethylene Pipe. Backfill and compaction shall be performed per Specifications, Section 02200, Earthwork, except as modified below.
- B. Storm drain pipe shall consist of installing P.V.C. or H.D.P.E. storm drain pipe to the alignment and grades indicated on the Drawings.
- C. Granular bedding will be required from four inches (4") below the bottom of the pipe to one foot (1') above the pipe. All clean dirt spoils generated from the installation of the storm drain lines shall be removed from the site and disposed of legally.

### **3.03 CATCH BASINS, AREA DRAINS, DRYWELLS AND OIL/GREASE INTERCEPTOR**

- A. Catch Basins, area drains, Bubbler Boxes, Drywells and oil/grease interceptors shall be installed per the details on the Drawings and per the MAG Standard Details as indicated on the Drawings.


### **3.04 "AS-BUILT" DRAWINGS**

- A. The Contractor's Surveyor shall provide as-builts for all site storm drain lines (outside building areas). The Contractor shall schedule the Work to allow the Surveyor to obtain as-builts for the actual locations and elevations of the completed storm drain line including location, invert elevation and rim elevation of all catch basins, area drains, cleanouts, bends, etc. As-builts shall be provided on 4 mil mylars, certified, sealed and signed by the Surveyor. Mylar and Auto CADD 2011 disk as-builts shall be submitted to the Design Civil Engineer, Owner, and City for review and approval. Project is not accepted until all parties listed above approve as-built Drawings.

### **3.05 CLEANING**

- A. During the course of the Work and on completion of the Work, remove excess materials, equipment and debris and dispose of legally away from premises. Leave Work in clean condition.

**END OF SECTION**



**SECTION 33 70 00**

**DECOMPOSED GRANITE**

DECOMPOSED GRANITE

The Work under this item shall consist of installing a 2 inch compacted thickness of decomposed granite at the locations as indicated on the plans. The Work shall conform to MAG Specifications Section 430.4 except that no 10-mm black polyethylene liner will be required. Two applications of pre-emergent (one prior to placement of granite and one after placement) will be required.

Granite shall conform to MAG Specifications Section 702.4 and have a size of 1/4 inch minus. Color shall be Madison Gold to match the existing granite at the site.

**END OF SECTION**





# Glendale Elementary School District SFB Projects: Construction Cost Estimates

BRG: Project: Scope: Updated 9/1/16 Cost Estimate:

070440106-9999-010-BRG	Mensendick Structural		
	Phase 1	Temporary bracing of non-structural CMU walls - 55 panels	\$ 192,500.00
		<b>Estimated Phase 1 Subtotal</b>	<b>\$ 192,500.00</b>
	Phase 2	Installation of masonry control joints/repair CMU	\$ 80,000.00
		Securing of decorative wythe of CMU	\$ 60,000.00
		Repair of CMU surround the stair stepped cracks	\$ 100,000.00
		Install helical piers	\$ 400,000.00
		Grout injection of slab	\$ 100,000.00
		Repair of the cracked CMU and rusted reinforcing	\$ 250,000.00
		Riddle blockfill of new masonry, reseal with 10 year weatherization warranty and coating of Drylok extreme at exposed footing	\$ 200,000.00
		Remove turf and irrigation against building and replace with decomposed granite from face of wall to 5'-0" away from building	\$ 52,000.00
		<b>Estimated Phase 2 Subtotal</b>	<b>\$ 1,242,000.00</b>
		<b>Estimated Total Repair:</b>	<b>\$ 1,434,500.00</b>

August 26, 2016



Mr. Greg Gilliam  
Director of Maintenance & Operations  
Glendale Elementary School District #40  
Support Services  
7015 W. Maryland Avenue  
Glendale, AZ 85303

Robert L Pian, AIA  
William R Pittenger, RA, CSI  
Mark A Davenport, AIA, LEED AP  
Herb W Schneider, FAIA  
Howell Lewis Shay, AIA

**RE: Glendale Elementary School District #40  
SFB Corrections at Mensendick School – Additional Services Request**  
SPS+ Architects Fee Proposal 1535M.1  
GESD Purchase Order 3602080  
**SFB Project # 070440106-9999-010-BRG**

Dear Mr. Gilliam:

Thank you for the opportunity to work with you on your SFB Corrections at the above referenced School. We understand this will be an SFB funded project using Building Renewal Grants. Thank you in advance for your consideration of our additional services request.

Additional Services Scope of work:

Structural remediation in accordance with the attached coversheet from our structural engineer Bixler and associates. Please see below for an executive summary:

- Structural: Recommend to make repairs to cmu and interior slabs for aesthetic and functionality reasons. Weatherization/Structural: please see below. This includes painting at areas of repair.
- Weatherization project conditions: There was a significant amount of damage discovered for the reinforcing steel near the bottom of the walls. When you add the moisture conditions present, the amount of cracking, the fact that basically all the holes that had reinforcing, the reinforcing was approximately 33% to 66% rusted. In essence, at all those cracks along grade, the CMU face shells are basically delaminated, so the old 8" wall is now 5-6" or 4" at that point and then obviously the wall that is not close to current code now, is much worse. The engineer is unable to perform calculations without knowing to what extent the steel has delaminated. Therefore, I concur with the engineer and recommend to move forward with these repairs as soon as possible and brace immediately. In addition to civil projects that may be happening at these sites, we recommend removing grass and irrigation within 5 feet of the buildings.

Fee Proposal: \$73,875

Fee includes Architectural and Structural services for the following:

- Coordination of immediate implementation of wall bracing.
- Construction documents and construction administration utilizing a district procured contractor of the scope of work described above and attached.
- Special structural inspections during construction administration.
- Reimbursable expenses for printing, travel, etc.

Please let me know if you have any comments regarding our proposal. We are anticipating this proposal being approved at the September 7<sup>th</sup>, 2016 SFB board meeting.

Sincerely,

SPS+ ARCHITECTS, LLP

A handwritten signature in black ink, consisting of a stylized 'M' followed by a long horizontal stroke that curves slightly upwards at the end.

Mark Davenport, AIA, LEED AP BD&C  
Partner

enclosure

Cc: Mike Barragan, David Kennon, Terry Tower, Jennifer Bowen



# DAVID BIXLER & ASSOCIATES

## Structural Engineering

### VISION

August 23, 2016

Our vision is

to be recognized

throughout the

southwest as the

leader in structural

engineering.

Mark Davenport AIA, CEFPI, LEED AP, BD+C  
SPS+ ARCHITECTS LLP  
8681 E. Via de Negocio  
Scottsdale, AZ 85258

**Re: William Jack / Don Mensendick Elementary School  
Glendale, AZ**

### COMMITMENT

Dear Mr. Davenport:

We are committed to

technological

leadership

innovative and cost-

effective solutions

quality work

client satisfaction.

Per your request, we visited William Jack / Don Mensendick Elementary School on several occasions. I have reviewed the reports from Speedie and Associates, which are attached at the end of this report, along with pictures from our site visit during the CMU removal to investigate the reinforcing and typical pictures of the types of cracking along the buildings. We also reviewed the existing plans of the buildings which we have received. The purpose of this report is to review the conditions of the existing buildings along with the reports prepared by other consultants, and to recommend a plan of action going forward on the best course of action to remedy the deficient areas.

The buildings are typically steel and wood framed roofs bearing on wood posts with CMU exterior walls and concrete spread footings.

### VALUES

Our team delivers

integrity

service

collaboration

quality

efficiency

Based on the surface penetrating radar investigations Speedie and Associates performed of the walls, the vertical reinforcing appears to be randomly installed in the additions to each of the classrooms but was missing from the existing walls that were part of the original construction. Some of the additions had the reinforcing installed in what appears to be correct while other areas were sporadic. Probably about 50% of the additions were installed properly while the others were deficient in some manner. The readings from the original and the additional slab-on-grade seemed to indicate that there was not any reinforcing in the slab and no ties tying the new to the existing.



# DAVID BIXLER & ASSOCIATES

## Structural Engineering

Based on the soils investigations performed by Speedie and Associates, there does not appear to be a specific cause of the masonry distress due to the soils themselves, except the fact that the soil is very moist. The moisture fluctuations in the soils will have a tendency to cause continuous movement which will induce stresses on the buildings and sometimes resulting in cracks in the CMU. My understanding is that there is currently a project in place that will solve or reduce the amount of moisture in the soil and will divert the water away from the walls.

From our review of the CMU demolition, and our cursory review of the buildings in general, we discovered numerous cracks and some rusted reinforcing.

From the four holes that were opened up to expose the reinforcing, we found rusted and deteriorated vertical and horizontal reinforcing in approximately half of the locations we inspected. The degree of rust varied from minor in some areas to significant in others. The soil was moist in these areas as well.

From our visual inspection, we noticed several cracks; too many to document them all. They basically fell into four general categories:

1. There were several areas where there are shrinkage cracks most likely due to insufficient or improper locations of masonry control joints or improperly installed masonry control joints (see photographs 1, 6, and 9 on building 1, photos 2 and 6 on building 5, photo 2, 4, 10 and 11 on building 7 and photo photos 3, 4, and 9 on building 10, photo 1 on building 11, photo 8 on building 12, photo 3 on building 15, photos 3, 4 and 5 on building 17, photos 4, 5 and 6 on building 18, photo 1 on building 21 and photo 2 on building 22). While these are not structural in nature, they will affect the water tightness of the building, and therefore I recommend that new masonry control joints be installed, and for the CMU in these areas to be tuck pointed and repaired or replaced as applicable. There were approximately 15-20 locations throughout the school where this occurred.
2. There were several areas where there was an added wythe of CMU probably for aesthetic reasons however it does not appear to be attached to the CMU and has a crack along the side of the added wythe (see photo 10 on building 1, photo 1 on building 4, photos 1 and 8 on building 5, photos 1, 5, 6, 15 and 16 on building 7, photos, 5, 6, and 7 on building 9, photos 1, 4 and 5 on building 15, photos 1, 2 and 4 on building 16, photos 1, 6, 7 and 8 on building 17, photo 3 on building 18 and photo 3 on building 22). I would recommend drilling and epoxying some anchors into the supporting wythe to stabilize to stabilize the extra wythe. This probably occurs in approximately 20 locations.
3. There were several areas where there were there are stair stepped cracks in the CMU walls of the buildings. It is apparent by the inspection of the walls and the current slopes in the interior slabs that the additions to the original construction have settled at some time. This may have occurred during or





# DAVID BIXLER & ASSOCIATES

## Structural Engineering

shortly after construction. There is also some stair stepped cracks in the original construction. The geotech report does not appear to indicate anything that would be a cause for concern or continued settlement. So it is most likely that the moisture in the soil has caused some foundation movements that have caused the cracking in the CMU and the sloping of the interior extension of these slabs. These issues at this point at most of the locations appear to be non-structural and can be repaired by properly installing repointing and repairing the CMU along with the ongoing project to solve the moisture problem in the soil. However, since this is a serviceability issue, one of the other options would be to install helical piers below the exterior walls and jack them back up to their original placement. Then the slab could be raised as required by grout or foam injection. These repairs would be quite costly, but could be done to make the buildings more functional (see photos 2, 3, 4, 5 and 8 on building 1, photos 1, 2 and 3 on building 2, photo 2 on building 3, photo 3 on building 4, photo 3, 4, 5 and 7 on building 5, photos 1, 2 and 8 on building 9, photo 2 on building 10, photo 1 on building 14, photo 2, 4 and 6 on building 15, photo 3 on building 16, photo 2 on building 17, and photos 1 and 2 on building 18). This would be acceptable in all areas where this occurs except for buildings 12 which has significant stair stepped cracking and actually has settled approximately one inch. This building should have helical piers installed below the footings and to jack them back into place and then pressure inject grout below slab to raise the slab back in place; then repoint and repair the CMU, adding some additional vertical reinforcing and grout to help stiffen the walls. The typical repairs would occur in approximately 20 locations.

4. The remaining photos appear to be related to moisture and the rusting of the reinforcing in the CMU. Since reinforcing when it rusts can grow to over 400% of its original size, it appears that the reinforcing has rusted and expanded and has cracked the CMU. This causes the face shells to delaminate and then the CMU is essentially reduced in size and therefore reduced in strength. There is no real way to determine the loss in strength without knowing the exact thickness of the delaminated CMU. But this is a very old building that does not comply with the current building codes, and additionally, there is reduced strength in the existing wall. The reduction in strength could easily range from 33% - 90%. Therefore, the CMU walls should be braced immediately until the repairs are complete. In addition, there is no real way to eliminate moisture from entering into the cracks in the CMU and to continue to make the condition worse. There is no easy or accurate way to determine the extents of the rusting in the CMU without removing the face shells and investigating the reinforcing as we did in those four locations. The repair for these locations would be extremely expensive, but would entail removing the CMU at the cracked locations and then removing and replacing the rusted reinforcing with new reinforcing, grout and CMU. This would need to be done in an explorative manner where you start at each of the cracks and then you expand outward until you get to undamaged CMU and reinforcing. Therefore, there is no real way to determine the extents, but due to the moisture conditions and the amount of cracking, I would not be surprised if 20%-33% of the length of the walls are damaged at grade in this manner.



# DAVID BIXLER & ASSOCIATES

## Structural Engineering

If the decision is to repair the school, then this should start immediately, and we should brace the CMU walls until the repairs are completed. Without knowing the extent of the damage, it is extremely difficult to determine how the walls will perform as the reinforcing continues to rust and the walls continue to worsen.

While it is extremely difficult to provide any budgetary numbers due to the uncertainty of the full scope and amount of damage, we estimate the following corresponding to the item numbers above:

- |  |           |
|--|-----------|
| 1) Temporary Bracing of CMU Walls:                                   | \$80,000  |
| 2) Installation of masonry control joints and repair of damaged CMU: | \$80,000  |
| 3) Securing of the decorative wythe of CMU:                          | \$60,000  |
| 4) Repair of the CMU surrounding the stair stepped cracks:           | \$100,000 |
| 5) Install helical piers:  | \$400,000 |
| 6) Grout injection of slab:  | \$100,000 |
| 7) Repair of the cracked CMU and rusted reinforcing:                 | \$250,000 |

Please understand that this report represents a professional opinion based upon the results of our limited observations, and past experience with similar conditions. Our study was strictly limited to visual observations as stated above. This report is not intended to be a complete or comprehensive study of the structure. We have not reviewed, nor have we been asked to review, the capacity of the existing structure per the current code. Our work has been performed in accordance with generally accepted principles and practices of structural engineering.

We cannot be responsible for any future changes in the condition of the structure. No warranty is provided, either expressed or implied.


If there are any additional concerns or questions, please feel free to contact our office. Thank you for the opportunity to assist you on this project.

Sincerely,

*David Bixler*

David Bixler, PE, SE President  
David Bixler & Associates, PLLC





**NOTES:**

1. EXISTING MASONRY WALL.
2. EXISTING WINDOW OPENING.
3. EXISTING WOOD COLUMN.
4. C6x8.2 CONT.
5. 1/2"Ø x 4" EMBED LAG SCREWS @ 24"O.C.
6. 1/2"Ø x 6" EMBED EPOXY BOLTS @ 24"O.C.
7. 1/4"x3"x1'-0" STEEL PLATE.

3

ELEVATION

N.T.S.




David Bixler & Associates  
Structural Engineering

8360 East Raintree Drive, Suite 110  
Scottsdale, Arizona 85260

Office: (480) 219-2886 Fax: (480) 588-8584  
www.dbaaeng.com

UNLESS THIS DRAWING IS SIGNED AND SEALED BY A LICENSED STRUCTURAL ENGINEER, IT IS A PRELIMINARY DESIGN AND SHALL NOT BE USED FOR CONSTRUCTION.

**DON MESSENDICK SCHOOL**  
5535 NORTH 67TH AVENUE  
GLENDALE, AZ 85301




DRAWN BY:	ERB
CHECKED BY:	WDB
JOB NO:	16.098
PRINTED:	08.31.2016

**SSK1**



**NOTES:**

1. EXISTING MASONRY WALL.
2. EXISTING WOOD COLUMN.
3. C6x8.2 CONT.
4. 1/2"Ø x 4" EMBED LAG  
SCREWS @ 24"O.C.
5. 1/2"Ø x 6" EMBED EPOXY  
BOLTS @ 24"O.C.
6. 1/4"x3"x1'-0" STEEL PLATE.



4

SECTION

N.T.S.




David Bixler & Associates  
Structural Engineering

8360 East Raintree Drive, Suite 110  
Scottsdale, Arizona 85260  
Office: (480) 219-2886 Fax: (480) 588-8584  
www.dbaaeng.com

UNLESS THIS DRAWING IS SIGNED AND SEALED BY A LICENSED STRUCTURAL ENGINEER, IT IS A  
PRELIMINARY DESIGN AND SHALL NOT BE USED FOR CONSTRUCTION

**DON MESSENDICK SCHOOL**  
5535 NORTH 67TH AVENUE  
GLENDALE, AZ 85301



DRAWN BY:	ERB
CHECKED BY:	WDB
JOB NO:	16.098
PRINTED:	08.31.2016

**SSK2**







# STRUCTURAL CALCULATIONS FOR MENSENDICK AND JACK ELEMENTARY SCHOOL WALL REPAIRS

DBAA Job No. 16.098

August 31, 2016

## PREPARED FOR:

Jennifer Bowen, Director of Design

SPS+ Architects LLP

[Jbowen@spsplusarchitects.com](mailto:Jbowen@spsplusarchitects.com)

480.544.5851



## PREPARED BY:

DAVID BIXLER & ASSOCIATES  
STRUCTURAL ENGINEERING  
8360 E. RAIN TREE DR., SUITE 110  
SCOTTSDALE, AZ 85260  
PHONE: (480) 219-2886  
[david.bixler@dbaaeng.com](mailto:david.bixler@dbaaeng.com)  
[www.dbaaeng.com](http://www.dbaaeng.com)



[illegible]

Title Block Line 1  
 You can change this area  
 using the "Settings" menu item  
 and then using the "Printing &  
 Title Block" selection.  
 Title Block Line 6

Project Title:  
 Engineer:  
 Project Descr:

Project ID:

Printed: 31 AUG 2016, 2:20PM

## Steel Beam

File = \\dbaa-sv2\projects\16096 Challenger Middle School\Engineering\16096 challenger.ec6  
 ENERCALC, INC. 1983-2016, Build 6.16.6.7, Ver.6.16.6.7

Lic. #: KW-06009174

Licensee: DAVID BIXLER AND ASSOCIATES

Description: cahnnel over column

Load Combination		Max Stress Ratios		Summary of Moment Values							Summary of Shear Values		
Segment Length	Span #	M	V	Mmax +	Mmax -	Ma Max	Mnx	Mnx/Omega	Cb	Rm	Va Max	Vnx	Vnx/Omega
Dsgn. L = 8.00 ft	1		0.000				2.34	1.40	1.00	1.00	-0.00	14.22	8.52

### Overall Maximum Deflections

Load Combination	Span	Max. "-" Defl	Location in Span	Load Combination	Max. "+" Defl	Location in Span
W Only	1	1.1153	4.023		0.0000	0.000

### Vertical Reactions

Support notation: Far left is #1

Values in KIPS

Load Combination	Support 1	Support 2
Overall MAXimum	0.960	0.960
Overall MINimum	0.432	0.432
+D+H		
+D+L+H		
+D+Lr+H		
+D+S+H		
+D+0.750Lr+0.750L+H		
+D+0.750L+0.750S+H		
+D+0.60W+H	0.576	0.576
+D+0.70E+H		
+D+0.750Lr+0.750L+0.450W+H	0.432	0.432
+D+0.750L+0.750S+0.450W+H	0.432	0.432
+D+0.750L+0.750S+0.5250E+H		
+0.60D+0.60W+0.60H	0.576	0.576
+0.60D+0.70E+0.60H		
D Only		
Lr Only		
L Only		
S Only		
W Only	0.960	0.960
E Only		
H Only		





# DAVID BIXLER & ASSOCIATES

## Structural Engineering

### VISION

August 23, 2016

Our vision is  
to be recognized  
throughout the  
Southwest as the  
leader in structural  
engineering.

Mark Davenport AIA, CEFPI, LEED AP, BD+C  
SPS+ ARCHITECTS LLP  
8681 E. Via de Negocio  
Scottsdale, AZ 85258

**Re: William Jack / Don Mensendick Elementary School  
Glendale, AZ**

### COMMITMENT

We are committed to

- technological leadership
- innovative and cost-effective solutions
- quality work
- client satisfaction.

As per your request, we visited the site on several occasions and have reviewed the reports from Speedie and Associates, and have attached them to the end of this report along with pictures from our site visit during the CMU removal to investigate the reinforcing and typical pictures of the types of cracking along the buildings. We have also reviewed the existing plans of the buildings which we received. The purpose of this report is to review the conditions of the existing buildings along with the reports prepared by other consultants and to recommend a plan of action going forward on the best course of action to remedy the deficient areas.

The buildings are typically steel and wood framed roofs bearing on wood posts with cmu exterior walls and concrete spread footings.

Based off of the surface penetrating radar investigations Speedie and Associates performed of the walls the vertical reinforcing appears to be randomly installed in the additions to each of the classrooms but was missing from the existing walls that were part of the original construction. Some of the additions had the reinforcing installed in what appears to be correct while other areas were sporadic. Probably about 50% of the additions were installed properly while the others were deficient in some manner. The readings from the original and the additional slab-on-grade seemed to indicate that there was not any reinforcing in the slab and no ties tying the new to the existing.

### VALUES

**Our team delivers**

- integrity
- service
- collaboration
- quality
- efficiency



# DAVID BIXLER & ASSOCIATES

## Structural Engineering

Based on the soils investigations performed by Speedie and Associates, there does not appear to be a specific cause of the masonry distress due to the soils themselves, except the fact that the soil is very moist. The moisture fluctuations in the soils will have a tendency to cause continuous movement which will induce stresses on the buildings and sometimes resulting in cracks in the cmu. My understanding is that there is currently a project in place that will solve or reduce the amount of moisture in the soil and will divert the water away from the walls.

From our review of the cmu demolition and our cursory review of the buildings in general, we discovered numerous cracks and some rusted reinforcing.

From the four holes that were opened up to expose the reinforcing, we found rusted and deteriorated vertical and horizontal reinforcing in approximately half of the locations we inspected. The degree of rust varied from minor in some areas to significant in others. The soil was moist in these areas as well.

From our visual inspection we noticed several cracks and too many to document all of them however. They basically fell into four general categories;

1. There were several areas where there are shrinkage cracks most likely due to insufficient or improper locations of masonry control joints or improperly installed masonry control joints (see photographs 1, 6, and 9 on building 1, photos 2 and 6 on building 5, photo 2, 4, 10 and 11 on building 7 and photo photos 3, 4, and 9 on building 10, photo 1 on building 11, photo 8 on building 12, photo 3 on building 15, photos 3, 4 and 5 on building 17, photos 4, 5 and 6 on building 18, photo 1 on building 21 and photo 2 on building 22). While these are not structural in nature they will affect the water tightness of the building and therefore I recommend that new masonry control joints be installed and for the cmu in these areas to be tuck pointed and repaired or replaced as applicable. There were approximately 15-20 locations throughout the school where this occurred.
2. There were several areas where there was an added wythe of cmu probably for aesthetic reasons however it does not appear to be attached to the cmu and has a crack along the side of the added wythe (see photo 10 on building 1, photo 1 on building 4, photos 1 and 8 on building 5, photos 1, 5, 6, 15 and 16 on building 7, photos, 5, 6, and 7 on building 9, photos 1, 4 and 5 on building 15, photos 1, 2 and 4 on building 16, photos 1, 6, 7 and 8 on building 17, photo 3 on building 18 and photo 3 on building 22). I would recommend drilling and epoxying some anchors into the supporting wythe to stabilize to stabilize the extra wythe. This probably occurs in approximately 20 locations.



# DAVID BIXLER & ASSOCIATES

## Structural Engineering

3. There were several areas where there were there are stair stepped cracks in the cmu walls of the buildings. It is apparent by the inspection of the walls and the current slopes in the interior slabs that the additions to the original construction have settled at some time. This may have occurred during or shortly after construction. There is also some stair stepped cracks in the original construction. The geotech report does not appear to indicate anything that would be a cause for concern or continued settlement. So it is most likely that the moisture in the soil has caused some foundation movements that has caused the cracking in the cmu and the sloping of the interior extension of these slabs. These issues at this point at most of the locations appear to be non-structural and can be repaired by properly installing repointing and repairing the cmu along with the ongoing project to solve the moisture problem in the soil. However since this is a serviceability issue, one of the other options would be to install helical piers below the exterior walls and jack them back up to their original placement. Then the slab could be raised as required by grout or foam injection. These repairs would be quite costly, but could be done to make the buildings more functional (see photos 2, 3, 4, 5 and 8 on building 1, photos 1, 2 and 3 on building 2, photo 2 on building 3, photo 3 on building 4, photo 3, 4, 5 and 7 on building 5, photos 1, 2 and 8 on building 9, photo 2 on building 10, photo 1 on building 14, photo 2, 4 and 6 on building 15, photo 3 on building 16, photo 2 on building 17, and photos 1 and 2 on building 18). This would be acceptable in all areas where this occurs except for buildings 12 which has significant stair stepped cracking and actually has settled approximately one inch. This building should have helical piers installed below the footings and to jack them back into place and then pressure inject grout below slab to raise the slab back in place. Then repoint and repair the cmu and adding some additional vertical reinforcing and grout to help stiffen the walls. The typical repairs would occur in approximately 20 locations.
4. The remaining photos appear to be related to moisture and the rusting of the reinforcing in the cmu. Since reinforcing when it rusts can grow to over 400% of its original size, it appears that the reinforcing has rusted and expanded and has cracked the cmu. This causes the face shells to delaminate and then the cmu is essentially reduced in size and therefore reduced in strength. There is no real way to determine the loss in strength without knowing the exact thickness of the delaminated cmu. But you have a very old building that does not comply with the current building codes and then you have additionally reduced the strength of the existing wall. The reduction in strength could easily range from 33% - 90%. In addition there is no real way to eliminate moisture from entering into the cracks in the cmu and to continue to make the condition worse. There is no easy or accurate way to determine the extents of the rusting in the cmu without removing the face shells and investigating the reinforcing as we did in those four locations. The repair for these locations would be extremely expensive but would entail removing the cmu at the cracked locations and then removing and replacing the rusted reinforcing with new reinforcing, grout and cmu. This would need to be done in an explorative manner where you



# DAVID BIXLER & ASSOCIATES

## Structural Engineering

start at each of the cracks and then you expand outward until you get to undamaged cmu and reinforcing. Therefore, there is no real way to determine the extents, but due to the moisture conditions and the amount of cracking, I would not be surprised if 20%-33% of the length of the walls are damaged at grade in this manner.

If the decision is to repair the school, then this should start immediately, and we should brace the cmu walls until the repairs are completed. Without knowing the extent of the damage, it is extremely difficult to determine how the walls will perform as the reinforcing continues to rust and the walls continue to worsen.

While it is extremely difficult to provide any budgetary numbers due to the uncertainty of the full scope and amount of damage, we estimate the following corresponding to the item numbers above;

1) Installation of masonry control joints and repair of damaged cmu:	\$80,000
2) Securing of the decorative wythe of cmu:	\$60,000
3) Repair of the cmu surrounding the stair stepped cracks:	\$100,000
4) Install helical piers:	\$400,000
5) Grout injection of slab:	\$100,000
6) Repair of the cracked cmu and rusted reinforcing:	\$250,000

Please understand that this report represents a professional opinion based upon the results of our limited observations, and past experience with similar conditions. Our study was strictly limited to visual observations as stated above. This report is not intended to be a complete or comprehensive study of the structure. We have not reviewed, nor have we been asked to review, the capacity of the existing structure per the current code. Our work has been performed in accordance with generally accepted principles and practices of structural engineering.

We cannot be responsible for any future changes in the condition of the structure. No warranty is provided, either expressed or implied.

If there are any additional concerns or questions please feel free to contact our office. Thank you for the opportunity to assist you on this project.

Sincerely,

*David Bixler*


David Bixler, PE, SE President  
**David Bixler & Associates, PLLC**

# CMU REMOVAL AND INVESTIGATION PICTURES



DATE

1 SITE PLAN  
SCALE: 1"=30' 0"



**WILLIAM C. JACK ELEMENTARY SCHOOL/  
DON MENSEADICK SCHOOL**  
GLENDALE ELEMENTARY SCHOOL DISTRICT NO. 40  
5535 NORTH 67TH AVENUE, GLENDALE, AZ 85301

SITE PLAN

**SPS+ ARCHITECTS**  
P.O. BOX 10000  
PHOENIX, AZ 85068  
TEL: 602.998.1234  
FAX: 602.998.1235  
WWW.SPSARCHITECTS.COM

DESIGNED BY  
DRAWN BY  
CHECKED BY  
DATE  
PROJECT NO.  
SHEET

A100

DATE: 4/20/2011  
CDS: JH  
LADS

NOT FOR CONSTRUCTION

## **MENSENDICK - MARKER #1**



**PICTURE NO. 1**



**PICTURE NO. 2**

**MENSENDICK - MARKER #1**



**PICTURE NO. 3**



**PICTURE NO. 4**



**MENSENDICK - MARKER #2**



**PICTURE NO. 1**



**PICTURE NO. 2**

**MENSENDICK - MARKER #2**



**PICTURE NO. 3**



**PICTURE NO. 4**



**MENSENDICK - MARKER #3**



**PICTURE NO. 1**



**PICTURE NO. 2**

**MENSENDICK - MARKER #3**



**PICTURE NO. 3**



**PICTURE NO. 4**

**MENSENDICK - MARKER #3**



**PICTURE NO. 5**



**PICTURE NO. 6**



**MENSENDICK - MARKER #4**




**PICTURE NO. 1**



**PICTURE NO. 2**



**MENSENDICK - MARKER #4**



**PICTURE NO. 3**




**PICTURE NO. 4**



SITE

INVESTIGATION

PICTURES



① SITE PLAN  
SCALE: 1"=50'-0"



A100


DATE: 4/29/2015  
 DESIGNED BY: [blank]  
 DRAWN BY: [blank]  
 CHECKED BY: [blank]  
 APPROVED BY: [blank]  
 PRELIMINARY  
 NOT FOR  
 CONSTRUCTION

WILLIAM C. JACK ELEMENTARY SCHOOL  
 DON MENSENDICK SCHOOL  
 GLENDALE ELEMENTARY SCHOOL DISTRICT NO. 40  
 5535 NORTH 67TH AVENUE, GLENDALE, AZ 85301


WILLIAM C. JACK ELEMENTARY SCHOOL  
 DON MENSENDICK SCHOOL  
 GLENDALE ELEMENTARY SCHOOL DISTRICT NO. 40  
 5535 NORTH 67TH AVENUE, GLENDALE, AZ 85301  
 SITE PLAN

**SPS+**  
 ARCHITECTS  
 10000 N. 19TH AVENUE, SUITE 100  
 GLENDALE, AZ 85308  
 TEL: 480.711.5800  
 FAX: 480.711.5223  
 WWW.SPSARCHITECTS.COM


## 5 HEAD START BUILDING FLOOR PLAN




### 3 JACK BUILDING M FLOOR PLAN




2 JACK BUILDING L FLOOR PLAN  
SCALE 1/8" = 1'-0"



#### 4 JACK BUILDING N FLOOR PLAN



1 JACK BUILDING K FLOOR PLAN  
SCALE 1/8" = 1'-0"




**WILLIAM C. JACK ELEMENTARY SCHOOL/  
DON MENSENDICK SCHOOL**  
GLENDALE ELEMENTARY SCHOOL DISTRICT NO. 40  
5535 NORTH 67TH AVENUE, GLENDALE, AZ 85301

### JACK BUILDING K-N FLOOR PLANS

SPS ARCHITECTS LLP  
SCOTTDALE AZ 85275  
TEL 480 991 0800  
FAX 480 971 2123  
[spj@spjarch.com](mailto:spj@spjarch.com)

SPS+  
ARCHITECTS




REVISIONS BY  
DRAWN BY  
PRELIMINARY  
NOT FOR  
CONSTRUCTION  
C-118  
4/27/75 LLS  
JOB NO.  
314-ET  
A208



WILLIAM C. JACK ELEMENTARY SCHOOL/  
 DON MENSENDICK SCHOOL  
 GLENDALE ELEMENTARY SCHOOL DISTRICT NO. 40  
 5535 NORTH 67TH AVENUE, GLENDALE, AZ 85301  
 MENSENDICK BUILDING I-K + N FLOOR PLANS

**SPS+ ARCHITECTS**  
 1701 N. CENTRAL AVENUE  
 SUITE 100  
 GLENDALE, AZ 85301  
 TEL: 602.911.5252  
 FAX: 602.911.5253  
 www.spsarchitects.com


DESIGNED BY  
 DRAWN BY  
 PRELIMINARY  
 NOT FOR  
 CONSTRUCTION  
 DATE: 11/15/11  
 2011  
 11/15/11  
 A202







3 JACK BUILDING J FLOOR PLAN  
SCALE: 1/8" = 1'-0"



2 JACK BUILDING I FLOOR PLAN  
SCALE: 1/8" = 1'-0"




1 JACK BUILDING H FLOOR PLAN  
SCALE: 1/8" = 1'-0"


**WILLIAM C. JACK ELEMENTARY SCHOOL /  
DON MENSENDICK SCHOOL**  
GLENDALE ELEMENTARY SCHOOL DISTRICT NO. 40  
5535 NORTH 67TH AVENUE, GLENDALE, AZ 85301  
JACK BUILDING G, H + J FLOOR PLANS

**SPS+ ARCHITECTS**  
1000 N. CENTRAL AVENUE  
SUITE 100  
GLENDALE, AZ 85301  
TEL: 602.991.4000  
FAX: 602.991.4001  
WWW.SPSARCHITECTS.COM


DATE: 8.27.2018  
DRAWN BY: JCS  
CHECKED BY: JCS  
PROJECT: A207  
PRELIMINARY  
NOT FOR  
CONSTRUCTION



3 JACK BUILDING C FLOOR PLAN



2 JACK BUILDING B FLOOR PLAN



1 JACK BUILDING A FLOOR PLAN

**SPS+**  
ARCHITECTS


1000 N. GILBERT AVENUE  
SUITE 100  
GLENDALE, AZ 85301  
TEL: 480.791.0007  
WWW.SPSARCHITECTS.COM

**WILLIAM C. JACK ELEMENTARY SCHOOL /  
DON MENSENDICK SCHOOL**  
GLENDALE ELEMENTARY SCHOOL DISTRICT NO. 40  
5535 NORTH 67TH AVENUE, GLENDALE, AZ 85301  
JACK BUILDING A-C FLOOR PLANS


DATE: 11/11/11  
BY: [Signature]  
CHECKED BY: [Signature]  
APPROVED BY: [Signature]

REVISIONS:  
DRAWN BY:  
DATE:  
PRELIMINARY  
NOT FOR  
CONSTRUCTION


DATE: 4/2/2015  
JOB NO.:  
SHEET:  
**A205**



3 MENESENDICK BUILDING H FLOOR PLAN



2 MENESENDICK BUILDING G FLOOR PLAN



1 MENESENDICK BUILDING E FLOOR PLAN

DATE: 11/20/18  
BY: [Signature]  
CHECKED: [Signature]  
APPROVED: [Signature]

**WILLIAM C. JACK ELEMENTARY SCHOOL /  
DON MENESENDICK SCHOOL**  
GLENDALE ELEMENTARY SCHOOL DISTRICT NO. 40  
5535 NORTH 67TH AVENUE, GLENDALE, AZ 85301  
MENESENDICK BUILDING E, G + H FLOOR PLANS



DATE: 11/20/18  
BY: [Signature]  
CHECKED: [Signature]  
APPROVED: [Signature]



**PRELIMINARY  
NOT FOR  
CONSTRUCTION**

DATE: 11/20/18  
BY: [Signature]  
CHECKED: [Signature]  
APPROVED: [Signature]

A201






MEDSENDICK BUILDING M FLOOR PLAN

**SPS + ARCHITECTS**  
395 S. ARIZONA AVE. #1111P  
SCOTTSDALE, AZ 85266  
TEL. 480.971.4000  
FAX 480.971.5263  
www.spsarch.com


RECEIVED BY  
DRAWING  
PRELIMINARY  
NOT FOR  
CONSTRUCTION

DATE 6/7/21  
 ACCOUNT # A203  
 STREET 518 E 1





2 MENESENDICK BUILDING O SECOND FLOOR PLAN



1 MENESENDICK BUILDING O FIRST FLOOR PLAN



WILLIAM C. JACK ELEMENTARY SCHOOL/  
DON MENSENDICK SCHOOL  
GLENDALE ELEMENTARY SCHOOL DISTRICT NO. 40  
5535 NORTH 67TH AVENUE, GLENDALE, AZ 85301

MENSENDICK BUILDING O FLOOR PLANS




PRELIMINARY  
NOT FOR  
CONSTRUCTION

A204

**DON MENSENDICK SCHOOL – BUILDING 1**

**7**



**MARKER NO. 1**



**MARKER NO. 2**

**DON MENSENDICK SCHOOL – BUILDING 1**




**MARKER NO. 3**




**MARKER NO. 4**



**DON MENSENDICK SCHOOL – BUILDING 1**




**MARKER NO. 5**



**MARKER NO. 6**


**DON MENSENDICK SCHOOL – BUILDING 1**



**MARKER NO. 7**




**DON MENSENDICK SCHOOL – BUILDING 1**



**MARKER NO. 8**

**DON MENSENDICK SCHOOL – BUILDING 1**



**MARKER NO. 9**

**DON MENSENDICK SCHOOL – BUILDING 1**



**MARKER NO. 10**

**DON MENSENDICK SCHOOL – BUILDING 2**




**MARKER NO. 1**



**DON MENSENDICK SCHOOL – BUILDING 2**




**MARKER NO. 2**



**MARKER NO. 3**




**DON MENSENDICK SCHOOL – BUILDING 2**



**MARKER NO. 4**

**DON MENSENDICK SCHOOL – BUILDING 3**



**MARKER NO. 1**



**MARKER NO. 2**

**DON MENSENDICK SCHOOL – BUILDING 4**




**MARKER NO. 1**



**MARKER NO. 2**


**DON MENSENDICK SCHOOL – BUILDING 4**



**MARKER NO. 3**



**DON MENSENDICK SCHOOL – BUILDING 5**




**MARKER NO. 1**



**DON MENSENDICK SCHOOL – BUILDING 5**




**MARKER NO. 2**




**MARKER NO. 3**

**DON MENSENDICK SCHOOL – BUILDING 5**




**MARKER NO. 4**




**MARKER NO. 5**

**DON MENSENDICK SCHOOL – BUILDING 5**



**MARKER NO. 6**



**MARKER NO. 7**



**DON MENSENDICK SCHOOL – BUILDING 5**



**MARKER NO. 8**

**DON MENSENDICK SCHOOL – BUILDING 6**



**MARKER NO. 1**




**DON MENSENDICK SCHOOL – BUILDING 7**




**MARKER NO. 1**

**DON MENSENDICK SCHOOL – BUILDING 7**



**MARKER NO. 2**

**DON MENSENDICK SCHOOL – BUILDING 7**




**MARKER NO. 4**



**MARKER NO. 5**


**DON MENSENDICK SCHOOL – BUILDING 7**



**MARKER NO. 6**



**DON MENSENDICK SCHOOL – BUILDING 7**




**MARKER NO. 7**



**MARKER NO. 8**




**DON MENSENDICK SCHOOL – BUILDING 7**




**MARKER NO. 9**

**DON MENSENDICK SCHOOL – BUILDING 7**




**MARKER NO. 10**

**DON MENSENDICK SCHOOL – BUILDING 7**




**MARKER NO. 11**




**MARKER NO. 12**

**DON MENSENDICK SCHOOL – BUILDING 7**



**MARKER NO. 13**


**DON MENSENDICK SCHOOL – BUILDING 7**



**MARKER NO. 14**



**DON MENSENDICK SCHOOL – BUILDING 7**



**MARKER NO. 15**

**DON MENSENDICK SCHOOL – BUILDING 7**



**MARKER NO. 16**

**DON MENSENDICK SCHOOL – BUILDING 8**




**MARKER NO. 1**

**DON MENSENDICK SCHOOL – BUILDING 8**



**MARKER NO. 2**

**DON MENSENDICK SCHOOL – BUILDING 9**



**MARKER NO. 1**




**DON MENSENDICK SCHOOL – BUILDING 9**




**MARKER NO. 2**

**DON MENSENDICK SCHOOL – BUILDING 9**



**MARKER NO. 3**

**DON MENSENDICK SCHOOL – BUILDING 9**



**MARKER NO. 4**


**DON MENSENDICK SCHOOL – BUILDING 9**




**MARKER NO. 5**



**DON MENSENDICK SCHOOL – BUILDING 9**




**MARKER NO. 6**



**MARKER NO. 7**



**DON MENSENDICK SCHOOL – BUILDING 9**




**MARKER NO. 8**




**MARKER NO. 9**

**DON MENSENDICK SCHOOL – BUILDING 9**




**MARKER NO. 10**



**MARKER NO. 11**

**DON MENSENDICK SCHOOL – BUILDING 9**



**MARKER NO. 12**



**DON MENSENDICK SCHOOL – BUILDING 9**




**MARKER NO. 13**



**MARKER NO. 14**

**DON MENSENDICK SCHOOL – BUILDING 10**




**MARKER NO. 1**



**MARKER NO. 2**




**DON MENSENDICK SCHOOL – BUILDING 10**



**MARKER NO. 3**

**DON MENSENDICK SCHOOL – BUILDING 10**



**MARKER NO. 4**

**DON MENSENDICK SCHOOL – BUILDING 10**



**MARKER NO. 5**



**MARKER NO. 6**

**DON MENSENDICK SCHOOL – BUILDING 10**



**MARKER NO. 7**



**MARKER NO. 8**




**DON MENSENDICK SCHOOL – BUILDING 10**



**MARKER NO. 9**



**DON MENSENDICK SCHOOL – BUILDING 11**




**MARKER NO. 1**

**DON MENSENDICK SCHOOL – BUILDING 12**



**MARKER NO. 1**




**MARKER NO. 2**

**DON MENSENDICK SCHOOL – BUILDING 12**



**MARKER NO. 3**



**MARKER NO. 4**





**DON MENSENDICK SCHOOL – BUILDING 12**




**MARKER NO. 7**



**MARKER NO. 8**



**DON MENSENDICK SCHOOL – BUILDING 12**



**MARKER NO. 9**




**MARKER NO. 10**

**DON MENSENDICK SCHOOL – BUILDING 12**




**MARKER NO. 11**

**DON MENSENDICK SCHOOL – BUILDING 13**



**MARKER NO. 1**

**DON MENSENDICK SCHOOL – BUILDING 14**



**MARKER NO. 1**




**DON MENSENDICK SCHOOL – BUILDING 15**



**MARKER NO. 1**



**DON MENSENDICK SCHOOL – BUILDING 15**




**MARKER NO. 2**




**MARKER NO. 3**



**DON MENSENDICK SCHOOL – BUILDING 15**



**MARKER NO. 4**



**MARKER NO. 5**

**DON MENSENDICK SCHOOL – BUILDING 15**



**MARKER NO. 6**



**DON MENSENDICK SCHOOL – BUILDING 16**




**MARKER NO. 1**



**MARKER NO. 2**

**DON MENSENDICK SCHOOL – BUILDING 16**



**MARKER NO. 3**



**DON MENSENDICK SCHOOL – BUILDING 16**



**MARKER NO. 4**

**DON MENSENDICK SCHOOL – BUILDING 17**



**MARKER NO. 1**

**DON MENSENDICK SCHOOL – BUILDING 17**




**MARKER NO. 2**




**MARKER NO. 3**



**DON MENSENDICK SCHOOL – BUILDING 17**



**MARKER NO. 4**



**MARKER NO. 5**


**DON MENSENDICK SCHOOL – BUILDING 17**



**MARKER NO. 6**




**DON MENSENDICK SCHOOL – BUILDING 17**




**MARKER NO. 7**

**DON MENSENDICK SCHOOL – BUILDING 17**




**MARKER NO. 8**

**DON MENSENDICK SCHOOL – BUILDING 18**




**MARKER NO. 1**



**MARKER NO. 2**


**DON MENSENDICK SCHOOL – BUILDING 18**




**MARKER NO. 3**



**DON MENSENDICK SCHOOL – BUILDING 18**



**MARKER NO. 4**



**MARKER NO. 5**



**DON MENSENDICK SCHOOL – BUILDING 18**




**MARKER NO. 6**

**DON MENSENDICK SCHOOL – BUILDING 20**




**MARKER NO. 1**




**MARKER NO. 2**



**DON MENSENDICK SCHOOL – BUILDING 20**



**MARKER NO. 3**



**MARKER NO. 4**

**DON MENSENDICK SCHOOL – BUILDING 20**




**MARKER NO. 5**



**MARKER NO. 6**

**DON MENSENDICK SCHOOL – BUILDING 21**



**MARKER NO. 1**




**DON MENSENDICK SCHOOL – BUILDING 22**




**MARKER NO. 1**

**DON MENSENDICK SCHOOL – BUILDING 22**



**MARKER NO. 2**

**DON MENSENDICK SCHOOL – BUILDING 22**



**MARKER NO. 3**


**DON MENSENDICK SCHOOL – BUILDING 24**



**MARKER NO. 1**

# **SURFACE PENETRATING RADAR REPORT**





- ② - APPROXIMATE GPR SCAN LOCATIONS (FLOOR SLAB)
- △ - APPROXIMATE GPR SCAN LOCATIONS (CMU WALL)



## G.P.R. SCAN LOCATION PLAN

DR. TSW

REV.

DATE 07/06/16

CHK:

PROJECT NO. 16128BTA

**MENSENDICK SCHOOL BUILDING DISTRESS**

5535 N. 67TH AVENUE  
GLENDALE, ARIZONA

**SPEEDIE AND ASSOCIATES**

GEOTECHNICAL/ENVIRONMENTAL/MATERIALS ENGINEERS

3001 E. WOOD ST.  
PHOENIX, ARIZONA 85034

(602) 971-6291

# GROUND PENETRATING RADAR FIELD REPORT

<b>Project Name:</b> Mensendick School-Building Distress - GPR		<b>Project #:</b> 161288TA	<b>Date:</b> 07/07/16
<b>Project Location:</b> 5535 N. 67th Ave. - Glendale, AZ.		<b>Time Start:</b> 4:30 AM	<b>Time Stop:</b> 2:30 PM
<b>Client:</b> SPS Arrchitects		<b>Rep:</b> Dave Bixler	<b>Doc #:</b> GPR RW432

**WORK ORDERED BY CLIENT:**

**STRUCTURE TYPE:**    Cast in Place ☒    Pre-Cast ☐    Masonry ☒    Other ☐ \_\_\_\_\_

**STRUCTURE ELEMENT:**    Footing ☐    SOG ☒    Wall ☒    Column ☐    Beam ☐    Deck ☐    Other ☐ \_\_\_\_\_

**TARGET INDICATIONS:**    Reinforcing Steel ☒    PT Cables ☐    PVC Conduit ☐    Voids ☐  
    Grouted Cells ☒    Un-Grouted Cells ☒    Other ☐ \_\_\_\_\_

**PICTURES TAKEN:**    Yes ☒    No ☐    **TARGETS MARKED WITH:**    Crayon ☐    Paint ☐    Duct Tape ☒

**SIZE / LOCATION OF AREA(S):**

S&A performed Ground Penetrating Radar (GPR) scanning at the Mensendick/Jack Elementary School buildings. We utilized the GSSI SIR-3000 Data Acqulsition System with model 5100B - 1600 and 2000 MHz antennas. We scanned the CMU walls and slab on grade at locations that were predetermined by the structural engineer to identify and note reinforcement indications. Per our proposal, we scanned an approximate 10' x 10' sections of wall and SOG at each location. We marked reinforcement indications with tape. The tape markings were stopped at the limits of the approximate 10'x10' scanned sections.

\* Please see our attached site plan for specific locations.  
 \* Observations and measurements were reported separately at each scan location (see scan notes).  
 \* A photo of each scanned location was taken for reference (see photo outline) .

1. Mensendick Elementary School:  
 A. (10) CMU Wall with approximate 10'x10' areas scanned.  
 B. (5) Slab-on-grade with approximate 10'x10' floor areas scanned.

GPR SERVICE PROVIDED:	QUANTITY	UNIT PRICE	EXTENSION
Trip Charge	_____	\$ _____	\$ _____
GPR Technician    (3 hr. minimum)	_____	\$ _____	\$ _____
Support Tech        (3 hr. minimum)	_____	\$ _____	\$ _____
3-D Imaging	_____	\$ _____	\$ _____
Additional Services	_____	\$ _____	\$ _____
<b>TOTAL</b>			

On Account <input checked="" type="checkbox"/> COD - Cash <input type="checkbox"/> Check <input type="checkbox"/> # _____	Credit Card - VISA <input type="checkbox"/> MC <input type="checkbox"/> DISCOVER <input type="checkbox"/>
---	---

The information presented is based upon interpretation of the data collected and is provided solely for illustration and informational purposes. Speedie & Associates is not responsible for any loss or damage caused, arising out of the use of or reliance on the data collected or the report generated. Speedie & Associates hereby disclaims all warranties, expressed or implied with respect to the nature, or quality of the services performed hereunder and except to the extent of its sole gross negligence shall not be liable for any damages as a result of its performance.

Accepted By: \_\_\_\_\_ Technician: Rodd Whisel

# SPEEDIE AND ASSOCIATES

GEOTECHNICAL/ENVIRONMENTAL/MATERIALS ENGINEERS  
3331 E. Wood St., Phoenix, Arizona 85040 Telephone (602) 997-6391 Fax (602) 943-5508

## GROUND PENETRATING RADAR SCAN NOTES

Project Name: Mensendick/Jack Elementary School Distress - GPR Project #: 161288TA Date: 07/07/2016  
Project Location: 535 N. 67th Ave., Glendale AZ Time Start: 4:30AM Time Stop: 2:30PM  
Client: SPS Architects Rep: Jennifer Bowen Doc #: GPR RW432-1

SCAN NUMBER: 1-Wall

SCAN LOCATION: Mensendick School, Room 602, South Wall (PO picture 1)

STRUCTURE TYPE: Cast in Place ☐ Pre-Cast ☐ Masonry ☒ Other ☐

STRUCTURE ELEMENT: Footing ☐ SOG ☐ Wall ☒ Column ☐ Beam ☐ Deck ☐ Other ☐

TARGET INDICATIONS: Reinforcing Steel ☒ PT Cables ☐ PVC Conduit ☐ Voids ☐  
Grouted Cells ☒ Un-Grouted Cells ☐ Other ☐

PICTURES TAKEN: Yes ☒ No ☐ TARGETS MARKED WITH: Crayon ☐ Paint ☐ Tape ☒

### CONCRETE TARGET INDICATION ORIENTATION / APPROXIMATE SPACING AND DEPTH:

Vertical Target Spacing: \_\_\_\_\_  
Vertical Target Depth: \_\_\_\_\_

Horizontal Target Spacing: \_\_\_\_\_  
Horizontal Target Depth: \_\_\_\_\_

Longitudinal Target Spacing: \_\_\_\_\_  
Longitudinal Target Depth: \_\_\_\_\_

Lateral Target Spacing: \_\_\_\_\_  
Lateral Target Depth: \_\_\_\_\_

### CMU TARGET INDICATION ORIENTATION / APPROXIMATE SPACING AND DEPTH:

Vertical Target Spacing: No indications (ungrouted)  
Vertical Target Depth: \_\_\_\_\_

Horizontal Target Spacing: No indications (ungrouted)  
Horizontal Target Depth: \_\_\_\_\_

Masonry Joint Reinf. Spacing: No indications

### ADDITIONAL NOTES/OBSERVATIONS:

4"x8"x16" CMU Block  
Green tape indicating possible target in un-grouted block

The information presented is based upon interpretation of the data collected and is provided solely for illustration and informational purposes. Speedie & Associates is not responsible for any loss or damage caused, arising out of the use of or reliance on the data collected or the report generated. Speedie & Associates hereby disclaims all warranties, expressed or implied with respect to the nature, or quality of the services performed hereunder and except to the extent of its sole gross negligence shall not be liable for any damages as a result of its performance.

Accepted By: \_\_\_\_\_

Technician: Rodd Whisel

## GROUND PENETRATING RADAR SCAN NOTES

**Project Name:** Mensendick/Jack Elementary School Distress - GPR **Project #:** 161288TA **Date:** 07/07/2016  
**Project Location:** 535 N. 67th Ave., Glendale AZ **Time Start:** 4:30AM **Time Stop:** 2:30PM  
**Client:** SPS Architects **Rep:** Jennifer Bowen **Doc #:** GPR RW432-6

**SCAN NUMBER:** 4-Wall

**SCAN LOCATION:** Mensendick School, Room 537, North Wall (PO picture 6)

**STRUCTURE TYPE:** Cast in Place ☐ Pre-Cast ☐ Masonry ☒ Other ☐ \_\_\_\_\_

**STRUCTURE ELEMENT:** Footing ☐ SOG ☐ Wall ☒ Column ☐ Beam ☐ Deck ☐ Other ☐ \_\_\_\_\_

**TARGET INDICATIONS:** Reinforcing Steel ☒ PT Cables ☐ PVC Conduit ☐ Voids ☐  
Grouted Cells ☒ Un-Grouted Cells ☐ Other ☐ \_\_\_\_\_

**PICTURES TAKEN:** Yes ☒ No ☐ **TARGETS MARKED WITH:** Crayon ☐ Paint ☐ Tape ☒

**CONCRETE TARGET INDICATION ORIENTATION / APPROXIMATE SPACING AND DEPTH:**

Vertical Target Spacing: \_\_\_\_\_  
Vertical Target Depth: \_\_\_\_\_

Horizontal Target Spacing: \_\_\_\_\_  
Horizontal Target Depth: \_\_\_\_\_

Longitudinal Target Spacing: \_\_\_\_\_  
Longitudinal Target Depth: \_\_\_\_\_

Lateral Target Spacing: \_\_\_\_\_  
Lateral Target Depth: \_\_\_\_\_

**CMU TARGET INDICATION ORIENTATION / APPROXIMATE SPACING AND DEPTH:**

Vertical Target Spacing: Each side of wood column and near center span (grouted)  
Vertical Target Depth: \_\_\_\_\_

Horizontal Target Spacing: Approximately 8" down from window, possible bond beam (grouted)  
Horizontal Target Depth: \_\_\_\_\_

Masonry Joint Reinf. Spacing: 16" OC up to 4" above FF elevation

**ADDITIONAL NOTES/OBSERVATIONS:**

8"x8"x16" CMU Block

The information presented is based upon interpretation of the data collected and is provided solely for illustration and informational purposes. Speedie & Associates is not responsible for any loss or damage caused, arising out of the use of or reliance on the data collected or the report generated. Speedie & Associates hereby disclaims all warranties, expressed or implied with respect to the nature, or quality of the services performed hereunder and except to the extent of its sole gross negligence shall not be liable for any damages as a result of its performance.

Accepted By: \_\_\_\_\_ Technician: Rodd Whisel

**GROUND PENETRATING RADAR  
SCAN NOTES**

**Project Name:** Mensendick/Jack Elementary School Distress - GPR **Project #:** 161288TA **Date:** 07/07/2016  
**Project Location:** 535 N. 67th Ave., Glendale AZ **Time Start:** 4:30AM **Time Stop:** 2:30PM  
**Client:** SPS Architects **Rep:** Jennifer Bowen **Doc #:** GPR RW432-7

**SCAN NUMBER:** 3-SOG

**SCAN LOCATION:** Jack School, Room 528, SOG near center of room (PO picture 7)

**STRUCTURE TYPE:** Cast in Place ☒ Pre-Cast ☐ Masonry ☐ Other ☐ \_\_\_\_\_

**STRUCTURE ELEMENT:** Footing ☐ SOG ☒ Wall ☐ Column ☐ Beam ☐ Deck ☐ Other ☐ \_\_\_\_\_

**TARGET INDICATIONS:** Reinforcing Steel ☒ PT Cables ☐ PVC Conduit ☐ Voids ☐  
Grouted Cells ☐ Un-Grouted Cells ☐ Other ☐ \_\_\_\_\_

**PICTURES TAKEN:** Yes ☒ No ☐ **TARGETS MARKED WITH:** Crayon ☐ Paint ☐ Tape ☒

**CONCRETE TARGET INDICATION ORIENTATION / APPROXIMATE SPACING AND DEPTH:**

Vertical Target Spacing: \_\_\_\_\_  
Vertical Target Depth: \_\_\_\_\_

Horizontal Target Spacing: \_\_\_\_\_  
Horizontal Target Depth: \_\_\_\_\_

Longitudinal Target Spacing: No indications  
Longitudinal Target Depth: \_\_\_\_\_

Lateral Target Spacing: No indications  
Lateral Target Depth: \_\_\_\_\_

**CMU TARGET INDICATION ORIENTATION / APPROXIMATE SPACING AND DEPTH:**

Vertical Target Spacing: \_\_\_\_\_  
Vertical Target Depth: \_\_\_\_\_

Horizontal Target Spacing: \_\_\_\_\_  
Horizontal Target Depth: \_\_\_\_\_

Masonry Joint Reinf. Spacing: \_\_\_\_\_

**ADDITIONAL NOTES/OBSERVATIONS:**

Approximate scan area 10'x10'  
Approximate slab thickness 4.0"

The information presented is based upon interpretation of the data collected and is provided solely for illustration and informational purposes. Speedie & Associates is not responsible for any loss or damage caused, arising out of the use of or reliance on the data collected or the report generated. Speedie & Associates hereby disclaims all warranties, expressed or implied with respect to the nature, or quality of the services performed hereunder and except to the extent of its sole gross negligence shall not be liable for any damages as a result of its performance.

Accepted By: \_\_\_\_\_ Technician: Rodd Whisel



## GROUND PENETRATING RADAR SCAN NOTES

<b>Project Name:</b> Mensendick/Jack Elementary School Distress - GPR	<b>Project #:</b> 161288TA	<b>Date:</b> 07/07/2016
<b>Project Location:</b> 535 N. 67th Ave., Glendale AZ	<b>Time Start:</b> 4:30AM	<b>Time Stop:</b> 2:30PM
<b>Client:</b> SPS Architects	<b>Rep:</b> Jennifer Bowen	<b>Doc #:</b> GPR RW432-8

**SCAN NUMBER:** 5-Wall

**SCAN LOCATION:** Jack School, Room 521, North Wall (PO picture 8)

**STRUCTURE TYPE:** Cast in Place ☐ Pre-Cast ☐ Masonry ☒ Other ☐

**STRUCTURE ELEMENT:** Footing ☐ SOG ☐ Wall ☒ Column ☐ Beam ☐ Deck ☐ Other ☐

**TARGET INDICATIONS:** Reinforcing Steel ☒ PT Cables ☐ PVC Conduit ☐ Voids ☐  
Grouted Cells ☒ Un-Grouted Cells ☐ Other ☐

**PICTURES TAKEN:** Yes ☒ No ☐ **TARGETS MARKED WITH:** Crayon ☐ Paint ☐ Tape ☒

**CONCRETE TARGET INDICATION ORIENTATION / APPROXIMATE SPACING AND DEPTH:**

Vertical Target Spacing: \_\_\_\_\_  
Vertical Target Depth: \_\_\_\_\_

Horizontal Target Spacing: \_\_\_\_\_  
Horizontal Target Depth: \_\_\_\_\_

Longitudinal Target Spacing: \_\_\_\_\_  
Longitudinal Target Depth: \_\_\_\_\_

Lateral Target Spacing: \_\_\_\_\_  
Lateral Target Depth: \_\_\_\_\_

**CMU TARGET INDICATION ORIENTATION / APPROXIMATE SPACING AND DEPTH:**

Vertical Target Spacing: Varies see picture in photo outline. See notes below  
Vertical Target Depth: \_\_\_\_\_

Horizontal Target Spacing: Approximately 8" down from window, 12" down from top of wall (grouted)  
Horizontal Target Depth: \_\_\_\_\_

Masonry Joint Reinf. Spacing: 16" OC up to 4' from FF elevation (varies above 4 feet from FF elevation-see pic)

**ADDITIONAL NOTES/OBSERVATIONS:**

8"x8"x16" CMU Block  
Dashed orange tape indicates voids at vertical reinforced location

The information presented is based upon interpretation of the data collected and is provided solely for illustration and informational purposes. Speedie & Associates is not responsible for any loss or damage caused, arising out of the use of or reliance on the data collected or the report generated. Speedie & Associates hereby disclaims all warranties, expressed or implied with respect to the nature, or quality of the services performed hereunder and except to the extent of its sole gross negligence shall not be liable for any damages as a result of its performance.

Accepted By: \_\_\_\_\_

Technician: Rodd Whisel

## GROUND PENETRATING RADAR SCAN NOTES

**Project Name:** Mensendick/Jack Elementary School Distress - GPR **Project #:** 161288TA **Date:** 07/07/2016  
**Project Location:** 535 N. 67th Ave., Glendale AZ **Time Start:** 4:30AM **Time Stop:** 2:30PM  
**Client:** SPS Architects **Rep:** Jennifer Bowen **Doc #:** GPR RW432-9

**SCAN NUMBER:** 6-Wall

**SCAN LOCATION:** Jack School, Room 518, North Wall (PO picture 9)

**STRUCTURE TYPE:** Cast in Place ☐ Pre-Cast ☐ Masonry ☒ Other ☐

**STRUCTURE ELEMENT:** Footing ☐ SOG ☐ Wall ☒ Column ☐ Beam ☐ Deck ☐ Other ☐

**TARGET INDICATIONS:** Reinforcing Steel ☒ PT Cables ☐ PVC Conduit ☐ Voids ☐  
Grouted Cells ☒ Un-Grouted Cells ☐ Other ☐

**PICTURES TAKEN:** Yes ☒ No ☐ **TARGETS MARKED WITH:** Crayon ☐ Paint ☐ Tape ☒

**CONCRETE TARGET INDICATION ORIENTATION / APPROXIMATE SPACING AND DEPTH:**

Vertical Target Spacing: \_\_\_\_\_  
Vertical Target Depth: \_\_\_\_\_

Horizontal Target Spacing: \_\_\_\_\_  
Horizontal Target Depth: \_\_\_\_\_

Longitudinal Target Spacing: \_\_\_\_\_  
Longitudinal Target Depth: \_\_\_\_\_

Lateral Target Spacing: \_\_\_\_\_  
Lateral Target Depth: \_\_\_\_\_

**CMU TARGET INDICATION ORIENTATION / APPROXIMATE SPACING AND DEPTH:**

Vertical Target Spacing: First cell adjacent to column and near mid span of wall  
Vertical Target Depth: \_\_\_\_\_

Horizontal Target Spacing: Approximately 12" down from window, possible bond beam (grouted)  
Horizontal Target Depth: \_\_\_\_\_

Masonry Joint Reinf. Spacing: 16" OC up to 5'-8" from FF elevation

**ADDITIONAL NOTES/OBSERVATIONS:**

4"x8"x16" CMU Block  
Blue tape indicates metal terminated near mid span (possible rebar)

The information presented is based upon interpretation of the data collected and is provided solely for illustration and informational purposes. Speedie & Associates is not responsible for any loss or damage caused, arising out of the use of or reliance on the data collected or the report generated. Speedie & Associates hereby disclaims all warranties, expressed or implied with respect to the nature, or quality of the services performed hereunder and except to the extent of its sole gross negligence shall not be liable for any damages as a result of its performance.

Accepted By: \_\_\_\_\_

Technician: Rodd Whisel

## GROUND PENETRATING RADAR SCAN NOTES

**Project Name:** Mensendick/Jack Elementary School Distress - GPR **Project #:** 161288TA **Date:** 07/07/2016  
**Project Location:** 535 N. 67th Ave., Glendale AZ **Time Start:** 4:30AM **Time Stop:** 2:30PM  
**Client:** SPS Architects **Rep:** Jennifer Bowen **Doc #:** GPR RW432-10

**SCAN NUMBER:** 7-Wall

**SCAN LOCATION:** Jack School, Room 521, South Wall (PO picture 10)

**STRUCTURE TYPE:** Cast in Place ☐ Pre-Cast ☐ Masonry ☒ Other ☐

**STRUCTURE ELEMENT:** Footing ☐ SOG ☐ Wall ☒ Column ☐ Beam ☐ Deck ☐ Other ☐

**TARGET INDICATIONS:** Reinforcing Steel ☒ PT Cables ☐ PVC Conduit ☐ Voids ☐  
Grouted Cells ☒ Un-Grouted Cells ☐ Other ☐

**PICTURES TAKEN:** Yes ☒ No ☐ **TARGETS MARKED WITH:** Crayon ☐ Paint ☐ Tape ☒

**CONCRETE TARGET INDICATION ORIENTATION / APPROXIMATE SPACING AND DEPTH:**

Vertical Target Spacing: \_\_\_\_\_  
Vertical Target Depth: \_\_\_\_\_

Horizontal Target Spacing: \_\_\_\_\_  
Horizontal Target Depth: \_\_\_\_\_

Longitudinal Target Spacing: \_\_\_\_\_  
Longitudinal Target Depth: \_\_\_\_\_

Lateral Target Spacing: \_\_\_\_\_  
Lateral Target Depth: \_\_\_\_\_

**CMU TARGET INDICATION ORIENTATION / APPROXIMATE SPACING AND DEPTH:**

Vertical Target Spacing: Varies see photo outline, see below for additional notes  
Vertical Target Depth: \_\_\_\_\_

Horizontal Target Spacing: Varies see photo outline, possible partial bond beam at 4'-8"  
Horizontal Target Depth: \_\_\_\_\_

Masonry Joint Reinf. Spacing: Partial at 24" above FF

**ADDITIONAL NOTES/OBSERVATIONS:**

4"x8"x16" CMU Block  
Wall infill at previous man door  
Solid orange tape indicate grouted solid  
Dashed orange tape indicates voids at reinforced cells

The information presented is based upon interpretation of the data collected and is provided solely for illustration and informational purposes. Speedie & Associates is not responsible for any loss or damage caused, arising out of the use of or reliance on the data collected or the report generated. Speedie & Associates hereby disclaims all warranties, expressed or implied with respect to the nature, or quality of the services performed hereunder and except to the extent of its sole gross negligence shall not be liable for any damages as a result of its performance.

Accepted By: \_\_\_\_\_ Technician: Rodd Whisel

## GROUND PENETRATING RADAR SCAN NOTES

**Project Name:** Mensendick/Jack Elementary School Distress - GPR **Project #:** 161288TA **Date:** 07/07/2016  
**Project Location:** 535 N. 67th Ave., Glendale AZ **Time Start:** 4:30AM **Time Stop:** 2:30PM  
**Client:** SPS Architects **Rep:** Jennifer Bowen **Doc #:** GPR RW432-11

**SCAN NUMBER:** 8-Wall

**SCAN LOCATION:** Jack School, Room 517, South Wall (PO picture 11)

**STRUCTURE TYPE:** Cast in Place ☐ Pre-Cast ☐ Masonry ☒ Other ☐ \_\_\_\_\_

**STRUCTURE ELEMENT:** Footing ☐ SOG ☐ Wall ☒ Column ☐ Beam ☐ Deck ☐ Other ☐ \_\_\_\_\_

**TARGET INDICATIONS:** Reinforcing Steel ☒ PT Cables ☐ PVC Conduit ☐ Voids ☐  
Grouted Cells ☒ Un-Grouted Cells ☐ Other ☐ \_\_\_\_\_

**PICTURES TAKEN:** Yes ☒ No ☐ **TARGETS MARKED WITH:** Crayon ☐ Paint ☐ Tape ☒

**CONCRETE TARGET INDICATION ORIENTATION / APPROXIMATE SPACING AND DEPTH:**

Vertical Target Spacing: \_\_\_\_\_  
Vertical Target Depth: \_\_\_\_\_

Horizontal Target Spacing: \_\_\_\_\_  
Horizontal Target Depth: \_\_\_\_\_

Longitudinal Target Spacing: \_\_\_\_\_  
Longitudinal Target Depth: \_\_\_\_\_

Lateral Target Spacing: \_\_\_\_\_  
Lateral Target Depth: \_\_\_\_\_

**CMU TARGET INDICATION ORIENTATION / APPROXIMATE SPACING AND DEPTH:**

Vertical Target Spacing: Adjacent cell E. of column and partial near mid span. see photo outline  
Vertical Target Depth: \_\_\_\_\_

Horizontal Target Spacing: Possible bond beam at 8" below top of wall  
Horizontal Target Depth: \_\_\_\_\_

Masonry Joint Reinf. Spacing: 16" OC starting at 8" above FF

**ADDITIONAL NOTES/OBSERVATIONS:**

4"x8"x16" CMU Block

The information presented is based upon interpretation of the data collected and is provided solely for illustration and informational purposes. Speedie & Associates is not responsible for any loss or damage caused, arising out of the use of or reliance on the data collected or the report generated. Speedie & Associates hereby disclaims all warranties, expressed or implied with respect to the nature, or quality of the services performed hereunder and except to the extent of its sole gross negligence shall not be liable for any damages as a result of its performance.

Accepted By: \_\_\_\_\_

Technician: Rodd Whisel

## GROUND PENETRATING RADAR SCAN NOTES

**Project Name:** Mensendick/Jack Elementary School Distress - GPR **Project #:** 161288TA **Date:** 07/07/2016  
**Project Location:** 535 N. 67th Ave., Glendale AZ **Time Start:** 4:30AM **Time Stop:** 2:30PM  
**Client:** SPS Architects **Rep:** Jennifer Bowen **Doc #:** GPR RW432-12

**SCAN NUMBER:** 4-SOG

**SCAN LOCATION:** Jack School, Room 515, SOG West end of room near center (PO picture 12)

**STRUCTURE TYPE:** Cast in Place ☒ Pre-Cast ☐ Masonry ☐ Other ☐

**STRUCTURE ELEMENT:** Footing ☐ SOG ☒ Wall ☐ Column ☐ Beam ☐ Deck ☐ Other ☐

**TARGET INDICATIONS:** Reinforcing Steel ☒ PT Cables ☐ PVC Conduit ☐ Voids ☐  
Grouted Cells ☐ Un-Grouted Cells ☐ Other ☐

**PICTURES TAKEN:** Yes ☒ No ☐ **TARGETS MARKED WITH:** Crayon ☐ Paint ☐ Tape ☒

**CONCRETE TARGET INDICATION ORIENTATION / APPROXIMATE SPACING AND DEPTH:**

Vertical Target Spacing: \_\_\_\_\_  
Vertical Target Depth: \_\_\_\_\_

Horizontal Target Spacing: \_\_\_\_\_  
Horizontal Target Depth: \_\_\_\_\_

Longitudinal Target Spacing: No indications  
Longitudinal Target Depth: \_\_\_\_\_

Lateral Target Spacing: No indications  
Lateral Target Depth: \_\_\_\_\_

**CMU TARGET INDICATION ORIENTATION / APPROXIMATE SPACING AND DEPTH:**

Vertical Target Spacing: \_\_\_\_\_  
Vertical Target Depth: \_\_\_\_\_

Horizontal Target Spacing: \_\_\_\_\_  
Horizontal Target Depth: \_\_\_\_\_

Masonry Joint Reinf. Spacing: \_\_\_\_\_

**ADDITIONAL NOTES/OBSERVATIONS:**

Approximate scan area 10'x10'

Approximate slab thickness 4.0"

White tape indicates metal (possible electrical conduits) at approximately 2" below surface

The information presented is based upon interpretation of the data collected and is provided solely for illustration and informational purposes. Speedie & Associates is not responsible for any loss or damage caused, arising out of the use of or reliance on the data collected or the report generated. Speedie & Associates hereby disclaims all warranties, expressed or implied with respect to the nature, or quality of the services performed hereunder and except to the extent of its sole gross negligence shall not be liable for any damages as a result of its performance.

Accepted By: \_\_\_\_\_

Technician: Rodd Whisel



## GROUND PENETRATING RADAR SCAN NOTES

**Project Name:** Mensendick/Jack Elementary School Distress - GPR **Project #:** 161288TA **Date:** 07/07/2016  
**Project Location:** 535 N. 67th Ave., Glendale AZ **Time Start:** 4:30AM **Time Stop:** 2:30PM  
**Client:** SPS Architects **Rep:** Jennifer Bowen **Doc #:** GPR RW432-13

**SCAN NUMBER:** 9-Wall

**SCAN LOCATION:** Jack School, Room 506, North Wall (PO picture 13)

**STRUCTURE TYPE:** Cast in Place ☐ Pre-Cast ☐ Masonry ☒ Other ☐

**STRUCTURE ELEMENT:** Footing ☐ SOG ☐ Wall ☒ Column ☐ Beam ☐ Deck ☐ Other ☐

**TARGET INDICATIONS:** Reinforcing Steel ☒ PT Cables ☐ PVC Conduit ☐ Voids ☐  
Grouted Cells ☒ Un-Grouted Cells ☐ Other ☐

**PICTURES TAKEN:** Yes ☒ No ☐ **TARGETS MARKED WITH:** Crayon ☐ Paint ☐ Tape ☒

**CONCRETE TARGET INDICATION ORIENTATION / APPROXIMATE SPACING AND DEPTH:**

Vertical Target Spacing: \_\_\_\_\_  
Vertical Target Depth: \_\_\_\_\_

Horizontal Target Spacing: \_\_\_\_\_  
Horizontal Target Depth: \_\_\_\_\_

Longitudinal Target Spacing: \_\_\_\_\_  
Longitudinal Target Depth: \_\_\_\_\_

Lateral Target Spacing: \_\_\_\_\_  
Lateral Target Depth: \_\_\_\_\_

**CMU TARGET INDICATION ORIENTATION / APPROXIMATE SPACING AND DEPTH:**

Vertical Target Spacing: 1st adjacent cell from wood column and near mid span (grouted)  
Vertical Target Depth: \_\_\_\_\_

Horizontal Target Spacing: Possible bond beams at 6'-8" and 8'-6" above FF (grouted)  
Horizontal Target Depth: \_\_\_\_\_

Masonry Joint Reinf. Spacing: At 16", 32" and 64" above FF

**ADDITIONAL NOTES/OBSERVATIONS:**

8"x8"x16" CMU Block  
Grouted solid between horizontal reinforcing

The information presented is based upon interpretation of the data collected and is provided solely for illustration and informational purposes. Speedie & Associates is not responsible for any loss or damage caused, arising out of the use of or reliance on the data collected or the report generated. Speedie & Associates hereby disclaims all warranties, expressed or implied with respect to the nature, or quality of the services performed hereunder and except to the extent of its sole gross negligence shall not be liable for any damages as a result of its performance.

Accepted By: \_\_\_\_\_ Technician: Rodd Whisel

## GROUND PENETRATING RADAR SCAN NOTES

**Project Name:** Mensendick/Jack Elementary School Distress - GPR **Project #:** 161288TA **Date:** 07/07/2016  
**Project Location:** 535 N. 67th Ave., Glendale AZ **Time Start:** 4:30AM **Time Stop:** 2:30PM  
**Client:** SPS Architects **Rep:** Jennifer Bowen **Doc #:** GPR RW432-14

**SCAN NUMBER:** 10-Wall

**SCAN LOCATION:** Jack School, Room 503, North Wall (PO picture 14)

**STRUCTURE TYPE:** Cast in Place ☐ Pre-Cast ☐ Masonry ☒ Other ☐

**STRUCTURE ELEMENT:** Footing ☐ SOG ☐ Wall ☒ Column ☐ Beam ☐ Deck ☐ Other ☐

**TARGET INDICATIONS:** Reinforcing Steel ☒ PT Cables ☐ PVC Conduit ☐ Voids ☐  
Grouted Cells ☒ Un-Grouted Cells ☐ Other ☐

**PICTURES TAKEN:** Yes ☒ No ☐ **TARGETS MARKED WITH:** Crayon ☐ Paint ☐ Tape ☒

**CONCRETE TARGET INDICATION ORIENTATION / APPROXIMATE SPACING AND DEPTH:**

Vertical Target Spacing: \_\_\_\_\_  
Vertical Target Depth: \_\_\_\_\_

Horizontal Target Spacing: \_\_\_\_\_  
Horizontal Target Depth: \_\_\_\_\_

Longitudinal Target Spacing: \_\_\_\_\_  
Longitudinal Target Depth: \_\_\_\_\_

Lateral Target Spacing: \_\_\_\_\_  
Lateral Target Depth: \_\_\_\_\_

**CMU TARGET INDICATION ORIENTATION / APPROXIMATE SPACING AND DEPTH:**

Vertical Target Spacing: 1st adjacent cell of wood column and near mid span (grouted)  
Vertical Target Depth: \_\_\_\_\_

Horizontal Target Spacing: Possible bond beams at 8'-6" above FF (grouted)  
Horizontal Target Depth: \_\_\_\_\_

Masonry Joint Reinf. Spacing: At 16", 32", 48", 64" and 88" above FF

**ADDITIONAL NOTES/OBSERVATIONS:**

8"x8"x16" CMU Block

The information presented is based upon interpretation of the data collected and is provided solely for illustration and informational purposes. Speedie & Associates is not responsible for any loss or damage caused, arising out of the use of or reliance on the data collected or the report generated. Speedie & Associates hereby disclaims all warranties, expressed or implied with respect to the nature, or quality of the services performed hereunder and except to the extent of its sole gross negligence shall not be liable for any damages as a result of its performance.

Accepted By: \_\_\_\_\_ Technician: Rodd Whisel

# SPEEDIE AND ASSOCIATES

GEOTECHNICAL/ENVIRONMENTAL/MATERIALS ENGINEERS  
3331 E. Wood St., Phoenix, Arizona 85040 Telephone (602) 997-6391 Fax (602) 943-5508

## GROUND PENETRATING RADAR SCAN NOTES

**Project Name:** Mensendick/Jack Elementary School Distress - GPR **Project #:** 161288TA **Date:** 07/07/2016  
**Project Location:** 535 N. 67th Ave., Glendale AZ **Time Start:** 4:30AM **Time Stop:** 2:30PM  
**Client:** SPS Architects **Rep:** Jennifer Bowen **Doc #:** GPR RW432-15

**SCAN NUMBER:** 5-SOG

**SCAN LOCATION:** Jack School, Room 515, SOG West end of room near center (PO picture 15)

**STRUCTURE TYPE:** Cast in Place ☒ Pre-Cast ☐ Masonry ☐ Other ☐

**STRUCTURE ELEMENT:** Footing ☐ SOG ☒ Wall ☐ Column ☐ Beam ☐ Deck ☐ Other ☐

**TARGET INDICATIONS:** Reinforcing Steel ☒ PT Cables ☐ PVC Conduit ☐ Voids ☐  
Grouted Cells ☐ Un-Grouted Cells ☐ Other ☐

**PICTURES TAKEN:** Yes ☒ No ☐ **TARGETS MARKED WITH:** Crayon ☐ Paint ☐ Tape ☒

**CONCRETE TARGET INDICATION ORIENTATION / APPROXIMATE SPACING AND DEPTH:**

Vertical Target Spacing: \_\_\_\_\_  
Vertical Target Depth: \_\_\_\_\_

Horizontal Target Spacing: \_\_\_\_\_  
Horizontal Target Depth: \_\_\_\_\_

Longitudinal Target Spacing: No indications  
Longitudinal Target Depth: \_\_\_\_\_

Lateral Target Spacing: No indications  
Lateral Target Depth: \_\_\_\_\_

**CMU TARGET INDICATION ORIENTATION / APPROXIMATE SPACING AND DEPTH:**

Vertical Target Spacing: \_\_\_\_\_  
Vertical Target Depth: \_\_\_\_\_

Horizontal Target Spacing: \_\_\_\_\_  
Horizontal Target Depth: \_\_\_\_\_

Masonry Joint Reinf. Spacing: \_\_\_\_\_

**ADDITIONAL NOTES/OBSERVATIONS:**

Approximate scan area 10'x10'  
Approximate slab thickness 5.0"

The information presented is based upon interpretation of the data collected and is provided solely for illustration and informational purposes. Speedie & Associates is not responsible for any loss or damage caused, arising out of the use of or reliance on the data collected or the report generated. Speedie & Associates hereby disclaims all warranties, expressed or implied with respect to the nature, or quality of the services performed hereunder and except to the extent of its sole gross negligence shall not be liable for any damages as a result of its performance.

Accepted By: \_\_\_\_\_ Technician: Rodd Whisel





Project Name: Mensendick School-Building Distress - GPR

Project Address: 5535 N. 67<sup>th</sup> Ave. – Glendale, AZ.

Photo Outline 1

Project No.:161288TA / GPR RW432

Date: July 7, 2016

			
No. 1	Scan 1-Wall: Mensendick, Rm 602, S. wall. Green Tape indicating ungrouted target, possible electrical conduit.	No. 2	Scan 1-SOG: Mensendick, Rm 602. Approx 10'x10' area. slab approx.. 4" Thick.
			
No. 3	Scan 2-Wall: Mensendick, Rm. 623, W. wall. Orange vert-rebar, green horiz joint reinf. Blue- steel indications at top course	No. 4	Scan 3-Wall: Mensendick, Rm 625, S. wall. Green-horiz joint reinf. White-steel indications at wood columns (grouted solid)





Project Name: Mensendick School-Building Distress - GPR

Project Address: 5535 N. 67<sup>th</sup> Ave. – Glendale, AZ.

Photo Outline 1

Project No.:161288TA / GPR RW432

Date: July 7, 2016

	
No. 5 Scan 2 SOG: Mensendick, Rm. 624. Approx. 10'x10' area. NWC of Room. No indication of reinf, approx 4" thick. Note crack at blue arrow.	No. 6 Scan 4 Wall: Mensendick, Rm. 537, N wall. Orange-vert & horiz reinf. Green-joint reinf at bottom of wall
	
No. 7 Scan 3 SOG: Jack, Rm 528, S. SOG at center of room, slab approx. 4" thick	No. 8 Scan 5 Wall: Jack, Rm 521: Orange-vert & horiz reinf (dashed line not grouted), greet-joint reinf







**Project Name: Mensendick School-Building Distress - GPR**

**Project Address: 5535 N. 67<sup>th</sup> Ave. – Glendale, AZ.**

**Photo Outline 2**

Project No.:161288TA / GPR RW432

Date: July 7, 2016

	
<p>No. 9</p> <p>Scan 6 Wall: Jack Bldg., Rm. 518 N. wall. Orange-vert. &amp; horiz. reinf. Green-joint reinf.</p>	<p>No. 10</p> <p>Scan 7 Wall: Jack Bldg. Rm. 521. S. wall. Orange-vert. &amp; horiz. Reinf (dashed line indicates voids). Green – joint reinf, infill at man door</p>
	
<p>No. 11</p> <p>Scan 8 Wall: Jack Bldg. Rm. 517, S. wall. Orange-vert &amp; horiz. Reinf, green-joint reinf.</p>	<p>No. 12</p> <p>Scan 4 SOG: Jack Bldg. Rm. 515. W. end at center of room. White tape indicates possible rebar/conduits 2" deep, Slab approx.. 4" thick.</p>




Project Name: Mensendick School-Building Distress - GPR

Project Address: 5535 N. 67<sup>th</sup> Ave. – Glendale, AZ.

Photo Outline 2

Project No.:161288TA / GPR RW432

Date: July 7, 2016

			
No. 13	Scan 9 Wall: Jack Bldg., Rm. 506 N. Wall. Orange-vert. & horiz. reinf, Green-joint reinf.	No. 14	Scan 10 Wall: Jack Bldg. Rm. 503, N. Wall. Orange-vert. & horiz. reinf. Green-joint reinf.
			
No. 15	Scan 5 SOG: Jack Bldg. Rm. 502 W. end at center of room. Approx.. 10'x10' area. No reinf. indications. SOG approx. 5''		

SOILS

INVESTIGATION

REPORT

August 5, 2016

Jennifer Bowen, AIA  
SPS+ Partners Architects LLP  
8681 E. Via de Negocio  
Scottsdale, AZ 85258

**RE: Project No. 161211SA  
Mensendick School – Building Distress  
5535 North 67<sup>th</sup> Avenue  
Glendale, AZ  
Findings & Test Results**

Dear Ms. Bowen:

This letter presents the findings of our visual site assessment, limited subsurface investigation and our opinions on the possible cause(s) for the stair step cracking of the masonry walls, separation of doorframes from masonry walls and evidence of slab movement of the interior of the buildings resulting in slab cracks.

On July 7 and 8, 2016, representatives from Speedie & Associates were at the site to conduct a limited soil investigation, as outlined in our proposal number 56061s. The investigation was broken into three tasks. The first task consisted of coring the interior slab of the buildings at three (3) locations and obtaining soil samples. The second task was to hand auger up to fifteen (15) exterior locations and obtaining soil samples. The third task was to excavate six (6) test pits on the exterior of the buildings in order to determine the depth and size of the footings and general subsoil bearing conditions, including the type of footing or turnaround.

The results of the sampling and individual logs of each core, boring and test pit location and laboratory data are attached to this report. The approximate locations of each are located on the attached Soil Boring Location Plan. The following summarizes our findings:

### **Interior Testing**

Three cores were selected at the interior of three separate buildings spread throughout the school campus. Each core was made along the interior walls. Coring consisted of hand augering and sampling of soils up to 3 to 4 feet below grade.

The concrete building slab thicknesses ranged from approximately 4.25 to 5.50 inches underlain by 4.0 to 6.0 inches of coarse gravel. It is noted that core C-2 had a 3-inch void under the slab. The subgrade soils consisted of moist sandy lean clay. An undisturbed ring sample was taken of the subgrade soils at a depth of 2.5 and 3.5 feet below the existing surface. The samples were obtained by driving a ring sampler with a 30-lb post hammer. At a depth of 1.5 feet it took between 13 and 27 blows to drive the hammer 12 inches. At a depth of 2.5 feet it took between 16 and 35 blows to drive the hammer 12 inches.

### **Exterior Testing**

Fifteen hand auger borings were selected throughout the school campus along the south side of the buildings in the landscaped areas closest to the buildings. The majority of the landscaping was consistent with irrigated grass and large trees. Each boring was hand augered to a depth of approximately three feet below existing grade and soil samples were obtained at each foot interval. Subgrade soils consisted predominately of moist sandy lean clay with the exception of borings B-10, B-11 and B-14, which consisted of moist sandy silty clay with subordinate amount of gravel.

### **Test Pits**

As part of this analysis, six locations on the north side of the buildings were selected to document the current soil conditions, depth of foundations and foundation type. Samples of the soils over and under the slab footings were obtained by means of hand auger. The subgrade soils consisted predominately of moist sandy lean clay and moist sandy silty clay.

Depths to the bottom of the footings ranged from 21 to 42 inches. It is noted that test pit #3 was not excavatable due to an existing sewer line that runs parallel to the building. More detailed diagrams and measurements of the footing dimensions are located on the attached Test Pit/Footing Details.

### **General Subsurface Conditions**

The native subsoils consisted primarily of sandy lean clay and sandy silty clay to the termination depths of 3 to 4 feet below existing grades. Subordinate amounts of gravel were also noted throughout the profile. No groundwater was encountered during this investigation. Based on visual and tactile observation, the upper soils were in a 'moist' state at the time of investigation.

Laboratory testing indicates in-situ dry densities of the upper soils ranged from 78 to 107 pcf and water contents from 7.2 to 26.4 percent at the time of investigation. Liquid limits ranged from 23 to 30 percent with plasticity indices at 16 to 19 percent. The upper clayey soils exhibit volume increase (swell) due to wetting of 1.6 to 3.8 percent when compacted to moisture and density levels normally expected during construction. Undisturbed samples displayed minor to moderate (2 to 4%) compression due to incremental loading and **minor to significant (1 to 16%)** additional compression due to inundation under a maximum confining load of 3,200 psf.



Laboratory testing for sulfate contents indicates 22 ppm. This value represents a minor potential for sulfate attack on concrete. The soil pH was 8.2, the soil resistivity was 1000 Ohm-Centimeters, and Chloride concentrations were 149 ppm. The laboratory resistivity test is conducted under a saturated condition. In the field, the saturation of soils should not be expected which would thereby increase the resistivity. Based on the soil classification, test results and local experience, the soils will likely have moderate corrosivity to direct buried metal. Chloride concentrations of 500 ppm or greater are considered severely corrosive.

### Conclusions

At this time no obvious single cause was observed to cause the distress in the building. Based on the limited investigation, our laboratory testing and field observation, it is our opinion that the distress may be related to a combination of water induced settlement, or shrinkage of the soil and possibly minor amounts of slab heave or swell as a result of moisture fluctuations in the supporting soils. These moisture fluctuations are a result of the constant irrigation of the grassy areas surrounding the buildings. Based on the soil classification and observations, the soils on the site are moisture sensitive and will be prone to volume change (both shrinkage and swelling) as a result of moisture changes (drying and wetting).

Most all soils related issues are in direct relationship to moisture change in the supporting soils. This can come from results of wet utility leaks or breaks, over irrigation, or poor drainage. Based on the samples obtained, the amounts of moisture in the majority of the soils were at optimum moisture or higher.

At this time our scope was only to conduct the field sampling and laboratory testing and provide the data obtained. If there are any questions, please feel free to call.

Respectfully Submitted,  
SPEEDIE & ASSOCIATES, INC.




Ray C. Markley Jr., E.I.T.




Keith R. Gravel, P.E.

Attachments


TEST PIT #1




TEST PIT #2




TEST PIT #4



TEST PIT #5



TEST PIT #6



TEST PIT / FOOTING DETAILS

DR. TSW

REV:

CHK:


DATE: 08/05/18

PROJECT NO. 1612118A

MENSENICK SCHOOL BUILDING DISTRESS

5535 N. 67TH AVENUE  
GLENDALE, ARIZONA

**SPEEDIE**  
AND ASSOCIATES  
GEOTECHNICAL/ENVIRONMENTAL/MATERIALS ENGINEERS  
3531 E. WOOD ST.  
PHOENIX, ARIZONA 85018  
(602) 997-5071



W. MISSOURI AVENUE

N. 67TH AVENUE

- - APPROXIMATE HAND-AUGER BORING LOCATIONS
- - APPROXIMATE FLOOR SLAB CORE LOCATIONS
- - APPROXIMATE TEST PIT LOCATIONS



## SOIL BORING LOCATION PLAN

MENSENDICK SCHOOL BUILDING DISTRESS

5535 N. 67TH AVENUE  
GLENDALE, ARIZONA

**SPEEDIE  
AND ASSOCIATES**  
GEOTECHNICAL/ENVIRONMENTAL ENGINEERS  
201 E. 10TH ST.  
PHOENIX, ARIZONA 85004  
(602) 977-4391

DR: TSW	REV:	CHK:	DATE: 07/06/16	PROJECT NO. 161211SA
---------	------	------	----------------	----------------------

Depth (feet)	Graphic Log	Rig Type: <b>Hand Auger</b> Boring Type: <b>Hollow Stem Auger</b> Surface Elevation: <b>N/A</b>	Sample Number	Depth of Sample	Natural Water Content (%)	In-place Dry Density (P.C.F.)	Penetration Resistance Blows per Foot
		Visual Classification					0      25      60
0		Firm Brown <u>SANDY LEAN CLAY</u> (CL-Moist) with Trace Gravel					
			AS-1	1.0	NT	NT	
			AS-2	2.0	NT	NT	
			AS-3	3.0	10.7	NT	
5							

Boring Date: **7-7-16**  
 Field Engineer/Technician: **K. Euge II**  
 Driller: **R. Markley**  
 Contractor: **Speedie & Assoc.**

Water Level		
Depth	Hour	Date
Free Water was Not Encountered		

NT = Not Tested

<b>SPEEDIE AND ASSOCIATES</b>
Log of Test Boring Number: <b>B-1</b>
<b>Mensendick School-Building Distress</b>  <b>5535 North 67th Avenue</b>  <b>Glendale, Arizona</b>  Project No.: <b>161211SA</b>

SPEEDIE 161211SA.GPJ GENGEO.GDT 8/1/16

Depth (feet)	Graphic Log	Rig Type: Hand Auger Boring Type: Hollow Stem Auger Surface Elevation: N/A	Sample Number	Depth of Sample	Natural Water Content (%)	In-place Dry Density (P.C.F.)	Penetration Resistance Blows per Foot
		Visual Classification					
0		Firm Brown <u>SANDY LEAN CLAY</u> (CL-Moist) with Trace Gravel	AS-1	1.0	NT	NT	
AS-2			2.0	NT	NT		
AS-3			3.0	14.7	NT		
End of Boring							
5							

Boring Date: 7-7-16  
 Field Engineer/Technician: K. Euge II  
 Driller: R. Markley  
 Contractor: Speedie & Assoc.

Water Level		
Depth	Hour	Date
Free Water was Not Encountered		

NT = Not Tested

<b>SPEEDIE AND ASSOCIATES</b>
Log of Test Boring Number: <b>B- 2</b>
Mensendick School-Building Distress  5535 North 67th Avenue  Glendale, Arizona
Project No.: 161211SA

SPEEDIE 161211SA.GPJ GENGEO.GDT 8/1/16



Depth (feet)

0

5

**Graphic Log**

Rig Type: Hand Auger  
 Boring Type: Hollow Stem Auger  
 Surface Elevation: N/A

Visual Classification

Firm Brown SANDY LEAN CLAY (CL-Moist)  
 with Trace Gravel

End of Boring

Sample Number	Depth of Sample	Natural Water Content (%)	In-place Dry Density (P.C.F.)	Penetration Resistance Blows per Foot
AS-1	1.0	15.7	NT	
AS-2	2.0	NT	NT	
AS-3	3.0	NT	NT	

Boring Date: 7-7-16  
 Field Engineer/Technician: K. Euge II  
 Driller: R. Markley  
 Contractor: Speedie & Assoc.

Water Level		
Depth	Hour	Date
Free Water was Not Encountered		

NT = Not Tested

**SPEEDIE AND ASSOCIATES**

Log of Test Boring Number: **B- 3**

**Mensendick School-Building Distress**

**5535 North 67th Avenue**

**Glendale, Arizona**

Project No.: **161211SA**

SPEEDIE 161211SA.GPJ GENEOQ.GDT 8/1/16

0

Firm Brown SANDY LEAN CLAY (CL-Moist)

End of Boring

5

The diagram is a vertical cross-section of a soil boring. On the left, a vertical line represents the borehole wall. The upper portion of this line is filled with a diagonal hatching pattern. A horizontal dashed line extends from the borehole wall to the right, labeled "End of Boring". To the right of the borehole wall, the text "Firm Brown SANDY LEAN CLAY (CL-Moist)" is written. At the bottom of the borehole wall, there is a small horizontal tick mark and the number "5".

Sample Number	Depth of Sample	Natural Water Content (%)	In-place Dry Density (P.C.F.)	Penetration Resistance Blows per Foot
AS-1	1.0	NT	NT	0 25 50

**Boring Date:** 7-7-16  
**Field Engineer/Technician:** K. Euge II  
**Driller:** R. Markley  
**Contractor:** Speedie & Assoc.

Water Level		
Depth	Hour	Date
<i>Free Water was Not Encountered</i>		

NT = Not Tested

**SPEEDIE  
AND ASSOCIATES**

Log of Test Boring Number: **B- 4**

**Mensendick School-Building Distress**

**5535 North 67th Avenue**

**Glendale, Arizona**

**Project No.: 161211SA**

\_\_SPEEDIE 161211SA.GPJ GENGEO.GDT 8/7/16

Depth (feet)	Graphic Log	<b>Rig Type:</b> Hand Auger <b>Boring Type:</b> Hollow Stem Auger <b>Surface Elevation:</b> N/A	Sample Number	Depth of Sample	Natural Water Content (%)	In-place Dry Density (P.C.F.)	Penetration Resistance Blows per Foot
0		<b>Visual Classification</b>  Firm Brown <u>SANDY LEAN CLAY</u> (CL-Moist)					0 25 50
			AS-1	1.0	NT	NT	
			AS-2	2.0	NT	NT	
			AS-3	3.0	13.5	NT	
5		End of Boring					

**Boring Date:** 7-7-16  
**Field Engineer/Technician:** K. Euge II  
**Driller:** R. Markley  
**Contractor:** Speedie & Assoc.

Water Level		
Depth	Hour	Date
Free Water was Not Encountered		

NT = Not Tested

<b>SPEEDIE AND ASSOCIATES</b>
<b>Log of Test Boring Number: B- 5</b>
<b>Mensendick School-Building Distress</b>  <b>5535 North 67th Avenue</b>  <b>Glendale, Arizona</b>  <b>Project No.: 161211SA</b>

SPEEDIE 161211SA.GPJ GENGEO.GDT 8/1/16

Depth (feet)	Graphic Log	<b>Rig Type:</b> Hand Auger <b>Boring Type:</b> Hollow Stem Auger <b>Surface Elevation:</b> N/A	Sample Number	Depth of Sample	Natural Water Content (%)	In-place Dry Density (P.C.F.)	Penetration Resistance Blows per Foot
0		<b>Visual Classification</b>					
		Firm Brown <u>SANDY LEAN CLAY (CL-Moist)</u>					
			AS-1	1.0	NT	NT	
			AS-2	2.0	NT	NT	
			AS-3	3.0	22.8	NT	
5		End of Boring -----					


**Boring Date:** 7-7-16  
**Field Engineer/Technician:** K. Euge II  
**Driller:** R. Markley  
**Contractor:** Speedle & Assoc.

Water Level		
Depth	Hour	Date
Free Water was Not Encountered		

NT = Not Tested

<b>SPEEDIE AND ASSOCIATES</b>
<b>Log of Test Boring Number: B- 6</b>
<b>Mensendick School-Building Distress</b>  <b>5535 North 67th Avenue</b>  <b>Glendale, Arizona</b>
<b>Project No.: 161211SA</b>

SPEEDIE 161211SA GPJ GENGEO.GDT 8/1/16

Depth (feet)	Graphic Log	<b>Rig Type:</b> Hand Auger <b>Boring Type:</b> Hollow Stem Auger <b>Surface Elevation:</b> N/A	Sample Number	Depth of Sample	Natural Water Content (%)	In-place Dry Density (P.C.F.)	Penetration Resistance Blows per Foot
0		<b>Visual Classification</b>  Firm Brown <u>SANDY LEAN CLAY</u> (CL-Moist)					
			AS-1	1.0	NT	NT	
			AS-2	2.0	18.8	NT	
			AS-3	3.0	NT	NT	
5		End of Boring					

**Boring Date:** 7-7-16  
**Field Engineer/Technician:** K. Euge II  
**Driller:** R. Markley  
**Contractor:** Speedie & Assoc.


Water Level		
Depth	Hour	Date
Free Water was Not Encountered		

NT = Not Tested

<b>SPEEDIE AND ASSOCIATES</b>
<b>Log of Test Boring Number: B-7</b>
<b>Mensendick School-Building Distress</b>  <b>5535 North 67th Avenue</b>  <b>Glendale, Arizona</b>  <b>Project No.: 161211SA</b>

SPEEDIE 161211SA.GPJ GENGEO.GOT 8/1/16





Boring Date: 7-7-16  
 Field Engineer/Technician: K. Euge II  
 Driller: R. Markley  
 Contractor: Speedie & Assoc.

Water Level		
Depth	Hour	Date
Free Water was Not Encountered		

NT = Not Tested

<b>SPEEDIE AND ASSOCIATES</b>	
Log of Test Boring Number: <b>B- 8</b>	
Mensendick School-Building Distress 5535 North 67th Avenue Glendale, Arizona	
Project No.: 161211SA	

SPEEDIE 161211SA.GPJ GENGEO.GDT 8/1/16

Graphic Log

## Visual Classification

Firm Brown SANDY LEAN CLAY (CL-Moist)

Penetration  
Resistance  
Blows  
per Foot

NT

## End of Boring

Water Level		
Depth	Hour	Date
<i>Free Water was Not Encountered</i>		

**Project No.: 161211SA**

SPEEDIE 101211SA.GPJ GENGE0.GDT 84/16

Depth (feet)	Graphic Log	Rig Type: Hand Auger Boring Type: Hollow Stem Auger Surface Elevation: N/A	Sample Number	Depth of Sample	Natural Water Content (%)	In-place Dry Density (P.C.F.)	Penetration Resistance Blows per Foot
0		<b>Visual Classification</b>  Firm Brown <u>SANDY SILTY CLAY</u> (CL/ML-Moist)					0 25 50
			AS-1	1.0	NT	NT	
			AS-2	2.0	NT	NT	
			AS-3	3.0	26.4	NT	
		End of Boring					
5							

Boring Date: 7-7-16  
 Field Engineer/Technician: K. Euge II  
 Driller: R. Markley  
 Contractor: Speedie & Assoc.

Water Level		
Depth	Hour	Date
Free Water was Not Encountered		

NT = Not Tested

<b>SPEEDIE AND ASSOCIATES</b>
Log of Test Boring Number: <b>B-10</b>
<b>Mensendick School-Building Distress</b>  5535 North 67th Avenue  Glendale, Arizona  Project No.: 161211SA

SPEEDIE 161211SA.GPJ GENGEO.GDT 8/1/16

Depth (feet)	Graphic Log	<b>Rig Type:</b> Hand Auger <b>Boring Type:</b> Hollow Stem Auger <b>Surface Elevation:</b> N/A	Sample Number	Depth of Sample	Natural Water Content (%)	In-place Dry Density (P.C.F.)	Penetration Resistance Blows per Foot
0		<b>Visual Classification</b>					0 25 50
		Firm Brown <u>SANDY LEAN CLAY</u> (CL-Moist)	AS-1	1.0	NT	NT	
			AS-2	2.0	NT	NT	
			AS-3	3.0	14.5	NT	
5		End of Boring					


**Boring Date:** 7-7-16  
**Field Engineer/Technician:** K. Euge II  
**Driller:** R. Markley  
**Contractor:** Speedie & Assoc.

Water Level		
Depth	Hour	Date
Free Water was Not Encountered		

NT = Not Tested

<b>SPEEDIE AND ASSOCIATES</b>
<b>Log of Test Boring Number: B-11</b>
<b>Mensendick School-Building Distress</b>  5535 North 67th Avenue  Glendale, Arizona  <b>Project No.: 161211SA</b>

\_SPEEDIE 161211SA.GPJ GENGEO.GDT 8/1/16



Boring Date: 7-7-16  
 Field Engineer/Technician: K. Euge II  
 Driller: R. Markley  
 Contractor: Speedie & Assoc.


Water Level		
Depth	Hour	Date
Free Water was Not Encountered		

NT = Not Tested

<b>SPEEDIE AND ASSOCIATES</b>
Log of Test Boring Number: <b>B-12</b>
<b>Mensendick School-Building Distress</b>
<b>5535 North 67th Avenue</b>
<b>Glendale, Arizona</b>
Project No.: <b>161211SA</b>

SPEEDIE 161211SA.GPJ GENGEO.GDT 8/1/16





Boring Date: 7-7-16  
Field Engineer/Technician: K. Euge II  
Driller: R. Markley  
Contractor: Speedie & Assoc.

Water Level		
Depth	Hour	Date
Free Water was Not Encountered		

NT = Not Tested

<b>SPEEDIE AND ASSOCIATES</b>
Log of Test Boring Number: <b>B-13</b>
<b>Mensendick School-Building Distress</b>  <b>5535 North 67th Avenue</b>  <b>Glendale, Arizona</b>
Project No.: <b>161211SA</b>

SPEEDIE 161211SA.GPJ GENGEO.GDT 8/1/16

Rig Type:	Hand Auger
Boring Type:	Hollow Stem Auger
Surface Elevation:	N/A

## Visual Classification

Firm Brown SANDY SILTY CLAY  
(CL/ML-Moist) with Trace Gravel

### 3.0

## End of Boring

**Boring Date:** 7-7-16  
**Field Engineer/Technician:** K. Euge II  
**Driller:** R. Markley  
**Contractor:** Speedie & Assoc.

Water Level		
Depth	Hour	Date
<i>Free Water was Not Encountered</i>		

**NT = Not Tested**

[illegible]

# SPEEDIE AND ASSOCIATES

Log of Test Boring Number: **B-14**

### Mensendick School-Building Distress

**5535 North 67th Avenue**

## Glendale, Arizona

Project No.: 161211SA

**SPEEDIE 161211SA.GPJ GENGEQ.GDT BMHB**

Depth (feet)	Graphic Log	<b>Rig Type:</b> Hand Auger <b>Boring Type:</b> Hollow Stem Auger <b>Surface Elevation:</b> N/A	Sample Number	Depth of Sample	Natural Water Content (%)	In-place Dry Density (P.C.F.)	Penetration Resistance Blows per Foot
0		<b>Visual Classification</b>					
		Firm Brown <u>SANDY LEAN CLAY</u> (CL-Moist)					
			AS-1	1.0	NT	NT	
			AS-2	2.0	NT	NT	
			AS-3	3.0	21.6	NT	
5		End of Boring					


**Boring Date:** 7-7-16  
**Field Engineer/Technician:** K. Euge II  
**Driller:** R. Markley  
**Contractor:** Speedie & Assoc.

Water Level		
Depth	Hour	Date
Free Water was Not Encountered		

NT = Not Tested

<b>SPEEDIE AND ASSOCIATES</b>
<b>Log of Test Boring Number: B-15</b>
<b>Mensendick School-Building Distress</b>  <b>5535 North 67th Avenue</b>  <b>Glendale, Arizona</b>  <b>Project No.: 161211SA</b>

SPEEDIE 161211SA.GPJ GENGEO.GDT 8/1/16




Boring Date: 7-7-16  
 Field Engineer/Technician: K. Euge II  
 Driller: R. Markley  
 Contractor: Speedie & Assoc.

Water Level		
Depth	Hour	Date
Free Water was Not Encountered		

NT = Not Tested

<b>SPEEDIE AND ASSOCIATES</b>
Log of Test Boring Number: <b>C-1</b>
<b>Mensendick School-Building Distress</b>  <b>5535 North 67th Avenue</b>  <b>Glendale, Arizona</b>
Project No.: <b>161211SA</b>

SPEEDIE 161211SA.GPJ GENGEO.GDT 8/1/16



Boring Date: 7-7-16  
 Field Engineer/Technician: K. Euge II  
 Driller: R. Markley  
 Contractor: Speedie & Assoc.


Water Level		
Depth	Hour	Date
Free Water was Not Encountered		

NT = Not Tested

<b>SPEEDIE AND ASSOCIATES</b>
Log of Test Boring Number: <b>C-2</b>
<b>Mensendick School-Building Distress</b>  <b>5535 North 67th Avenue</b>  <b>Glendale, Arizona</b>
Project No.: <b>161211SA</b>

SPEEDIE 161211SA.GPJ GENGEO.GDT 8/1/16





Boring Date: 7-7-16  
 Field Engineer/Technician: K. Euge II  
 Driller: R. Markley  
 Contractor: Speedie & Assoc.

Water Level		
Depth	Hour	Date
Free Water was Not Encountered		

NT = Not Tested

<b>SPEEDIE AND ASSOCIATES</b>
Log of Test Boring Number: C-3
Mensendick School-Building Distress
5535 North 67th Avenue
Glendale, Arizona
Project No.: 161211SA

SPEEDIE 161211SA.GPJ GENGEO.GDT 8/1/16



Sample Number	Depth of Sample	Natural Water Content (%)	In-place Dry Density (P.C.F.)	Penetration Resistance Blows per Foot
				0 25 50

<b>SPEEDIE AND ASSOCIATES</b>
Log of Test Pit Number: TP-2
Mensendick School-Building Distress
5535 North 67th Avenue
Glendale, Arizona
Project No.: 161211SA

TEST ENT 161241SA GP1 GENREFO GDT 84HH8

TEST PIT 161211SA.GPJ GENGEO.GDT B/M/M6

Depth (feet)	Graphic Log	Equipment Type: Hand Tools Hand Excavation Surface Elevation: N/A	Sample Number	Depth of Sample	Natural Water Content (%)	In-place Dry Density (P.C.F.)	Penetration Resistance Blows per Foot
0		Visual Classification					0 25 50
		Soft to Firm Brown <u>SANDY LEAN CLAY</u> (CL-Moist) with Trace Gravel					
		End of Test Pit					
			BS-1	3.5	NT	NT	
5							

Excavation Date: 7-8-16  
 Field Engineer/Technician: K. Euge II  
 Excavator: R. Markley  
 Contractor: Speedie & Assoc.

Water Level		
Depth	Hour	Date
Free Water was Not Encountered		

NT = Not Tested

<b>SPEEDIE AND ASSOCIATES</b>
Log of Test Pit Number: TP-4
Mensendick School-Building Distress
5535 North 67th Avenue
Glendale, Arizona
Project No.: 161211SA

TEST PIT 161211SA.GPJ GENGEO.GDT 8/1/16





Log  
Graphic

## Visual Classification

Soft to Firm Brown SANDY SILTY CLAY  
(CL/ML-Moist) with Trace Gravel

## 1.8

## End of Test Pit

5.

Excavation Date: 7-8-16  
Field Engineer/Technician: K. Euge II  
Excavator: R. Markley  
Contractor: Speedie & Assoc.

Water Level		
Depth	Hour	Date
<i>Free Water was Not Encountered</i>		

**NT = Not Tested**

Sample Number

Depth  
of  
Sample

Natural Water Content (%)	Stress Ratio	Strain (%)	Modulus (GPa)
60	0.8	0.0	0.00
60	0.8	0.1	0.00
60	0.8	0.2	0.00
60	0.8	0.3	0.00
60	0.8	0.4	0.00
60	0.8	0.5	0.00
60	0.8	0.6	0.00
60	0.8	0.7	0.00
60	0.8	0.8	0.00
60	0.8	0.9	0.00
60	0.8	1.0	0.00
60	0.8	1.1	0.00
60	0.8	1.2	0.00
60	0.8	1.3	0.00
60	0.8	1.4	0.00
60	0.8	1.5	0.00
60	0.8	1.6	0.00
60	0.8	1.7	0.00
60	0.8	1.8	0.00
60	0.8	1.9	0.00
60	0.8	2.0	0.00
60	0.8	2.1	0.00
60	0.8	2.2	0.00
60	0.8	2.3	0.00
60	0.8	2.4	0.00
60	0.8	2.5	0.00
60	0.8	2.6	0.00
60	0.8	2.7	0.00
60	0.8	2.8	0.00
60	0.8	2.9	0.00
60	0.8	3.0	0.00
60	0.8	3.1	0.00
60	0.8	3.2	0.00
60	0.8	3.3	0.00
60	0.8	3.4	0.00
60	0.8	3.5	0.00
60	0.8	3.6	0.00
60	0.8	3.7	0.00
60	0.8	3.8	0.00
60	0.8	3.9	0.00
60	0.8	4.0	0.00
60	0.8	4.1	0.00
60	0.8	4.2	0.00
60	0.8	4.3	0.00
60	0.8	4.4	0.00
60	0.8	4.5	0.00
60	0.8	4.6	0.00
60	0.8	4.7	0.00
60	0.8	4.8	0.00
60	0.8	4.9	0.00
60	0.8	5.0	0.00
60	0.8	5.1	0.00
60	0.8	5.2	0.00
60	0.8	5.3	0.00
60	0.8	5.4	0.00
60	0.8	5.5	0.00
60	0.8	5.6	0.00
60	0.8	5.7	0.00
60	0.8	5.8	0.00
60	0.8	5.9	0.00
60	0.8	6.0	0.00
60	0.8	6.1	0.00
60	0.8	6.2	0.00
60	0.8	6.3	0.00
60	0.8	6.4	0.00
60	0.8	6.5	0.00
60	0.8	6.6	0.00
60	0.8	6.7	0.00
60	0.8	6.8	0.00
60	0.8	6.9	0.00
60	0.8	7.0	0.00
60	0.8	7.1	0.00
60	0.8	7.2	0.00
60	0.8	7.3	0.00
60	0.8	7.4	0.00
60	0.8	7.5	0.00
60	0.8	7.6	0.00
60	0.8	7.7	0.00
60	0.8	7.8	0.00
60	0.8	7.9	0.00
60	0.8	8.0	0.00
60	0.8	8.1	0.00
60	0.8	8.2	0.00
60	0.8	8.3	0.00
60	0.8	8.4	0.00
60	0.8	8.5	0.00
60	0.8	8.6	0.00
60	0.8	8.7	0.00
60	0.8	8.8	0.00
60	0.8	8.9	0.00
60	0.8	9.0	0.00
60	0.8	9.1	0.00
60	0.8	9.2	0.00
60	0.8	9.3	0.00
60	0.8	9.4	0.00
60	0.8	9.5	0.00
60	0.8	9.6	0.00
60	0.8	9.7	0.00
60	0.8	9.8	0.00
60	0.8	9.9	0.00
60	0.8	10.0	0.00
60	0.8	10.1	0.00
60	0.8	10.2	0.00
60	0.8	10.3	0.00
60	0.8	10.4	0.00
60	0.8	10.5	0.00
60	0.8	10.6	0.00
60	0.8	10.7	0.00
60	0.8	10.8	0.

**In-place  
Dry Density  
(P.C.F.)**

Penetration  
Resistance  
Blows  
per Foot

2

—

BS-1

## 2.5

NT

NT

# SPEEDIE AND ASSOCIATES

Log of Test Pit Number: TP-6

### Mensendick School-Building Distress

**5535 North 67th Avenue**

## Glendale, Arizona

**Project No.: 161211SA**

TEST BIT 161211SA GPJ GENGE0.GDT BMH6

# TABULATION OF TEST DATA

SOIL BORING or TEST PIT NUMBER	SAMPLE NUMBER	SAMPLE TYPE	SAMPLE INTERVAL (ft)	NATURAL WATER CONTENT (Percent of Dry Weight)	IN-PLACE DRY DENSITY (Pounds Per Cubic Foot)	PARTICLE SIZE DISTRIBUTION (Percent Finer)					ATTERBERG LIMITS			UNIFIED SOIL CLASSIFICATION	SPECIMEN DESCRIPTION
						#200 SIEVE	#40 SIEVE	#10 SIEVE	#4 SIEVE	3" SIEVE	LIQUID LIMIT	PLASTIC LIMIT	PLASTICITY INDEX		
B-1	AS-3	AS	2.0 - 3.0	10.7	NT	NT	NT	NT	NT	NT	NT	NT	NT	CL	SANDY LEAN CLAY
B-2	AS-3	AS	2.0 - 3.0	14.7	NT	NT	NT	NT	NT	NT	NT	NT	NT		
B-3	AS-1	AS	0.0 - 1.0	15.7	NT	NT	NT	NT	NT	NT	NT	NT	NT		
B-6	AS-3	AS	2.0 - 3.0	22.8	NT	NT	NT	NT	NT	NT	NT	NT	NT		
B-7	AS-2	AS	1.0 - 2.0	18.8	NT	NT	NT	NT	NT	NT	NT	NT	NT		
B-8	AS-2	AS	1.0 - 2.0	9.5	NT	NT	NT	NT	NT	NT	NT	NT	NT		
B-9	AS-3	AS	2.0 - 3.0	7.2	NT	NT	NT	NT	NT	NT	NT	NT	NT		
B-10	AS-3	AS	2.0 - 3.0	26.4	NT	NT	NT	NT	NT	NT	NT	NT	NT		
B-11	AS-3	AS	2.0 - 3.0	14.5	NT	NT	NT	NT	NT	NT	NT	NT	NT		
B-12	AS-2	AS	1.0 - 2.0	8.1	NT	NT	NT	NT	NT	NT	NT	NT	NT		
B-13	AS-3	AS	2.0 - 3.0	12.7	NT	NT	NT	NT	NT	NT	NT	NT	NT		
B-14	AS-1	AS	0.0 - 1.0	14.6	NT	NT	NT	NT	NT	NT	NT	NT	NT		
B-15	AS-3	AS	2.0 - 3.0	21.6	NT	NT	NT	NT	NT	NT	NT	NT	NT		
C-1	RS-1	RING	1.5 - 2.5	13.2	98.4	93	99	NT	NT	NT	NT	NT	NT		
C-1	RS-2	RING	2.5 - 3.5	12.4	102.6	67	NT	NT	NT	NT	NT	NT	NT		
C-2	RS-1	RING	1.5 - 2.5	14.9	78.3	NT	NT	NT	NT	NT	NT	NT	NT		

Sieve analysis results do not include material greater than 3". Refer to the actual boring logs for the possibility of cobble and boulder sized materials.

NT=Not Tested

Sheet 1 of 2

Mensendick School-Building District

5535 North 67th Avenue

Glendale, Arizona

Project No. 161211SA

**SPEEDIE  
AND ASSOCIATES**

TABULATION OF TEST DATA 161211SA.GPJ GENOEO.GDT 8/1/16

# TABULATION OF TEST DATA

SOIL BORING or TEST PIT NUMBER	SAMPLE NUMBER	SAMPLE TYPE	SAMPLE INTERVAL (ft)	NATURAL WATER CONTENT (Percent of Dry Weight)	IN-PLACE DRY DENSITY (Pounds Per Cubic Foot)	PARTICLE SIZE DISTRIBUTION (Percent Finer)					ATTERBERG LIMITS			UNIFIED SOIL CLASSIFICATION	SPECIMEN DESCRIPTION
						#200 SIEVE	#40 SIEVE	#10 SIEVE	#4 SIEVE	3" SIEVE	LIQUID LIMIT	PLASTIC LIMIT	PLASTICITY INDEX		
C-2	RS-2	RING	2.5 - 3.5	16.1	94.0	NT	NT	NT	NT	NT	NT	NT	NT		
C-3	RS-1	RING	1.5 - 2.5	17.0	106.7	NT	NT	NT	NT	NT	NT	NT	NT		
C-3	RS-2	RING	2.5 - 3.5	20.2	87.5	NT	NT	NT	NT	NT	NT	NT	NT		
TP-1	BS-1	BULK	0.0 - 3.0	NT	NT	61	75	86	96	100	30	19	11	CL	SANDY LEAN CLAY
TP-4	BS-1	BULK	1.5 - 3.5	NT	NT	NT	NT	NT	NT	NT	NT	NT	NT		
TP-6	BS-1	BULK	0.0 - 2.5	NT	NT	52	86	94	96	100	23	17	6	CL-ML	SANDY SILTY CLAY

Sieve analysis results do not include material greater than 3". Refer to the actual boring logs for the possibility of cobble and boulder sized materials.

NT=Not Tested

Sheet 2 of 2

Mensendick School-Building Distress  
5535 North 67th Avenue  
Glendale, Arizona  
Project No. 161211SA

**SPEEDIE**  
AND ASSOCIATES

# SWELL TEST DATA

BORING or TEST PIT No.	SAMPLE DEPTH, ft	MAXIMUM DRY DENSITY (pcf)	OPTIMUM MOISTURE CONTENT (%)	REMOLDED DRY DENSITY (pcf)	INITIAL MOISTURE CONTENT (%)	PERCENT COMPACTION	FINAL MOISTURE CONTENT (%)	CONFINING LOAD (psf)	TOTAL SWELL (%)
TP-1, BS-1	3.0	114.5	13.6	108.9	11.7	95.1	20.4	100	3.8
TP-6, BS-1	2.5	118.6	13.5	112.4	12.0	94.8	17.6	100	1.6

Mensendick School-Building District  
5535 North 67th Avenue  
Glendale, Arizona  
Project No. 161211SA

**SPEDIE**  
AND ASSOCIATES



# CORROSIVE TEST DATA

SOIL BORING or TEST PIT NUMBER	SAMPLE NUMBER	SAMPLE TYPE	SAMPLE INTERVAL (ft)	PERCENT FINER #200 SIEVE	pH	RESISTIVITY (Ohm-Centimeters)	PPM SULFATE (SO4)	PPM CHLORIDE (CL)	SULFIDE (+ or -)	REDOX (millivolts)	UNIFIED SOIL CLASSIFICATION	SPECIMEN DESCRIPTION
TP-4	BS-1	BULK	1.5 - 3.5	NT	8.2	1000	22	149	NT	NT		

Mensendick School-Building Distress  
5535 North 67th Avenue  
Glendale, Arizona  
Project No. 161211SA

**SPEEDIE  
AND ASSOCIATES**

# MOISTURE-DENSITY RELATIONS

PROJECT: Mensendick School-Building Distress

PROJECT NO.: 161211SA

LOCATION: 5535 North 67th Avenue

DATE: 7/8/16

BORING NO.: TP-6

SAMPLE NO.: BS-1

SAMPLE DEPTH: 0 to 2.5

LABORATORY NO.:

METHOD OF COMPACTION:

D698A

LIQUID LIMIT:

23

PLASTIC LIMIT:

17

PLASTICITY INDEX:

6

CLASSIFICATION:


CL-ML

ASTM SOIL DESCRIPTION:

SANDY SILTY CLAY

MAXIMUM DRY DENSITY: 118.6 PCF

OPTIMUM MOISTURE CONTENT: 13.5%



**SPEEDIE  
AND ASSOCIATES**

# MOISTURE-DENSITY RELATIONS

PROJECT: Mensendick School-Building Distress

PROJECT NO.: 181211SA

LOCATION: 5535 North 67th Avenue

DATE: 7/8/16

BORING NO.: TP-1

SAMPLE NO.: BS-1

SAMPLE DEPTH: 0 to 3

LABORATORY NO.:

METHOD OF COMPACTION:

D698A

LIQUID LIMIT: 30

PLASTIC LIMIT: 19

PLASTICITY INDEX:

11


CLASSIFICATION: CL

ASTM SOIL DESCRIPTION:

SANDY LEAN CLAY

MAXIMUM DRY DENSITY: 114.5 PCF

OPTIMUM MOISTURE CONTENT: 13.6%



**SPEEDIE  
AND ASSOCIATES**

# CONSOLIDATION TEST

PROJECT: Mensendick School-Building Distress

PROJECT NO.: 161211SA

LOCATION: 5535 North 67th Avenue

DATE: 7/7/16

BORING NO.: C-3

SAMPLE NO.: RS-1

SAMPLE DEPTH: 1.5 to 2.5

LABORATORY NO.:


LIQUID LIMIT:

PLASTIC LIMIT:

PLASTICITY INDEX:

CLASSIFICATION:

ASTM SOIL DESCRIPTION:



Sample inundated at end of test at 3200 psf

**SPEEDIE**  
AND ASSOCIATES

# CONSOLIDATION TEST

PROJECT: Mensendick School-Building Distress

PROJECT NO.: 161211SA

LOCATION: 5535 North 67th Avenue

DATE: 7/7/16

BORING NO.: C-1

SAMPLE NO.: RS-2

SAMPLE DEPTH: 2.5 to 3.5

LABORATORY NO.:

LIQUID LIMIT:

26

PLASTIC LIMIT:

16

PLASTICITY INDEX:


10

CLASSIFICATION:

CL

ASTM SOIL DESCRIPTION:

SANDY LEAN CLAY



Sample inundated at end of test at 3200 psf

**SPEEDIE**  
AND ASSOCIATES



# CONSOLIDATION TEST

PROJECT: Mensendick School-Building Distress

PROJECT NO.: 161211SA

LOCATION: 5535 North 67th Avenue

DATE: 7/7/16

BORING NO.: C-2

SAMPLE NO.: RS-1

SAMPLE DEPTH: 1.5 to 2.5

LABORATORY NO.:


LIQUID LIMIT:

PLASTIC LIMIT:

PLASTICITY INDEX:

CLASSIFICATION:

ASTM SOIL DESCRIPTION:



Sample Inundated at end of test at 3200 psf

**SPEEDIE  
AND ASSOCIATES**

# CONSOLIDATION TEST

PROJECT: Mensendick School-Building Distress

PROJECT NO.: 161211SA

LOCATION: 5535 North 67th Avenue

DATE: 7/7/16

BORING NO.: C-2

SAMPLE NO.: RS-2

SAMPLE DEPTH: 2.6 to 3.5

LABORATORY NO.:


LIQUID LIMIT:

PLASTIC LIMIT:

PLASTICITY INDEX:

CLASSIFICATION:

ASTM SOIL DESCRIPTION:



**SPEEDIE  
AND ASSOCIATES**





Glendale Elementary School District SFB Projects: Construction Cost Estimates

BRG:                                      Project:                                      Scope: Updated 9/1/16                                      Cost Estimate:

070440106-9999-011-BRG	Mensendick Drainage		
	Phase2	Chasse Estimate	\$ 250,133.25
		Estimated Phase 2 Subtotal	\$ 250,133.25
		Estimated Total Repair:	\$ 250,133.25



GENERAL NOTES FOR CONSTRUCTION:

- A. ALL CONSTRUCTION SHALL CONFORM TO THE LATEST MAG STANDARD DETAILS AND SPECIFICATIONS AND THE CITY'S CURRENT ENGINEERING DESIGN AND CONSTRUCTION STANDARDS.
- B. THIS SET OF PLANS HAS BEEN REVIEWED FOR COMPLIANCE WITH CITY REQUIREMENTS PRIOR TO ISSUANCE OF CONSTRUCTION PERMITS. HOWEVER, SUCH REVIEW AND ACCEPTANCE SHALL NOT PREVENT THE CITY FROM REQUIRING CORRECTION OF ERRORS IN SAID PLANS AND/OR CONSTRUCTION WHEN IN VIOLATION OF ANY LAWS, ORDINANCES, CODES OR STANDARDS THAT ARE IN EFFECT. REVIEW AND ACCEPTANCE OF PLANS DOES NOT RELEASE A DEVELOPER OR ENGINEER FROM RESPONSIBILITY FOR ERRORS OR OMISSIONS ON SAID PLANS.
- C. THE CITY DOES NOT WARRANT ANY QUANTITIES SHOWN ON THESE PLANS.
- D. THE CITY PLANS ACCEPTANCE IS FOR GENERAL LAYOUT IN THE RIGHT-OF-WAY ONLY. THIS ACCEPTANCE IS VALID FOR A PERIOD OF SIX MONTHS. CONSTRUCTION PERMITS SHALL BE OBTAINED DURING THIS PERIOD OR THE PLANS SHALL BE RESUBMITTED FOR REVIEW.
- E. A CITY ACCEPTED SET OF PLANS SHALL BE AVAILABLE ON THE JOB SITE AT ALL TIMES.
- F. THE CITY SHALL BE NOTIFIED 48 HOURS PRIOR TO ANY CONSTRUCTION WORK. CONSTRUCTION WORK CONCEALED WITHOUT INSPECTION BY THE CITY SHALL BE SUBJECT TO EXPOSURE AT THE CONTRACTOR'S EXPENSE.
- G. A RIGHT-OF-WAY CONSTRUCTION PERMIT IS REQUIRED FOR ALL WORK WITHIN THE PUBLIC RIGHT-OF-WAY OR WITHIN A CITY EASEMENT. A 100% PERFORMANCE BOND OR EQUIVALENT FORM OF FINANCIAL SURETY MAY BE REQUIRED FOR ALL WORK WITHIN THE RIGHT-OF-WAY PRIOR TO THE ISSUANCE OF ANY RIGHT-OF-WAY CONSTRUCTION PERMIT(S). ALL WORK WITHIN THE RIGHT-OF-WAY SHALL BE INSPECTED AND APPROVED BY THE CITY'S ENGINEERING DIVISION.
- H. IMPROVEMENTS SHALL NOT BE ACCEPTED UNTIL "AS-BUILT" PLANS AND ELECTRONIC (AUTOCAD) FILES HAVE BEEN SUBMITTED AND APPROVED BY THE CITY.
- I. THE DEVELOPER IS RESPONSIBLE FOR ALL COSTS AND WORK RELATED TO THE REMOVAL, RELOCATION OR ABANDONMENT OF ALL OBSTRUCTIONS AND/OR UTILITIES WITHIN THE RIGHT-OF-WAY THAT CONFLICT WITH THE NEW IMPROVEMENTS.
- J. THE DEVELOPER IS RESPONSIBLE FOR OBTAINING OR DEDICATING ALL REQUIRED RIGHTS-OF-WAY AND EASEMENTS TO THE CITY PRIOR TO ISSUANCE OF THE BUILDING'S CERTIFICATE OF OCCUPANCY.
- K. THE CONTRACTOR SHALL CONTACT BLUE STAKE (602-263-1100) 48 HOURS PRIOR TO CONSTRUCTION.
- L. THE CONTRACTOR SHALL BARRICADE CONSTRUCTION SITES AT ALL TIMES PER THE CITY OF PHOENIX TRAFFIC BARRICADE MANUAL. WHEN REQUIRED BY THE CITY, A TRAFFIC CONTROL PLAN SHALL BE SUBMITTED FOR APPROVAL A MINIMUM OF 72 HOURS IN ADVANCE OF CONSTRUCTION.
- M. THE CONTRACTOR MAY OBTAIN A FIRE HYDRANT METER FOR CONSTRUCTION WATER FROM THE CITY WATER SERVICES DEPARTMENT. THE UNLAWFUL REMOVAL OF WATER FROM A FIRE HYDRANT IS A VIOLATION OF THE MUNICIPAL CODE, PUNISHABLE BY FINE AND/OR IMPRISONMENT.
- N. DAMAGE CAUSED BY THE DEVELOPER DURING CONSTRUCTION TO CITY INFRASTRUCTURE OR FACILITIES SHALL BE REPAIRED OR REPLACED BY THE DEVELOPER, AT HIS EXPENSE, IN A MANNER ACCEPTABLE TO THE CITY.
- O. THERE SHALL BE NO DIRT RAMPS OVER SIDEWALKS DURING CONSTRUCTION.
- P. AN AZPDES PERMIT IS REQUIRED FOR ALL CONSTRUCTION THAT DISTURBS LAND OVER ONE (1) ACRE IN SIZE. PRIOR TO START OF ANY CONSTRUCTION, THE CONTRACTOR SHALL SUBMIT A NOTICE OF INTENT (NOI) TO THE ARIZONA DEPARTMENT OF ENVIRONMENTAL QUALITY (ADEQ) AND A COPY TO THE CITY OF GLENDALE AND HAVE A COPY OF THE SWPPP ON SITE AT ALL TIMES.

NOTE:

THESE DRAWINGS ARE AN INSTRUMENT OF SERVICE ONLY AND ARE AND SHALL REMAIN THE EXCLUSIVE PROPERTY OF HESS-ROUNTREE, INC. NO REPRODUCTION OR OTHER USE SHALL BE MADE BY ANY PERSON OR FIRM OTHER THAN HESS-ROUNTREE, INC. OR THE CITY OF PHOENIX WITHOUT EXPRESS PERMISSION OF HESS-ROUNTREE, INC. ANY UNAUTHORIZED USE SHALL VOID THE ENGINEER'S SEAL AND SIGNATURE HEREON AND NO PROFESSIONAL RESPONSIBILITY WILL REMAIN.

THESE PLANS HAVE BEEN SUBMITTED TO THE FOLLOWING UTILITY COMPANIES AND THE WORK CONTAINED IN THESE PLANS HAS BEEN APPROVED BY THESE COMPANIES WITHIN THEIR AREA OF INTEREST. THE SIZE AND LOCATIONS, AS SHOWN OF THE GAS, TELEPHONE AND POWER LINES, AND CONNECTIONS AGREE WITH THE INFORMATION CONTAINED IN THE UTILITY COMPANY'S RECORDS. WHERE THE WORK TO BE DONE CONFLICTS WITH ANY OF THESE UTILITIES, THE CONFLICTS WILL BE RESOLVED AS SPECIFIED IN THE SPECIAL PROVISIONS AND/OR AS OTHERWISE NOTED ON THESE PLANS. CONFLICTS ARISING DURING THE COURSE OF CONSTRUCTION FROM UNFORSEEN CIRCUMSTANCES SHALL BE REPORTED TO THE INTERESTED UTILITY COMPANY AND BE RESOLVED BY THEM AND THE DESIGN ENGINEER.

SPRINT COMMUNICATIONS	COLIN SWORD	DATE SUBMITTED
COX COMMUNICATIONS	TMC-DV2-01	DATE SUBMITTED
SALT RIVER PROJECT DISTRICT	BECKY THOMAS	DATE SUBMITTED
S R V W U A	SUSANA ORTEGA	DATE SUBMITTED
ARIZONA PUBLIC SERVICE	VIRGINIA NISKALA	DATE SUBMITTED
QWEST COMMUNICATIONS	CONFLICT LIAISON DEPT.	DATE SUBMITTED
EL PASO NATURAL GAS COMPANY	DENNIS SEGARS	DATE SUBMITTED
KINDER MORGAN	D. TARANGO	DATE SUBMITTED
SOUTHWEST GAS CORPORATION	FRANCHISE DEPT. 420-586	DATE SUBMITTED

ACREAGE

GROSS SITE AREA	= 25.57 ACRES
NET SITE AREA	= 24.67 ACRES
CONSTRUCTION AREA	= 0.16 ACRES

GENERAL NOTES FOR GRADING AND DRAINAGE CONSTRUCTION:

- A. THE DEVELOPER/CONTRACTOR IS RESPONSIBLE FOR PAYING PERMIT FEES PRIOR TO CONSTRUCTION.
- B. A SEPARATE PERMIT IS NECESSARY FOR ANY CONSTRUCTION IN THE RIGHT-OF-WAY.
- C. PRIOR TO THE START OF ANY ON-SITE GRADING OPERATIONS, THE CONTRACTOR SHALL NOTIFY THE CITY ENGINEERING DIVISION AT LEAST 48 HOURS PRIOR TO COMMENCING WORK BY CALLING 623-930-3630.
- D. STAKING PAD AND/OR FINISHED FLOOR ELEVATIONS ARE THE RESPONSIBILITY OF THE DEVELOPER OR HIS ENGINEER. IN NON-CRITICAL AREAS, THE DEVELOPER'S ENGINEER SHALL SUBMIT CERTIFICATIONS OF CONSTRUCTED BUILDING PAD ELEVATIONS PRIOR TO THE CITY'S ACCEPTANCE OF PROJECT. IN A CRITICAL DRAINAGE AREA, CERTIFICATION OF THE FINISHED BUILDING FLOOR OR STEM WALL ELEVATION SHALL BE SUBMITTED AND APPROVED PRIOR TO ANY VERTICAL CONSTRUCTION.
- E. AN APPROVED GRADING AND DRAINAGE PLAN SHALL BE ON THE JOB SITE AT ALL TIMES. DEVIATIONS FROM THE PLAN MUST BE PRECEDED BY AN APPROVED PLAN REVISION.
- F. ACCEPTANCE OF GRADING AND DRAINAGE IMPROVEMENTS SHALL INCLUDE, BUT NOT BE LIMITED TO, THE CONSTRUCTION OF RETENTION BASINS, CATCH BASINS, CURB FOR OTHER DRAINAGE FACILITIES, SITE GRADING, DRYWELLS, STORM DRAIN PIPES, UNDERGROUND STORAGE TANKS AND ASPHALT PAVEMENT.
- G. DRYWELLS MUST BE DRILLED A MINIMUM OF 10 FEET INTO PERMEABLE POROUS STRATA.
- H. THE CONTRACTOR SHALL CONSTRUCT ALL RETENTION BASINS TO THE ELEVATIONS AND SLOPES SHOWN ON THE PLANS.
- I. THE CONTRACTOR IS RESPONSIBLE FOR LOCATING AND CONFIRMING DEPTH OF ALL THE EXISTING UTILITY LINES WITHIN PROPOSED RETENTION BASIN AREAS. IF THE BASIN CANNOT BE CONSTRUCTED PER PLAN AS A RESULT OF CONFLICT WITH UNDERGROUND UTILITIES, THE CONTRACTOR SHOULD CONTACT THE CITY AND DESIGN ENGINEER AND REQUEST MODIFICATION OF THE BASIN DESIGN.
- J. THIS SET OF PLANS HAS BEEN REVIEWED FOR COMPLIANCE WITH CITY REQUIREMENTS PRIOR TO ISSUANCE OF CONSTRUCTION PERMITS AND SHALL BE KEPT AT THE CONSTRUCTION SITE. SUCH REVIEW SHALL NOT PREVENT THE CITY FROM REQUIRING CORRECTIONS TO ERRORS ON THE PLANS, WHICH ARE FOUND TO BE IN VIOLATION OF ANY LAW OR ORDINANCE.
- K. NO PERSON SHALL USE ANY MECHANICAL EQUIPMENT FOR CLEARING, GRUBBING, ROAD CONSTRUCTION, TRENCHING, EXCAVATING, DEMOLITION OR ENGAGE IN ANY EARTHMOVING ACTIVITY WITHOUT FIRST OBTAINING A DUST CONTROL PERMIT FROM MARICOPA COUNTY DEPARTMENT OF ENVIRONMENTAL SERVICES.

GRADING & DRAINAGE PERMIT FEE

BASE FEE	1 EA
ON-SITE PAVING	0 SY
CATCH BASIN/SCUPPER	1 EA
MANHOLE/DRYWELL	1 EA
STORM DRAIN PIPE (12"+)	350 LF

UTILITY UNDERGROUND STATEMENT:

"PURSUANT TO CHAPTER 32.5 OF THE GLENDALE CITY CODE, ALL NEW AND EXISTING UTILITIES WITHIN OR CONTIGUOUS TO THIS STATE SHALL BE PLACED UNDERGROUND IN CONDUIT."

DRAINAGE CORRECTIONS

AT


DON MENSENDICK MIDDLE SCHOOL

SITE ADDRESS: 5535 NORTH 67TH AVENUE  
GLENDALE, ARIZONA 85301


FOR

GLENDALE ELEMENTARY SCHOOL DISTRICT NO. 40 (OWNER)

7301 N. 58TH AVENUE  
GLENDALE, ARIZONA 85303  
PHONE: (623) 842-8100  
CONTACT: GREG GILLIAM



VICINITY MAP  
NOT TO SCALE



SHEET INDEX MAP  
NOT TO SCALE

OWNER/DEVELOPER:

GLENDALE ELEMENTARY SCHOOL DISTRICT NO. 40  
7301 NORTH 58TH AVENUE  
GLENDALE, ARIZONA 85303  
PHONE: (623) 842-8100  
CONTACT: DEAN WALLACE

ENGINEER:

HESS-ROUNTREE, INC.  
9831 S. 51ST STREET, SUITE C110  
PHOENIX, ARIZONA 85044  
PHONE: (480) 496-0244  
FAX: (480) 496-0094  
CONTACT: PERCY MYRON JR., P.E.

SHEET INDEX:

- C-1 COVER SHEET  
C-2 DETAIL SHEET  
C-3 GRADING AND DRAINAGE PLAN

PLANS ACCEPTANCE

THE CITY OF GLENDALE ACCEPTS THESE PLANS FOR CONSTRUCTION, AS BEING IN GENERAL COMPLIANCE WITH PLAN PREPARATION REQUIREMENTS OF THE CITY. RESPONSIBILITY FOR THE COMPLETENESS AND ACCURACY OF THE PLANS AND RELATED DESIGNS RESIDES WITH THE ENGINEER AND THE ENGINEERING FIRM OF RECORD.

LAND DEVELOPMENT ENGINEER \_\_\_\_\_ DATE \_\_\_\_\_

TRANSPORTATION ENGINEER \_\_\_\_\_ DATE \_\_\_\_\_

RECORD DRAWING

I CERTIFY THAT THE LOCATIONS, ELEVATIONS, DEPTHS, AND RECORD DRAWING COMMENTS ACCURATELY REFLECT THE EXISTING FIELD CONDITIONS AND MATERIALS ACTUALLY USED DURING CONSTRUCTION. THIS CERTIFICATION IS BASED ON INFORMATION OBTAINED UNDER BY DIRECT SUPERVISION AND IS CORRECT AND COMPLETE TO THE BEST OF MY KNOWLEDGE AND BELIEF.

NAME \_\_\_\_\_ DATE \_\_\_\_\_

REGISTRATION NO. \_\_\_\_\_ EXP. DATE \_\_\_\_\_

REVD BY: \_\_\_\_\_ ENGINEERING DEPARTMENT

DRYWELL CERTIFICATION

I CERTIFY THAT ALL DRYWELLS HAVE BEEN REGISTERED WITH AND CONFORM TO ALL REQUIREMENTS OF THE ARIZONA DEPARTMENT OF ENVIRONMENTAL QUALITY (ADEQ).

NAME \_\_\_\_\_ DATE \_\_\_\_\_

COMPANY \_\_\_\_\_

ARIZONA PUBLIC SERVICE-ELECTRICAL  
SOUTHWEST GAS CORPORATION - GAS  
SALT RIVER PROJECT - IRRIGATION SALT  
RIVER PROJECT - ELECTRICAL QWEST  
COMMUNICATIONS - CABLE TV (OTHER)  
\*\*AGENCIES ALSO REQUIRING PERMITS WHEN  
INVOLVED ARE: MARICOPA COUNTY  
HIGHWAY DEPT., A.D.O.T., CITY OF PHOENIX,  
CITY OF PEORIA, SANTA FE RAILROAD, EL  
PASO NATURAL GAS, & MARICOPA COUNTY  
FLOOD CONTROL DISTRICT.

PLANS SUBMITTED TO (NAME)	PLANS REVIEWED BY (NAME)	PERMIT RECEIVED DATE



HESS - ROUNTREE, INC.

CONSULTING ENGINEERS & LAND SURVEYORS

9831 SOUTH 51ST STREET, SUITE C110  
PHOENIX, ARIZONA 85044 (480)496-0244

DES. **PMJ** DRN. **JCW** CKD. **PMJ** JOB NO. **1512-02**

DESIGN CIVIL ENGINEER'S  
NOTES TO CONTRACTOR:

- NOTHING CONTAINED IN THE CONTRACT DOCUMENTS SHALL CREATE, NOR SHALL BE CONSTRUED TO CREATE, ANY CONTRACTUAL RELATIONSHIP BETWEEN THE DESIGN CIVIL ENGINEER AND THE CONTRACTOR OR ANY SUBCONTRACTOR.
- THE DESIGN CIVIL ENGINEER WILL NOT BE RESPONSIBLE FOR CONSTRUCTION MEANS, METHODS, TECHNIQUES, SEQUENCES OR PROCEDURES OR FOR SAFETY PRECAUTIONS OR PROGRAMS UTILIZED IN CONNECTION WITH THE WORK. THESE ARE SOLELY THE CONTRACTOR'S RESPONSIBILITY. THE DESIGN CIVIL ENGINEER WILL NOT BE RESPONSIBLE FOR THE CONTRACTOR'S FAILURE TO CARRY OUT THE WORK IN ACCORDANCE WITH THE CONTRACT DOCUMENTS.
- THE CONTRACTOR SHALL PROVIDE ADEQUATE MEANS OF CLEANING TRUCKS AND/OR OTHER EQUIPMENT OF MUD PRIOR TO ENTERING PUBLIC STREETS, AND IT IS THE CONTRACTOR'S RESPONSIBILITY TO CLEAN STREETS, ALLAY DUST, AND TO TAKE WHATEVER MEASURES ARE NECESSARY TO INSURE THAT ALL ROADWAYS AND ON SITE PARKING LOTS/FIRE LANES ARE MAINTAINED IN A CLEAN, MUD AND DUST-FREE CONDITION AT ALL TIMES.
- IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO CONTACT THE BLUE STAKE CENTER TWO WORKING DAYS PRIOR TO ANY EXCAVATION. THE UNDERGROUND UTILITY LOCATIONS AS SHOWN HEREON ARE BASED ON THE BEST INFORMATION AVAILABLE FROM UTILITY RECORDS AND OTHER DATA AS SUPPLIED TO THIS DESIGN CIVIL ENGINEER. THERE MAY BE OTHER UNDERGROUND UTILITY LINES, SERVICE LINES AND STRUCTURES PRESENT IN THE SUBJECT AREA. CONTRACTOR SHALL INCLUDE IN HIS BID THE COST OF HIRING AN UNDERGROUND UTILITY LOCATING SERVICE FOR THE PURPOSE OF LOCATING ALL UNDERGROUND UTILITIES. CONTRACTOR WILL COORDINATE WITH THE OWNER AND ARCHITECT TO DETERMINE WHETHER SAID UTILITIES ARE TO BE ABANDONED OR PROTECTED FROM DAMAGE.
- THE DESIGN CIVIL ENGINEER MAKES NO REPRESENTATION OR GUARANTEE REGARDING THE EARTHWORK QUANTITIES OR THAT THE EARTHWORK FOR THIS PROJECT WILL BALANCE DUE TO THE VARYING FIELD CONDITIONS, CHANGING, SOIL TYPES, ALLOWABLE CONSTRUCTION TOLERANCES AND CONSTRUCTION METHODS. PRIOR TO BIDDING THE WORK, THE CONTRACTOR SHALL THOROUGHLY SATISFY HIMSELF AS TO THE ACTUAL CONDITIONS, EARTHWORK QUANTITIES AND REQUIREMENTS OF THE WORK AND EXCESS OR DEFICIENCY THEREIN, ACTUAL OR RELATIVE.
- THE CONTRACTOR SHALL ADJUST ALL EXISTING AND NEW CLEANOUTS, WATER VALVE BOXES, MANHOLES, GAS VALVE BOXES, IRRIGATION BOXES, ETC. IN THE CONSTRUCTION AREA TO FINISH GRADE PER THE APPLICABLE MAG STANDARD DETAIL. ALL VALVE BOXES, MANHOLES, ETC. IN CONCRETE PAVEMENT AREAS SHALL BE ISOLATED FROM THE CONCRETE PAVEMENT WITH EXPANSION JOINTS.
- ALL NEW UNDERGROUND FACILITIES/UTILITIES SHALL BE INSTALLED WITH A DETECTABLE UNDERGROUND LOCATION DEVICE. INSTALL A #18 INSULATED TRACER WIRE SECURELY ATTACHED TO EACH UTILITY AT 8'-FEET ON CENTER. 12" OF TRACER WIRE SHALL BE ACCESSIBLE ABOVE GRADE AT THE TERMINATION AND SHALL BE SECURELY ATTACHED AT THAT POINT. THE CONTRACTOR SHALL INCLUDE ALL COSTS ASSOCIATED WITH THIS REQUIREMENT IN THEIR BID.
- THE CONTRACTOR SHALL MAKE NO CLAIMS AGAINST THE OWNER OR THE DESIGN CIVIL ENGINEER REGARDING ALLEGED INACCURACY OF CONSTRUCTION STAKES SET BY THE DESIGN CIVIL ENGINEER UNLESS ALL SURVEY STAKES SET BY THE DESIGN CIVIL ENGINEER ARE MAINTAINED INTACT AND CANNOT BE VERIFIED AS TO THEIR ORIGIN, ANY REMEDIAL WORK REQUIRED TO CORRECT ANY ITEM OF IMPROPER CONSTRUCTION WORK IN THIS DEVELOPMENT SHALL BE PERFORMED AT THE SOLE EXPENSE OF THE RESPONSIBLE CONTRACTOR OR SUBCONTRACTOR.

BENCH MARK:

MCDOT BENCHMARK 23041-1. TOP OF 3" GLENDALE BRASS CAP IN HANDHOLE, DOWN 0.5', STAMPED "N397" LOCATED AT THE INTERSECTION OF 67TH AVENUE AND MISSOURI AVENUE.

ELEVATION = 1117.340 (NAVD88 DATUM)

CERTIFICATION:

"I HEREBY CERTIFY THAT THIS DESIGN IS BASED ON A SITE VISIT OR ACCURATE FIELD DATA WHICH HAS BEEN CHECKED IN THE FIELD WITHIN 180 DAYS PRIOR TO SUBMISSION FOR CITY APPROVAL.

BY: *[Signature]* DATE: *8/10/16*

COVER SHEET

GLENDALE ELEMENTARY SCHOOL DISTRICT NO. 40

DRAINAGE CORRECTIONS AT  
DON MENSENDICK ELEMENTARY SCHOOL

DRAWING STATUS	SHEET	OF	
1ST CITY SUBMITTAL			
	1	3	C-1
DATE:	08-10-16		






The MaxWell™ Plus Drainage System Detail And Specifications


NOTE:

1. CONTRACTORS TO REGISTER ALL DRYWELLS WITH ADEQ.
2. INSTALL 8" WIDE BY 8" DEEP CONCRETE COLLARS AROUND GRATES, MAG CLASS B.




ITEM NUMBERS

1. **MANHOLE CONE** - MODIFIED FLAT BOTTOM.
2. **STABILIZED BACKFILL** - COMPACTED NATIVE IN LANDSCAPED AREAS, 1 SACK SLURRY IN PAVEMENT.
3. **BOLTED RING & GRATE/COVER** - DIAMETER AS SHOWN. CLEAN CAST IRON WITH WORDING "STORM WATER ONLY" IN RAISED LETTERS. BOLTED IN 2 LOCATIONS AND SECURED TO CONE WITH MORTAR. RIM ELEVATION ±0.02' OF PLANS.
4. **GRADED BASIN OR PAVING** (BY OTHERS).
5. **COMPACTED BASE MATERIAL** (BY OTHERS).
6. **PUREFLO™ DEBRIS SHIELD** - ROLLED 16 GA. STEEL X 24" LENGTH WITH VENTED ANTI-SIPHON AND INTERNAL .285" MAX. S.WO FLATTENED EXPANDED STEEL SCREEN X 12" LENGTH. FUSION BONDED EPOXY COATED.
7. **PRE-CAST LINER** - 4000 PSI CONCRETE 48" ID. X 54" OD. CENTER IN HOLE AND ALIGN SECTIONS TO MAXIMIZE BEARING SURFACE.
8. **MIN. 6" Ø DRILLED SHAFT.**
9. **SUPPORT BRACKET** - FORMED 12 GA. STEEL. FUSION BONDED EPOXY COATED.
10. **OVERFLOW PIPE** - SCH. 40 PVC MATED TO DRAINAGE PIPE AT BASE SEAL.
11. **DRAINAGE PIPE** - ADS HIGHWAY GRADE WITH TRI-A COUPLER. SUSPEND PIPE DURING BACKFILL OPERATIONS TO PREVENT BUCKLING OR BREAKAGE. DIAMETER AS NOTED.
12. **BASE SEAL** - GEOTEXTILE, POLY LINER OR CONCRETE SLURRY.
13. **ROCK** - CLEAN AND WASHED, SIZED BETWEEN 3/8" AND 1-1/2" TO BEST COMPLEMENT SOIL CONDITIONS.
14. **FLOFAST™ DRAINAGE SCREEN** - SCH. 40 PVC 0.120" SLOTTED WELL SCREEN WITH 32 SLOTS PER ROW/FT. DIAMETER VARIES 96" OVERALL LENGTH WITH TRI-B COUPLER.
15. **MIN. 4" Ø SHAFT** - DRILLED TO MAINTAIN PERMEABILITY OF DRAINAGE SOILS.
16. **FABRIC SEAL** - U.V. RESISTANT GEOTEXTILE - TO BE REMOVED BY CUSTOMER AT PROJECT COMPLETION.
17. **ABSORBENT** - HYDROPHOBIC PETROCHEMICAL SPONGE. MIN. 128 OZ. CAPACITY.
18. **CONNECTOR PIPE** - 6" Ø SCH. 40 PVC.
19. **VENTED ANTI-SIPHON INTAKE** WITH FLOW REGULATOR.
20. **INTAKE SCREEN** - SCH. 40 PVC 0.120" MODIFIED SLOTTED WELL SCREEN WITH 32 SLOTS PER ROW/FT. 48" OVERALL LENGTH WITH TRI-C END CAP.
21. **FREEBOARD DEPTH VARIES** WITH INLET PIPE ELEVATION. INCREASE PRIMARY/SECONDARY SETTLING CHAMBER DEPTHS AS NEEDED TO MAINTAIN ALL INLET PIPE ELEVATIONS ABOVE CONNECTOR PIPE OVERFLOW.
22. **OPTIONAL INLET PIPE** (BY OTHERS).
23. **MOISTURE MEMBRANE** - 6 MIL. PLASTIC. PLACE SECURELY AGAINST ECCENTRIC CONE AND HOLE SIDEWALL. USED IN LIEU OF SLURRY IN LANDSCAPED AREAS.





TRENCH DRAIN DETAIL  
NOT TO SCALE



INSTALL 2 LAYERS OF MIRAFI 100X FABRIC BENEATH GRATE. GENERAL CONTRACTOR TO REMOVE AFTER CONSTRUCTION IS COMPLETE.

AREA DRAIN  
NOT TO SCALE



HESS - ROUNTREE, INC.  
CONSULTING ENGINEERS & LAND SURVEYORS  
9831 SOUTH 51ST STREET, SUITE C110  
PHOENIX, ARIZONA 85044 (480)496-0244

DES. **PMJ** DRN. **JCW** CKD. **PMJ** JOB NO. **1512-02**

LEGEND

- ×BC 1119.13 EXISTING BACK OF CURB ELEVATION
- ×G 1118.66 EXISTING GUTTER ELEVATION
- ×C 1119.43 EXISTING CONCRETE ELEVATION
- ×SW 1119.62 EXISTING SIDEWALK ELEVATION
- ×NG 1119.14 EXISTING NATURAL GROUND ELEVATION
- ×TB 1120.35 EXISTING TOP OF BERM ELEVATION
- ×TS 1118.07 EXISTING TOE OF SLOPE ELEVATION
- ×DG 1119.28 EXISTING DECOMPOSED GRANITE ELEVATION
- ×FL 1120.87 EXISTING FLOWLINE ELEVATION
- ×FF 1120.46 EXISTING FINISH FLOOR ELEVATION
- ⊗ ICV EXISTING IRRIGATION CONTROL VALVE
- ⊗ CLM EXISTING COLUMN
- RD EXISTING ROOF DRAIN
- DF EXISTING DRINKING FOUNTAIN
- ⊗ PV EXISTING PASTURE VALVE
- ⊗ WV EXISTING WATER VALVE
- SSCO EXISTING SANITARY SEWER CLEANOUT
- EV EXISTING ELECTRIC VAULT
- CV EXISTING COMMUNICATION VAULT
- ⊗ BCAP EXISTING BRASS CAP
- BLDR. EXISTING BOULDER
- DW RIM=1119.01 EXISTING DRYWELL
- CB RIM=1118.91 EXISTING CATCH BASIN
- SSMH RIM=1119.42 EXISTING SANITARY SEWER MANHOLE
- BB RIM=1118.68 EXISTING BUBBLER BOX
- ⊗ EXISTING CACTI
- TREE EXISTING TREE

- SAWCUT, REMOVE AND REPLACE EXISTING CONCRETE SIDEWALK (MAG S.D. NO. 230).
- SAWCUT, REMOVE AND REPLACE EXISTING CONCRETE FIRE LANE.

DETAIL SHEET

GLENDALE ELEMENTARY SCHOOL DISTRICT NO. 40



DRAINAGE CORRECTIONS AT  
DON MENSENDICK ELEMENTARY SCHOOL

DRAWING STATUS	SHEET	OF	
1ST CITY SUBMITTAL			
	2	3	C-2
DATE:	08-10-16		



151202071.DWG







**HESS - ROUNTREE, INC.**  
CONSULTING ENGINEERS & LAND SURVEYORS  
9831 SOUTH 51ST STREET, SUITE C110  
PHOENIX, ARIZONA 85044 (480)496-0244

DES. **PMJ** DRN. **JCW** CKD. **PMJ** JOB NO. **1512-02**

**CONSTRUCTION NOTE:**

- 1 SAWCUT, REMOVE AND REPLACE EXISTING CONCRETE SIDEWALK TO THE NEAREST JOINT (MAG STANDARD DETAIL NO. 230).
- 2 CONSTRUCT TRENCH DRAIN (SEE DETAIL ON SHEET C-2).
- 3 INSTALL 6" HIGH DENSITY POLYETHYLENE PIPE WITH SMOOTH INTERIOR AND 10.8 P.S.I. JOINTS.
- 4 CONNECT NEW STORM DRAIN PIPE TO EXISTING STORM DRAIN PIPE WITH NECESSARY AND APPROPRIATE FITTINGS. FIELD VERIFY ELEVATION OF EXISTING STORM DRAIN LINE PRIOR TO CONSTRUCTION.
- 5 INSTALL 6" VERTICAL PIPE CONNECTION AT END OF TRENCH DRAIN. INSTALL 6" HIGH DENSITY POLYETHYLENE PIPE WITH SMOOTH INTERIOR AND 10.8 P.S.I. JOINTS VERTICALLY DOWN TO 6"-90 DEGREE BEND. INVERT SHOWN ON PLAN IS AT 6"-90 DEGREE BEND.
- 6 HYDROVAC AND CLEANOUT EXISTING AREA DRAINS, STORM DRAIN PIPING, DRYWELL AND BUBBLER BOX.
- 7 INSTALL AREA DRAIN (SEE DETAIL ON SHEET C-2).
- 8 CONNECT TO EXISTING DRYWELL OR BUBBLER BOX WITH A WATERTIGHT CONNECTION.
- 9 INSTALL 8" HIGH DENSITY POLYETHYLENE PIPE WITH SMOOTH INTERIOR AND 10.8 P.S.I. JOINTS.
- 10 REPAIR/REPLACE DAMAGED LANDSCAPING AND GRANITE DISTURBED BY STORM DRAIN INSTALLATION. INSTALL SOD IN TURF AREAS.
- 11 CONSTRUCT CATCH BASIN (MAG STANDARD DETAIL 537).
- 12 CONSTRUCT DUAL CHAMBER DRYWELL (SEE DETAIL ON SHEET C-2).
- 13 SAWCUT, REMOVE AND REPLACE EXISTING CONCRETE FIRE LANE TO THE NEAREST JOINT. REPLACE WITH 7" THICK MAG AA CONCRETE.
- 14 SAWCUT AND REMOVE EXISTING CONCRETE SIDEWALK AS REQUIRED TO INSTALL TRENCH DRAIN.
- 15 INSTALL 8" TO 6" REDUCER AT THE HORIZONTAL END OF THE 6"-90° BEND.
- 16 INSTALL 12" HIGH DENSITY POLYETHYLENE PIPE WITH SMOOTH INTERIOR AND 10.8 P.S.I. JOINTS.
- 17 FIELD VERIFY ELEVATION AND LOCATION OF EXISTING ELECTRICAL, COMMUNICATION, WATER AND SEWER LINES. PROTECT FROM DAMAGE.
- 18 REMOVE EXISTING TREE.
- 19 GRADE PLANTER TO DRAIN TO RIM ELEVATION OF AREA DRAIN. REPLACE GRANITE WITH A 2" THICKNESS OF DECOMPOSED GRANITE (1/4" MINUS MADISON GOLD).
- 20 REMOVE EXISTING CONCRETE SLAB. INSTALL SOD AND FILL IN VOID WITH CLEAN TOPSOIL.
- 21 EXISTING WROUGHT IRON FENCE. PROTECT FROM DAMAGE.
- 22 REMOVE AND REINSTALL GARDEN PLANTER BOXES AND PLANTS IN KIND. REPAIR/REPLACE ENTIRE DRIP IRRIGATION SYSTEM DAMAGE/REMOVE FOR INSTALLATION OF STORM DRAIN PIPE. AT COMPLETION OF PROJECT, THE DROP IRRIGATION SHALL BE IN 100% COMPLETE WORKING ORDER.





SCALE: 1"=20'

**GRADING AND DRAINAGE PLANS**


**GLENDALE ELEMENTARY SCHOOL DISTRICT NO. 40**

**DRAINAGE CORRECTIONS AT  
DON MENSENDICK ELEMENTARY SCHOOL**

DRAWING STATUS	SHEET	OF	
1ST CITY SUBMITTAL			
DATE: 08-10-16	3	3	C-3







## SECTION 02 21 13

### CONSTRUCTION STAKING


Construction staking shall be performed by a licensed Surveyor acceptable to the Architect. Staking will be paid from the Construction Staking Allowance in the Contract.

Stakes: A minimum one set of construction grade stakes or "blue-tops" if possible of the following kind and at the stated interval shall be set. Blue-tops shall be set for all finish grading, sidewalk, curbing, concrete valley gutters, paving subgrade and A.B.C. and shall be left in place until checked and certified by the Civil Engineer.

1. Field staking control.
2. Two site benchmarks.
3. Mark out demo/sawcuts.
4. Rough grading cut and fill for onsite: at 50-foot intervals and grade breaks.
5. Concrete sidewalk: line and grade at 25-foot intervals and grade breaks.
6. Storm drain: 25-foot intervals and grade breaks.
7. As-builts finish grade.
8. Storm drain area drains/catch basins: location and elevation.
9. Prepare and submit as-built drawings to Contractor for submittal.
10. Office computer calculation for above staking.

**END OF SECTION**

**SECTION 31 01 00**  
**EARTHWORK**



**PART 1 GENERAL**

**1.01 SUMMARY**

- A. Section Includes: Perform earthwork as shown on the Drawing and as specified herein.

**1.02 QUALITY ASSURANCE**

- A. Regulatory Requirements: Procure necessary permits or certificates required by City of Phoenix, State of Arizona and Maricopa County. Comply with applicable federal, state and local ordinances, including MAG Standard Specifications and Details. Owner to pay for permits.
- B. Layout of all Work under this Section shall be made by a licensed Engineer/Surveyor acceptable to the Architect.
- C. General Contractor shall give the Work his personal supervision. In his absence, he shall leave a responsible representative in charge who shall have the authority to receive and execute orders from the Architect and/or his representative.

**1.03 PROJECT/SITE CONDITIONS**

- A. Environmental Requirements: No fill materials shall be placed, spread or rolled during unfavorable weather conditions. When the Work is interrupted by rain, fill operations shall not be resumed until it can be shown to the Civil Engineers/Architect's satisfaction that the moisture content and density of the previously placed fill are as specified.
- B. Visit the site. Examine and note conditions as to the character and extent of Work involved.

**PART 2 PRODUCTS**

**2.01 FILL**

- A. Cleaned onsite soils may be used for fills in all areas of the site.
- B. Fill materials shall be approved by the Geotechnical Engineer and Civil Engineer and shall have low swell potential and be free of organic or deleterious material.
- C. Imported fill of low or non-expansive soils shall conform with the following requirements:

Maximum Percent Passing	
No. 200 Sieve	15 percent
Maximum Particle Size	6 inches (1 inch in landscape or turf areas)
Maximum Swell Potential	1.5 percent *
Within exterior concrete slabs	

\*Based on a sample which is remolded to 95% of the ASTM D698 maximum dry density at a moisture content of 2 percent below optimum, placed under a surcharge load of 100 psf and wetted.



## **PART 3 EXECUTION**

### **3.01 PREPARATION**

- A. Existing Utilities:
  - 1. Where existing utilities not shown on the Drawings are encountered, support, shore up, protect same and immediately notify Engineer and General Contractor. Allow entrance, opportunity and ample time for measures necessary for continuance and/or relocation of such services.
  - 2. Where noted on Drawings, cut and cap all street connections encountered in the excavating along curb line and mark location so they can subsequently be located and reconnected as required.
- B. Protection:
  - 1. Keep all excavations, pits, trenches, etc. entirely free from water.
  - 2. Protect excavations from rain or water from any source during construction. Use suitable pumping equipment or other means as required by conditions. Continue pumping as necessary until completion of project or until released by Engineer.
  - 3. Conduct Work in an orderly manner so as not to create a nuisance. Dirt shall not be permitted to accumulate on streets or sidewalks nor to be washed into sewers.
  - 4. During construction operations and after building construction, buildings shall be protected from surface water run-off and drainage from surrounding heights. Run-off water shall be diverted around buildings and construction operations.
- C. Layout:
  - 1. Maintain all bench marks, control monuments and stakes, whether newly established by Surveyor or previously existing. Protect from damage and dislocation. If necessary to disturb existing bench marks, have Surveyor reestablish in a safe place.
  - 2. If any discrepancies are found by Surveyor between the Drawings and actual conditions at the site, Engineer reserves the right to make such minor adjustments in Work specified as necessary to accomplish the intent of the contract Documents, without increased cost to Owner.

### **3.02 EXCAVATABILITY**

- A. The excavatability of site materials is difficult to evaluate based only on the exploration equipment used during the geotechnical design report. Therefore, the Geotechnical Engineer recommends that the Contractor evaluate the excavatability of site materials by performing test excavations with the size and type of equipment that Contractor plans on using at the site.
- B. The near surface and underlying soils can probably be removed with conventional excavating equipment. Deeper excavations may be slower and more difficult to accomplish due to caving and presence of oversized material. Caving should be expected in the non-cohesive granular soils encountered. OSHA requires all excavations over five feet in depth, in which personnel are to enter, be either braced or sloped in accordance with OSHA regulations.

### 3.03 WORKABILITY

- A. Wetting site soils such that moisture contents are at or above optimum could result in some soil pumping under dynamic loadings such as heavy construction equipment driving over the area. In the building area, some pumping is not detrimental to foundation or floor slabs provided the specified percent compaction is achieved. However, in flexible pavement areas where pumping has occurred, and in building areas where severe pumping has damaged subgrade conditions, the area shall be allowed to dry until soils are workable without pumping or the wetted areas removed and replaced with drier site soils.

### 3.04 GRADING

- A. General Contractor shall provide personal supervision for the Work. Leaving a responsible representative in charge, when absent, who shall have the authority to receive and execute instructions from the Architect or his representative.
- B. Grading tolerance shall be +0.00 feet and -0.10 feet.
- C. The following requirements are for site grading under, within and extending five feet beyond the sidewalks, exterior concrete slabs, and concrete fire lanes.
- D. Strip the entire site of all existing fill zones, any backfill zones and any unstable soils. During stripping observe the surface for evidence of buried debris, vegetation or disturbed materials which will require additional removal. If encountered, these materials shall be removed. Areas steeper than 5H to 1V should be benched and any depressions widened to accommodate compaction equipment.
- E. Widen any resulting depressions as necessary to accommodate compaction equipment and provide a level base for placing fill.
- F. Prepare the ground surface in fill areas and in areas cut to grade by scarifying, moisture conditioning and compacting the exposed surface soils to a minimum 10-inch depth. Moisture conditioning and compaction shall meet requirements under Section 3.07, Compaction.
- G. Moisture condition and place engineering fill material required to elevate areas to specified subgrade elevations.
- H. Placing, Spreading and Compacting Fill Materials: Fill materials shall be placed and compacted in horizontal lifts of thickness compatible with the compaction equipment used. Each layer shall be spread evenly, moisture conditioned and compacted per Section 3.7, Compaction. The Contractor shall widen any depressions as necessary to accommodate compaction equipment and provide a level base for placing fill. Compaction of each layer shall be continuous over its entire area and the compaction equipment shall make sufficient trips to insure that the required density has been obtained. No lift shall be placed until the previous lift has been approved. Fill operation shall be continued until the fill has been brought to the finished slopes and elevations shown on the Drawings. Imported fill shall conform to the requirements previously defined.
- I. Compacted subgrade shall be maintained in a moist state and shall not be allowed to significantly dry prior to placing more fill or base course.

### 3.05 EXCAVATION

- A. Excavation consists of removal and disposal of materials encountered to obtain required subgrade elevations.
- B. Excavation for foundations and footings shall have clean vertical walls, all corners squared up. Keep entire excavation free from any loose material. Excavation shall conform to dimensions and elevations indicated with allowance for erection of forms, shoring and inspection of footings.
- C. Material to be excavated shall be non-classified and shall include all earth or other materials encountered in excavating and grading. Where material encountered within the limits of Work is considered unsuitable by the Architect, such material shall be excavated below the grade shown on the Drawings as directed, and replaced with suitable material.
- D. Earth forms for footings may be permitted provided the earth is suitable and self-supporting as approved by the Architect or Geotechnical Engineer. Earthbank forms for foundation walls will not be permitted.
- E. Unauthorized excavation consists of materials beyond indicated subgrade elevations or dimensions without specific direction of the Architect. Under footing, foundation bases, or retaining walls, fill unauthorized excavations by extending the indicated bottom elevations of footing or base at the excavation bottom, without altering required top elevation. Clean concrete fill may be used to bring elevations to proper position, only when acceptable to the Architect. Elsewhere, backfill and compact unauthorized excavation as specified for authorized excavations, unless otherwise directed by the Architect. Costs for testing, if required, shall be borne by the Contractor.
- F. Stockpile satisfactory materials where directed, until required for backfill or fill. Locate and retain materials away from edge of excavations, even though such excavations are sheeted and braced to prevent such material falling or sliding into the excavations.
- G. Maintain sides and slopes of excavations in a safe condition until completion of backfilling, by scaling, benching, shelving or bracing. Take precautions to prevent slide or cave-ins.

### 3.06 BACKFILLING

- A. Place backfill about the buildings and structures as far as practical, as the Work of construction progresses. Backfilling against concrete work shall be done only when approved and directed. Backfill shall be deposited in layers of not more than six inches (6") in depth, and for the full width of the cross section. The material shall be carefully watered during placing by means of a fine spray or other approved method, so that each layer shall be thoroughly and uniformly wetted as directed by the Architect. The moisture content of all the material shall be carefully controlled at all times, and shall be checked at proper intervals to insure correct moisture content for compaction specified.

Each layer of fill material shall be compacted by hand and machine tampers to the density required in Section 3.07 COMPACTION when forming subgrade for concrete areas or supporting concrete floor slabs or supporting building footings.

- J. Backfilling of trenches shall progress as rapidly as the construction and testing of the Work will permit. In back-filling pipe trenches, approved fill shall first be compacted on both sides of the pipe in eight inch (8") layers to a depth of one foot over the top of the pipe. The remainder of the trenches shall be backfilled in compacted one-foot layers, except that fill in trenches in paved areas shall be compacted in six inch (6") layers to required grade.

### 3.07 COMPACTION

Compaction of cleaned exposed soil, imported soils, each lift of backfill, subbase fill, imported fill and base course materials shall be accomplished to the following density criteria:

<u>Material</u>	<u>Percent Compaction</u> <u>(ASTM D698)</u>
Cleaned exposed soil, imported soils, backfill and subbase fill:	
Below concrete sidewalk/slabs	90 max
Below pavement sections	95 min
Top soil in playfields and landscape areas	85-90 min
Miscellaneous Backfill not under buildings, concrete or paved areas	90 min

Compaction of clean, exposed site soils or fills of cleaned site soils within sidewalks and exterior concrete slab areas shall be accomplished with soils uniformly mixed at a moisture content of optimum to optimum plus three percent (+3%).

Compaction of imported soils within sidewalks and exterior concrete slab areas shall be accomplished with soils uniformly mixed at a moisture content of optimum plus or minus three percent ( $\pm 3\%$ ).

Natural undisturbed soils or compacted soils subsequently disturbed or removed by construction operations shall be replaced with materials compacted as specified above.

### 3.08 FINISH GRADING

- A. Perform finish grading required as indicated or reasonably inferred to permit installation of Work of others as shown on Drawings. After final clean-up of exterior and removal of trash and construction of the buildings, the site shall be graded to slopes and elevations as indicated on the Drawings and as directed by the Architect. Additional material required for finish grading shall be of topsoil quality, provided, placed and graded by the Contractor. Lawn areas around walks shall provide good slope drainage away from buildings as indicated. Rake indicated site and lawn areas smooth and level to a tolerance of plus or minus 0.1 foot from elevations indicated.
- B. Existing clean site soils free of debris and rocks over 1 inch in diameter may be used for fills in landscape areas.

### 3.09 FIELD QUALITY CONTROL

- A. Test: Field density tests shall be made by an approved independent soils testing laboratory, as defined herein, or at the request of the Architect and paid for with the testing allowance. When these tests indicate that the density of any area(s) is below the required density, that particular area(s) shall be reworked until the required density has been obtained.
- B. Restore any damage to adjacent properties, street and the like, caused by operations of this Section to original condition without additional cost to Owner.

### 3.10 CLEANING


- A. Conduct Work in an orderly and workmanlike manner and so as not to create a nuisance. Dirt shall not be permitted to accumulate on streets or sidewalks nor to be washed into sewers.
- B. During the course of the Work and on completion of the Work, remove excess materials, equipment and debris and dispose of away from premises. Leave Work in clean condition.

### **3.11 AS-BUILT DRAWINGS**

- A. The Surveyor shall provide certified, signed and sealed as-builts for all finish grade elevations indicated on the Drawings on 4 mil mylar and AutoCAD disk (2011 version or later). The Contractor shall schedule the Work to allow the Surveyor to obtain the as-builts. This Work will not be accepted until as-builts are approved by the Design Civil Engineer and City of Glendale.

**END OF SECTION**





## SECTION 32 16 00

### CONCRETE CURBS, GUTTERS, SIDEWALKS, AND DRIVEWAYS

#### PART 1 GENERAL

##### 1.01 SUMMARY

- A. Section includes: Installation of concrete curbs, gutters, sidewalks, and driveways as shown on the Drawings and as specified herein.

##### 1.02 REFERENCE STANDARDS

- A. MAG Specifications Section 340: Concrete curb, gutter, sidewalk, driveways and alley entrances.
- B. City of Glendale and MAG Standard Details.

##### 1.03 SUBMITTALS

- A. Mix design to Architect a minimum of seven (7) days prior to start of construction.
- B. Tests: Submit three certified copies of test results, samples and suppliers certification that materials conform to specified criteria.

##### 1.04 QUALITY ASSURANCE

- A. Contractor shall obtain, at his expense, all necessary construction permits and shall coordinate all necessary inspections with City of Glendale.

#### PART 2 PRODUCTS

##### 2.01 MATERIALS

- A. Concrete Curb, Gutter (where not next to driveway) and Sidewalk:  
Concrete: 2,500 psi (28 day strength), MAG Section 725
- B. Concrete Driveway and Curb and Gutter (where next to driveway):  
Concrete: 4,000 psi (28 day strength), MAG Section 725

#### PART 3 EXECUTION

##### 3.01 CONSTRUCTION METHODS FOR CONCRETE CURB, GUTTER, SIDEWALK AND DRIVEWAY

- A. Execute Work in accordance with MAG Specifications Section 340 and MAG Details and City of Glendale specifications and details.
- B. Sawcut existing pavements and concrete joined by new construction to a true line with straight vertical edges free from irregularities.
- C. Construct and compact true to grades and line shown on the Drawings.
- D. Curb machines may not be used.

- E. Do not place material displaced in the construction on the base and/or surfacing material already in place on the roadway nor the excavated material in such a manner as to interfere with access to property or traffic flow in the street.

### **3.02 TESTING**


- A. Inspection and testing will be performed by an independent testing agency employed and paid for in accordance with Section 01 43 26.
- B. Provide free access to Work and cooperate with appointed firm.
- C. Submit 3 copies of proposed mix design of each class of concrete including water/cement/strength and all supporting data to testing agency and Architect for review a minimum seven (7) days prior to commencement of Work.
- D. Tests of cement and aggregates may be performed to ensure conformance with requirements stated herein.
- E. Four (4) concrete test cylinders will be taken for every 100 or less cubic yards of each class of concrete placed. Make and cure concrete compressive strength test specimens in accordance with ASTM C31. Construct storage box of sufficient size and design to provide protection required by paragraph 7(a).
- F. One (1) additional test cylinder will be taken during cold weather concreting, and be cured on job site under same conditions as concrete it represents.
- G. One (1) slump test will be taken in accordance with ASTM C-143 of each set of compressive strength test cylinders taken.
- H. Where concrete is placed by pumping, tests shall be taken at the truck before concrete is placed in the pump.
- I. Tests to be performed by testing agency personnel in accordance with ASTM C39.

### **3.03 CLEANING**

- A. During the course of the Work and on completion of the Work, remove excess materials, equipment and debris and dispose of away from premises. Leave Work in clean condition.

**END OF SECTION**

**SECTION 32 71 00**  
**STORM DRAIN SYSTEM**



**PART 1 GENERAL**

**1.01 SUMMARY**

- A. Section includes: Storm Drain Construction as shown on the Drawings and as specified herein.

**1.02 SUBMITTALS**

- A. General: Submittal requirements are specified in Section 01300 - Submittals.
- B. Quality Control Submittals:
1. Storm drainage pipe, fittings, cleanouts, etc.
  2. Area drains, catch basins
  3. Dry well
  4. Oil grease interceptor

**1.03 PROJECT/SITE CONDITIONS**

- A. Visit the site. Examine and note conditions as to the character and extent of Work involved.

**1.04 QUALITY ASSURANCE**

- A. Contractor shall obtain all necessary construction permits and shall coordinate all necessary inspections with the City of Glendale. Owner to pay for permits.
- B. Construction staking shall be performed by a State of Arizona licensed Surveyor acceptable to the Architect and Owner.

**PART 2 PRODUCTS**

**2.01 MATERIALS**

- A. As specified on the Drawings and as allowed per MAG Specifications and City of Glendale codes and requirements and as indicated on Drawings.

**PART 3 EXECUTION**

**3.01 EXAMINATION**

- A. Verification of Conditions: Failure to observe this requirement constitutes a waiver to subsequent claims to the contrary and holds Contractor responsible for correction(s) Architect may require. Commencement of Work will be construed as acceptance of subsurfaces.
- B. Coordination with other work: Coordinate with other work which affects, connects with, or will be concealed by this Work.

### **3.02 STORM DRAIN CONSTRUCTION**

- A. Storm drain construction shall conform to the applicable requirements of MAG Specifications, Section 601, Trench Excavation, Backfilling and Compaction, Section 745, P.V.C. Sewer Pipe and Fittings and Section 603, Installation for High Density Polyethylene Pipe. Backfill and compaction shall be performed per Specifications, Section 02200, Earthwork, except as modified below.
- B. Storm Drain pipe shall consist of installing P.V.C. or H.D.P.E. storm drain pipe to the alignment and grades indicated on the Drawings.
- C. Granular bedding will be required from four inches (4") below the bottom of the pipe to one foot (1') above the pipe. All clean dirt spoils generated from the installation of the storm drain lines shall be removed from the site and disposed of legally.

### **3.03 CATCH BASINS, AREA DRAINS, DRYWELLS AND OIL/GREASE INTERCEPTOR**

- A. Catch Basins, area drains, Bubbler Boxes, Drywells and oil/grease interceptors shall be installed per the details on the Drawings and per the MAG Standard Details as indicated on the Drawings.


### **3.04 "AS-BUILT" DRAWINGS**

- A. The Contractor's Surveyor shall provide as-builts for all site storm drain lines (outside building areas). The Contractor shall schedule the Work to allow the Surveyor to obtain as-builts for the actual locations and elevations of the completed storm drain line including location, invert elevation and rim elevation of all catch basins, area drains, cleanouts, bends, etc. As-builts shall be provided on 4 mil mylars, certified, sealed and signed by the Surveyor. Mylar and Auto CADD 2011 disk as-builts shall be submitted to the Design Civil Engineer, Owner, and City for review and approval. Project is not accepted until all parties listed above approve as-built Drawings.

### **3.05 CLEANING**

- A. During the course of the Work and on completion of the Work, remove excess materials, equipment and debris and dispose of legally away from premises. Leave Work in clean condition.

**END OF SECTION**



## SECTION 33 70 00

### DECOMPOSED GRANITE

#### DECOMPOSED GRANITE

The Work under this item shall consist of installing a 2 inch compacted thickness of decomposed granite at the locations as indicated on the plans. The Work shall conform to MAG Specifications Section 430.4 except that no 10-mm black polyethylene liner will be required. Two applications of pre-emergent (one prior to placement of granite and one after placement) will be required.

Granite shall conform to MAG Specifications Section 702.4 and have a size of 1/4 inch minus. Color shall be Madison Gold to match the existing granite at the site.

**END OF SECTION**





Glendale Elementary School District SFB Projects: Construction Cost Estimates

BRG: Project: Scope: Updated 9/1/16 Cost Estimate:

070440103-9999-013-BRG	Smith Structural and Drainage		
	Phase 2	Installation of masonry control joints/repair CMU	\$ 100,000.00
		Install helical piers	\$ 500,000.00
		Grout injection of slab	\$ 100,000.00
		Riddle blockfill of new masonry and coating of Drylok extreme at exposed footing	\$ 8,000.00
		Remove turf and irrigation against building and replace with decomposed granite from face of wall to 5'-0" away from building	\$ 40,000.00
		Chasse Drainage estimate	\$ 57,738.75
		Estimated Phase 2 Subtotal	\$ 805,738.75
		Estimated Total Repair:	\$ 805,738.75

# DESIGN CIVIL ENGINEER'S NOTES TO CONTRACTOR:

1. NOTHING CONTAINED IN THE CONTRACT DOCUMENTS SHALL CREATE, NOR SHALL BE CONSTRUED TO CREATE, ANY CONTRACTUAL RELATIONSHIP BETWEEN THE DESIGN CIVIL ENGINEER AND THE CONTRACTOR OR ANY SUBCONTRACTOR.
2. THE DESIGN CIVIL ENGINEER WILL NOT BE RESPONSIBLE FOR CONSTRUCTION MEANS, METHODS, TECHNIQUES, SEQUENCES OR PROCEDURES OR FOR SAFETY PRECAUTIONS OR PROGRAMS UTILIZED IN CONNECTION WITH THE WORK. THESE ARE SOLELY THE CONTRACTOR'S RESPONSIBILITY. THE DESIGN CIVIL ENGINEER WILL NOT BE RESPONSIBLE FOR THE CONTRACTOR'S FAILURE TO CARRY OUT THE WORK IN ACCORDANCE WITH THE CONTRACT DOCUMENTS.
3. THE CONTRACTOR SHALL PROVIDE ADEQUATE MEANS OF CLEANING TRUCKS AND/OR OTHER EQUIPMENT OF MUD PRIOR TO ENTERING PUBLIC STREETS, AND IT IS THE CONTRACTOR'S RESPONSIBILITY TO CLEAN STREETS, ALLAY DUST, AND TO TAKE WHATEVER MEASURES ARE NECESSARY TO INSURE THAT ALL ROADWAYS AND ON SITE PARKING LOTS/FIRE LANES ARE MAINTAINED IN A CLEAN, MUD AND DUST-FREE CONDITION AT ALL TIMES.
4. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO CONTACT THE BLUE STAKE CENTER TWO WORKING DAYS PRIOR TO ANY EXCAVATION. THE UNDERGROUND UTILITY LOCATIONS AS SHOWN HEREON ARE BASED ON THE BEST INFORMATION AVAILABLE FROM UTILITY RECORDS AND OTHER DATA AS SUPPLIED TO THIS DESIGN CIVIL ENGINEER. THERE MAY BE OTHER UNDERGROUND UTILITY LINES, SERVICE LINES AND STRUCTURES PRESENT IN THE SUBJECT AREA. CONTRACTOR SHALL INCLUDE IN HIS BID THE COST OF HIRING AN UNDERGROUND UTILITY LOCATING SERVICE FOR THE PURPOSE OF LOCATING ALL UNDERGROUND UTILITIES. CONTRACTOR WILL COORDINATE WITH THE OWNER AND ARCHITECT TO DETERMINE WHETHER SAID UTILITIES ARE TO BE ABANDONED OR PROTECTED FROM DAMAGE.
5. THE DESIGN CIVIL ENGINEER MAKES NO REPRESENTATION OR GUARANTEE REGARDING THE EARTHWORK QUANTITIES OR THAT THE EARTHWORK FOR THIS PROJECT WILL BALANCE DUE TO THE VARYING FIELD CONDITIONS, CHANGING SOIL TYPES, ALLOWABLE CONSTRUCTION TOLERANCES AND CONSTRUCTION METHODS. PRIOR TO BIDDING THE WORK, THE CONTRACTOR SHALL THOROUGHLY SATISFY HIMSELF AS TO THE ACTUAL CONDITIONS, EARTHWORK QUANTITIES AND REQUIREMENTS OF THE WORK AND EXCESS OR DEFICIENCY THEREIN, ACTUAL OR RELATIVE.
6. THE CONTRACTOR SHALL ADJUST ALL EXISTING AND NEW CLEANOUTS, WATER VALVE BOXES, MANHOLES, GAS VALVE BOXES, IRRIGATION BOXES, ETC. IN THE CONSTRUCTION AREA TO FINISH GRADE PER THE APPLICABLE MAG STANDARD DETAIL. ALL VALVE BOXES, MANHOLES, ETC. IN CONCRETE PAVEMENT AREAS SHALL BE ISOLATED FROM THE CONCRETE PAVEMENT WITH EXPANSION JOINTS.
7. ALL NEW UNDERGROUND FACILITIES/UTILITIES SHALL BE INSTALLED WITH A DETECTABLE UNDERGROUND LOCATION DEVICE. INSTALL A #18 INSULATED TRACER WIRE SECURELY ATTACHED TO EACH UTILITY AT 8-FOOT ON CENTER. 12" OF TRACER WIRE SHALL BE ACCESSIBLE ABOVE GRADE AT THE TERMINATION AND SHALL BE SECURELY ATTACHED AT THAT POINT. THE CONTRACTOR SHALL INCLUDE ALL COSTS ASSOCIATED WITH THIS REQUIREMENT IN THEIR BID.
8. THE CONTRACTOR SHALL MAKE NO CLAIMS AGAINST THE OWNER OR THE DESIGN CIVIL ENGINEER REGARDING ALLEGED INACCURACY OF CONSTRUCTION STAKES SET BY THE DESIGN CIVIL ENGINEER UNLESS ALL SURVEY STAKES SET BY THE DESIGN CIVIL ENGINEER ARE MAINTAINED INTACT AND THEIR ORIGIN. ANY REMEDIAL WORK REQUIRED TO CORRECT ANY ITEM OF IMPROPER CONSTRUCTION WORK IN THIS DEVELOPMENT SHALL BE PERFORMED AT THE SOLE EXPENSE OF THE RESPONSIBLE CONTRACTOR OR SUBCONTRACTOR.

## DRAINAGE CORRECTIONS

AT


# HAROLD W. SMITH ELEMENTARY SCHOOL

SITE ADDRESS: 6534 N. 63RD AVENUE  
GLENDALE, ARIZONA 85303

FOR

GLENDALE ELEMENTARY SCHOOL DISTRICT NO. 40 (OWNER)

7301 N. 58TH AVENUE  
GLENDALE, ARIZONA 85303  
PHONE: (623) 842-8100  
CONTACT: GREG GILLIAM




VICINITY MAP  
NOT TO SCALE

### OWNER/DEVELOPER:


GLENDALE ELEMENTARY SCHOOL DISTRICT NO. 40  
7301 NORTH 58TH AVENUE  
GLENDALE, ARIZONA 85303  
PHONE: (623) 842-8100  
CONTACT: DEAN WALLACE

### ENGINEER:

HESS-ROUNTREE, INC.  
9831 S. 51ST STREET, SUITE C110  
PHOENIX, ARIZONA 85044  
PHONE: (480) 496-0244  
FAX: (480) 496-0094  
CONTACT: PERCY MYRON JR., P.E.



SECTION A-A  
NOT TO SCALE



SECTION B-B  
NOT TO SCALE

### LEGEND


- BC EXISTING BACK OF CURB ELEVATION
- P EXISTING PAVEMENT ELEVATION
- SW EXISTING SIDEWALK ELEVATION
- NG EXISTING GROUND ELEVATION
- TB EXISTING TOP OF BERM ELEVATION
- TS EXISTING TOE OF SLOPE ELEVATION
- FF EXISTING FINISH FLOOR ELEVATION
- EXISTING AREA DRAIN
- ⊕ EXISTING HOSE BIBB
- ⊗ GM EXISTING GAS METER
- ⊗ WV EXISTING WATER VALVE
- OGP EXISTING GATE POST
- O-PP EXISTING POWER POLE
- SSCO EXISTING SANITARY SEWER CLEANOUT
- GR EXISTING GAS RISER
- UGE EXISTING UNDERGROUND ELECTRIC
- EXISTING TREE
- 37.85 PROPOSED FINISH GRADE ELEVATION
- + NEW DECOMPOSED GRANITE (1/4 MINUS MADISON GOLD).

### GRADING AND DRAINAGE CONSTRUCTION NOTES:

1. INSTALL 2" THICKNESS OF NEW DECOMPOSED GRANITE (1/4" MINUS MADISON GOLD).
2. PROTECT EXISTING TREE AND ROOTS FROM DAMAGE. MODIFY GRADING AS NEEDED, ADJACENT TO TREE TO PROTECT THE ROOTS.
3. REGRADE LANDSCAPE AREA PER GRADES AND CROSS SECTIONS.

### BENCHMARK

MCDOT BENCHMARK 23023-1. TOP OF 3" GLENDALE BRASS CAP IN HANDHOLE, DOWN 1.0', STAMPED "N397" LOCATED AT THE INTERSECTION OF 67TH AVENUE AND MARYLAND AVENUE.  
ELEVATION=1128.077 (NAVD88 DATUM)



### GRADING AND DRAINAGE PLAN

GLENDALE ELEMENTARY SCHOOL DISTRICT NO. 40

DRAINAGE CORRECTIONS AT  
HAROLD W. SMITH ELEMENTARY SCHOOL

DRAWING STATUS	SHEET	OF	
1ST CITY SUBMITTAL	1	1	C-1
DATE: 08-10-16			





## SECTION 02 21 13

### CONSTRUCTION STAKING

Construction staking shall be performed by a licensed Surveyor acceptable to the Architect. Staking will be paid from the Construction Staking Allowance in the Contract.

Stakes: A minimum one set of construction grade stakes or "blue-tops" if possible of the following kind and at the stated interval shall be set. Blue-tops shall be set for all finish grading, sidewalk, curbing, concrete valley gutters, paving subgrade and A.B.C. and shall be left in place until checked and certified by the Civil Engineer.

1. Field staking control.
2. One site benchmark.
3. Mark out demo/sawcuts.
4. Rough grading cut and fill for onsite: at 50-foot intervals and grade breaks.
5. As-builts finish grade.
6. Prepare and submit as-built drawings to Contractor for submittal.
7. Office computer calculation for above staking.

END OF SECTION

## SECTION 31 01 00

### EARTHWORK



#### PART 1 GENERAL

##### 1.01 SUMMARY

- A. Section Includes: Perform earthwork as shown on the Drawing and as specified herein.

##### 1.02 QUALITY ASSURANCE

- A. Regulatory Requirements: Procure necessary permits or certificates required by City of Phoenix, State of Arizona and Maricopa County. Comply with applicable federal, state and local ordinances, including MAG Standard Specifications and Details. Owner to pay for permits.
- B. Layout of all Work under this Section shall be made by a licensed Engineer/Surveyor acceptable to the Architect.
- C. General Contractor shall give the Work his personal supervision. In his absence, he shall leave a responsible representative in charge who shall have the authority to receive and execute orders from the Architect and/or his representative.

##### 1.03 PROJECT/SITE CONDITIONS

- A. Environmental Requirements: No fill materials shall be placed, spread or rolled during unfavorable weather conditions. When the Work is interrupted by rain, fill operations shall not be resumed until it can be shown to the Civil Engineers/Architect's satisfaction that the moisture content and density of the previously placed fill are as specified.
- B. Visit the site. Examine and note conditions as to the character and extent of Work involved.

#### PART 2 PRODUCTS

##### 2.01 FILL

- A. Cleaned onsite soils may be used for fills in all areas of the site.
- B. Fill materials shall be approved by the Geotechnical Engineer and Civil Engineer and shall have low swell potential and be free of organic or deleterious material.
- C. Imported fill of low or non-expansive soils shall conform with the following requirements:

Maximum Percent Passing	
No. 200 Sieve	15 percent
Maximum Particle Size	6 inches (1 inch in landscape or turf areas)
Maximum Swell Potential	1.5 percent *
Within exterior concrete slabs	

\*Based on a sample which is remolded to 95% of the ASTM D698 maximum dry density at a moisture content of 2 percent below optimum, placed under a surcharge load of 100 psf and wetted.



## **PART 3 EXECUTION**

### **3.01 PREPARATION**

- A. Existing Utilities:
  - 1. Where existing utilities not shown on the Drawings are encountered, support, shore up, protect same and immediately notify Engineer and General Contractor. Allow entrance, opportunity and ample time for measures necessary for continuance and/or relocation of such services.
  - 2. Where noted on Drawings, cut and cap all street connections encountered in the excavating along curb line and mark location so they can subsequently be located and reconnected as required.
- B. Protection:
  - 1. Keep all excavations, pits, trenches, etc. entirely free from water.
  - 2. Protect excavations from rain or water from any source during construction. Use suitable pumping equipment or other means as required by conditions. Continue pumping as necessary until completion of project or until released by Engineer.
  - 3. Conduct Work in an orderly manner so as not to create a nuisance. Dirt shall not be permitted to accumulate on streets or sidewalks nor to be washed into sewers.
  - 4. During construction operations and after building construction, buildings shall be protected from surface water run-off and drainage from surrounding heights. Run-off water shall be diverted around buildings and construction operations.
- C. Layout:
  - 1. Maintain all bench marks, control monuments and stakes, whether newly established by Surveyor or previously existing. Protect from damage and dislocation. If necessary to disturb existing bench marks, have Surveyor reestablish in a safe place.
  - 2. If any discrepancies are found by Surveyor between the Drawings and actual conditions at the site, Engineer reserves the right to make such minor adjustments in Work specified as necessary to accomplish the intent of the contract Documents, without increased cost to Owner.

### **3.02 EXCAVATABILITY**

- A. The excavatability of site materials is difficult to evaluate based only on the exploration equipment used during the geotechnical design report. Therefore, the Geotechnical Engineer recommends that the Contractor evaluate the excavatability of site materials by performing test excavations with the size and type of equipment that Contractor plans on using at the site.
- B. The near surface and underlying soils can probably be removed with conventional excavating equipment. Deeper excavations may be slower and more difficult to accomplish due to caving and presence of oversized material. Caving should be expected in the non-cohesive granular soils encountered. OSHA requires all excavations over five feet in depth, in which personnel are to enter, be either braced or sloped in accordance with OSHA regulations.

### 3.03 WORKABILITY

- A. Wetting site soils such that moisture contents are at or above optimum could result in some soil pumping under dynamic loadings such as heavy construction equipment driving over the area. In the building area, some pumping is not detrimental to foundation or floor slabs provided the specified percent compaction is achieved. However, in flexible pavement areas where pumping has occurred, and in building areas where severe pumping has damaged subgrade conditions, the area shall be allowed to dry until soils are workable without pumping or the wetted areas removed and replaced with drier site soils.

### 3.04 GRADING

- A. General Contractor shall provide personal supervision for the Work. Leaving a responsible representative in charge, when absent, who shall have the authority to receive and execute instructions from the Architect or his representative.
- B. Grading tolerance shall be +0.00 feet and -0.10 feet.
- C. The following requirements are for site grading under, within and extending five feet beyond the sidewalks, exterior concrete slabs, and concrete fire lanes.
- D. Strip the entire site of all existing fill zones, any backfill zones and any unstable soils. During stripping observe the surface for evidence of buried debris, vegetation or disturbed materials which will require additional removal. If encountered, these materials shall be removed. Areas steeper than 5H to 1V should be benched and any depressions widened to accommodate compaction equipment.
- E. Widen any resulting depressions as necessary to accommodate compaction equipment and provide a level base for placing fill.
- F. Prepare the ground surface in fill areas and in areas cut to grade by scarifying, moisture conditioning and compacting the exposed surface soils to a minimum 10-inch depth. Moisture conditioning and compaction shall meet requirements under Section 3.07, Compaction.
- G. Moisture condition and place engineering fill material required to elevate areas to specified subgrade elevations.
- H. Placing, Spreading and Compacting Fill Materials: Fill materials shall be placed and compacted in horizontal lifts of thickness compatible with the compaction equipment used. Each layer shall be spread evenly, moisture conditioned and compacted per Section 3.7, Compaction. The Contractor shall widen any depressions as necessary to accommodate compaction equipment and provide a level base for placing fill. Compaction of each layer shall be continuous over its entire area and the compaction equipment shall make sufficient trips to insure that the required density has been obtained. No lift shall be placed until the previous lift has been approved. Fill operation shall be continued until the fill has been brought to the finished slopes and elevations shown on the Drawings. Imported fill shall conform to the requirements previously defined.
- I. Compacted subgrade shall be maintained in a moist state and shall not be allowed to significantly dry prior to placing more fill or base course.

### 3.05 EXCAVATION

- A. Excavation consists of removal and disposal of materials encountered to obtain required subgrade elevations.
- B. Excavation for foundations and footings shall have clean vertical walls, all corners squared up. Keep entire excavation free from any loose material. Excavation shall conform to dimensions and elevations indicated with allowance for erection of forms, shoring and inspection of footings.
- C. Material to be excavated shall be non-classified and shall include all earth or other materials encountered in excavating and grading. Where material encountered within the limits of Work is considered unsuitable by the Architect, such material shall be excavated below the grade shown on the Drawings as directed, and replaced with suitable material.
- D. Earth forms for footings may be permitted provided the earth is suitable and self-supporting as approved by the Architect or Geotechnical Engineer. Earthbank forms for foundation walls will not be permitted.
- E. Unauthorized excavation consists of materials beyond indicated subgrade elevations or dimensions without specific direction of the Architect. Under footing, foundation bases, or retaining walls, fill unauthorized excavations by extending the indicated bottom elevations of footing or base at the excavation bottom, without altering required top elevation. Clean concrete fill may be used to bring elevations to proper position, only when acceptable to the Architect. Elsewhere, backfill and compact unauthorized excavation as specified for authorized excavations, unless otherwise directed by the Architect. Costs for testing, if required, shall be borne by the Contractor.
- F. Stockpile satisfactory materials where directed, until required for backfill or fill. Locate and retain materials away from edge of excavations, even though such excavations are sheeted and braced to prevent such material falling or sliding into the excavations.
- G. Maintain sides and slopes of excavations in a safe condition until completion of backfilling, by scaling, benching, shelving or bracing. Take precautions to prevent slide or cave-ins.

### 3.06 BACKFILLING

- A. Place backfill about the buildings and structures as far as practical, as the Work of construction progresses. Backfilling against concrete work shall be done only when approved and directed. Backfill shall be deposited in layers of not more than six inches (6") in depth, and for the full width of the cross section. The material shall be carefully watered during placing by means of a fine spray or other approved method, so that each layer shall be thoroughly and uniformly wetted as directed by the Architect. The moisture content of all the material shall be carefully controlled at all times, and shall be checked at proper intervals to insure correct moisture content for compaction specified.

Each layer of fill material shall be compacted by hand and machine tampers to the density required in Section 3.07 COMPACTION when forming subgrade for concrete areas or supporting concrete floor slabs or supporting building footings.

- J. Backfilling of trenches shall progress as rapidly as the construction and testing of the Work will permit. In back-filling pipe trenches, approved fill shall first be compacted on both sides of the pipe in eight inch (8") layers to a depth of one foot over the top of the pipe. The remainder of the trenches shall be backfilled in compacted one-foot layers, except that fill in trenches in paved areas shall be compacted in six inch (6") layers to required grade.

### 3.07 COMPACTION

Compaction of cleaned exposed soil, imported soils, each lift of backfill, subbase fill, imported fill and base course materials shall be accomplished to the following density criteria:

<u>Material</u>	<u>Percent Compaction</u> <u>(ASTM D698)</u>
Cleaned exposed soil, imported soils, backfill and subbase fill:	
Below concrete sidewalk/slabs	90 max
Below pavement sections	95 min
Top soil in playfields and landscape areas	85-90 min
Miscellaneous Backfill not under buildings, concrete or paved areas	90 min

Compaction of clean, exposed site soils or fills of cleaned site soils within sidewalks and exterior concrete slab areas shall be accomplished with soils uniformly mixed at a moisture content of optimum to optimum plus three percent (+3%).

Compaction of imported soils within sidewalks and exterior concrete slab areas shall be accomplished with soils uniformly mixed at a moisture content of optimum plus or minus three percent ( $\pm 3\%$ ).

Natural undisturbed soils or compacted soils subsequently disturbed or removed by construction operations shall be replaced with materials compacted as specified above.

### 3.08 FINISH GRADING

- A. Perform finish grading required as indicated or reasonably inferred to permit installation of Work of others as shown on Drawings. After final clean-up of exterior and removal of trash and construction of the buildings, the site shall be graded to slopes and elevations as indicated on the Drawings and as directed by the Architect. Additional material required for finish grading shall be of topsoil quality, provided, placed and graded by the Contractor. Lawn areas around walks shall provide good slope drainage away from buildings as indicated. Rake indicated site and lawn areas smooth and level to a tolerance of plus or minus 0.1 foot from elevations indicated.
- B. Existing clean site soils free of debris and rocks over 1 inch in diameter may be used for fills in landscape areas.

### 3.09 FIELD QUALITY CONTROL

- A. Test: Field density tests shall be made by an approved independent soils testing laboratory, as defined herein, or at the request of the Architect and paid for with the testing allowance. When these tests indicate that the density of any area(s) is below the required density, that particular area(s) shall be reworked until the required density has been obtained.
- B. Restore any damage to adjacent properties, street and the like, caused by operations of this Section to original condition without additional cost to Owner.

### 3.10 CLEANING

- A. Conduct Work in an orderly and workmanlike manner and so as not to create a nuisance. Dirt shall not be permitted to accumulate on streets or sidewalks nor to be washed into sewers.
- B. During the course of the Work and on completion of the Work, remove excess materials, equipment and debris and dispose of away from premises. Leave Work in clean condition.

### **3.11 AS-BUILT DRAWINGS**

- A. The Surveyor shall provide certified, signed and sealed as-builts for all finish grade elevations indicated on the Drawings on 4 mil mylar and AutoCAD disk (2011 version or later). The Contractor shall schedule the Work to allow the Surveyor to obtain the as-builts. This Work will not be accepted until as-builts are approved by the Design Civil Engineer and City of Glendale.

**END OF SECTION**





**SECTION 33 70 00**

**DECOMPOSED GRANITE**

**DECOMPOSED GRANITE**

The Work under this item shall consist of installing a 2 inch compacted thickness of decomposed granite at the locations as indicated on the plans. The Work shall conform to MAG Specifications Section 430.4 except that no 10-mm black polyethylene liner will be required. Two applications of pre-emergent (one prior to placement of granite and one after placement) will be required.

Granite shall conform to MAG Specifications Section 702.4 and have a size of 1/4 inch minus. Color shall be Madison Gold to match the existing granite at the site.

**END OF SECTION**