



ROC L-16 092461

FIRE EQUIPMENT SALES  
AND SERVICE CORPORATION

ROC L-67 092462

3107 W. VIRGINIA AVE. ★ PHX, AZ 85009-1604 ★ (602) 433-2484 ★ Fax (602) 433-9626  
2921 S. KISH AVE ★ YUMA, AZ 85366 ★ (928) 341-0025 ★ Fax (928) 341-0336  
SHOW LOW ★ PINETOP ★ LAKESIDE ★ (928) 632-2292

11/1/2012

Jeff Akins  
Blue Ridge Middle School  
3050 N. Porter Mt. Rd.  
Lake Side, Az. 85929

Phone: 928-341-0025  
E-Mail: jakins@brusdk12.az.us  
DNR#: SLM180

**RE: Fire alarm repairs per system report dated 1-27-2012. SE front office storage closet**

*American Fire Equipment Sales & Service would like to present you with the following proposal for the above referenced facility.*

**Deficiencies Noted**

- ▶ Upon arrival fire alarm panel was in trouble due to short on booster panel PAD3 #3 in electrical RM 429. Also has trouble on fire alarm panel due to bad monitor module on a beam detector on gym.
- ▶ Duct detector address 1-52 hall outside reception 237 did not shutdown A/C unit. Duct detector in PE storage rm. 409 no access due to hardlid ceiling.
- ▶ Room 351 has a bad horn on the horn/strobe, tone low & distorted. The following room has horn/strobes blocked by shelving or books: Rooms 142, 141, 135, 134, 102, 101 and 125.
- ▶ NAC's in the multi-pupose room and PE office did not work do to short on circuit. Class rooms, library and hall strobes are not synchronized. Main fire alarm batteries are out of date.

**Scope of Work**

- ▶ Trouble shoot short on booster panel. Siemens to replace monitor module on beam detector in gym.
- ▶ Trouble shoot duct detector 1-52 that does not shutdown a/c unit. Install access panel in hardlid rm. 409 and test duct detector.
- ▶ Replace bad horn strobe in room 351. Need customer to please make horn/strobes listed above visually accessible per NFPA 72
- ▶ Trouble shoot short in NAC circuit in PE office. Synchronize horn/strobes throughout facility.

**Cost Summary**

*American Fire Equipment is pleased to provide and complete the above scope of work for the sum of:*

Total Labor	\$2,210.00
Total Materials	\$1,208.00
Sub Total	\$3,418.00
Tax	\$112.34
<b>Total Proposal</b>	<b>\$3,530.34</b>