



Reg 133

Proposal Number: CS17002

April 27, 2017

Mr. Andy Valdivia  
Director of Transportation and Maintenance  
Riverside School District No. 2  
1414 South 51<sup>st</sup> Avenue  
Phoenix, Arizona 85043

**Riverside School District Curb Replacement**  
1414 South 51<sup>st</sup> Avenue  
Phoenix, Arizona 85043

Gentlemen:

DBA Construction, Inc. proposes to furnish all labor, equipment and materials (unless otherwise noted) to complete these items as listed. We thank you for the opportunity to submit a proposal for the project referenced.

**RIVERSIDE SCHOOL DISTRICT CURB REPLACEMENT**

ITEM #	QTY.	UNIT	DESCRIPTION	UNIT PRICE	EXTENSION
1	1	EA	Mobilization	\$250.00	\$ 250.00
2	16	LF	Remove & Reset Temporary Fence	\$16.50	\$ 264.00
3	16	LF	Remove Damage Curb	\$38.40	\$ 614.40
4	16	LF	MAG 222 Type B Concrete Curb	\$120.00	\$ 1,920.00
<b>TOTAL:</b>					<b>\$ 3,048.40</b>
<b>PROPOSAL TOTAL:</b>					<b>\$ 3,048.40</b>

**Assumptions**

Our proposal is based on assuming that the following conditions exist at the project site:

1. Curb repair work can be performed from the school parking lot.
2. No utility conflicts.
3. Traffic control will not be required.
4. The saw cutting, removal and patch back of 2 feet of asphalt adjacent to curb will not be required.

**Clarifications**

Our proposal requires further clarification on these points in order to be considered:

1. Pricing based on the mobilizations shown.
2. Pricing includes taxes and bond.
3. The existing temporary fence panel will be removed during the curb replacement and wire tied in place upon completion of the curb replacement.
4. Scheduling will be upon a mutual agreement between the Riverside School District and DBA Construction, Inc.



#### Exclusions

Our proposal excludes the following items and were not considered during the preparation of this estimate:

1. Permits.
2. Traffic control.
3. Fence repairs replacements.
4. The adjustment and relocation of conflicting utilities.
5. The two (2) feet overcut, removal and patching of asphalt adjacent to curbs, gutters and curb and gutter. (Removal/Replacement of 2 feet of asphalt would cost an additional \$448.00)

**DBA CONSTRUCTION, INC.**

Craig Schepp

**WOODRUFF CONSTRUCTION**

9401 N. 7th Ave. Phoenix, Az. 85021  
2710 E. Lakin Dr. / Flagstaff, AZ 86004

**PROPOSAL**

4/21/2017

To: **RESD #2**  
Attn: **Andy Valdivia**  
Address: **1414 S. 51st Ave**  
**Phoenix, AZ 85043**  
Phone: **602-272-1339**  
Email: \_\_\_\_\_

BWC Bid/Proj. #: **17-194**  
BWC Bid/Proj. Name: **RESD District Office Concrete Curb Repair**  
\_\_\_\_\_  
\_\_\_\_\_  
# of pages incl.: **1**

We propose to furnish the following material, labor & equipment necessary to complete the following:

**BASE BID:**

Repair the existing concrete curbing (where car damaged fencing) at the District Office.

**General Requirements:** Supervision, Trash Haul Off, Daily & Final Clean-up.

**Sitework:** Saw-cut and remove the existing asphalt and curbing to allow for forming of new curb. Once new curb has been installed patch back asphalt.

**Concrete:** Form and pour new 14" curb and new post foundation. Once curb has set up strip forms.

**Bid Clarifications:**

- 1) All work to be done during normal hours.
- 2) Owner to allow us to use their electric & water to complete the work.
- 3) No fencing work is included in this bid. Fence work is under a separate contract.

**Exclusions:** Bond, and anything not listed above.

**Base Bid #1**

<b>Base Bid:</b>	<b>\$4,239.02</b>
<b>Tax on Materials @8.05%:</b>	<b>Inc.</b>
<b>Total Price:</b>	<b>\$4,239.02</b>

Phoenix: Phone: 480.921.1925 / Fax: 480.446.0825  
Flagstaff: Phone: 928.527.4138 / Fax: 928.527.4139  
e-mail: info@woodruffaz.com / www.woodruffaz.com  
ROC: B-096802 - B1-096809 - A-263244