SFBADJW-16 Validation Form

Submission ID: Current Status: Submitted 3/14/2019 4:42:33 PM 1242

Initial Submission Date: 3/14/2019

Resubmission Date:

District Name: Deer Valley Unified District

Contact Person: Jim Migliorino **Contact Phone:** 623-445-4958

Contact Email: jim.migliorino@dvusd.org

School: Hillcrest Middle School

Site Address: 22833 N 71st Ave

Glendale AZ 85310

Project Title: Hillcrest Modernization

Project Detail: As part of a \$7.4 million bond-funded modernization project at Hillcrest Middle School, there is a small portion of this project that qualifies for Adjacent Ways funding (see below).

> Refer to sheets C1.2 Grading Drainage and Fire Line Plan sheet and C1.3 Grading, Drainage and Fire Line Plan for a graphic of what Work is being proposed for Adjacent Ways funding.

Fire line connection to City of Glendale water lines for fire sprinkler water mains along Patrick Lane and

71st Avenue to property line. Work includes:

- Traffic control:
- Cutting and pavement removal;
- Trenching;
- Pipe and valve installation;
- Backfill and pavement replacement;
- Roadway curb removal and replacement;
- Removal of landscape material and plantings and replacement of the same;
- Removal and relocation of landscape irrigation lines;
- Engineering design fees.

Replacement of fire lane pavement from installation of fire sprinkler lines to buildings. Work includes:

- Backfill of trenches:
- Replacement of asphaltic pavement and concrete pavement;
- Engineering design fees;
- Removal and replacement of curbs.

Revision to fire lane on parking lot south side. Work includes:

- Removal of existing pavement and curbs;
- Grading of subgrade for fire lane;
- Removal and replacement of landscape material and plantings;
- New pavement and concrete curbs;
- Painting and signage at new portion of fire lane.

Project Date Range: 5/1/2019 TO 12/1/2019

\$7,400,000.00 **Adjacent Ways Cost: Total Project Cost:** \$248,447.29

Board Meeting Date:

PDF Generated: 3/14/2019 4:42:35 PM **Submission ID:** 1242 1 Page:

Validation Status: Review Pending	
Staff Analysis:	
Board Decision:	

PDF Generated: 3/14/2019 4:42:35 PM **Submission ID:** 1242 **Page:** 2