



To: Higley USD
2935 S Recker Rd.
Gilbert AZ 85295

Project: Higley USD-Higley HS Fire Lane
4068 E. Pecos Rd
Gilbert AZ 85295

Scope of Work:

Remove & Replace

Project bid in accordance to 1GPA contract number 17-16P-03

ASPHALT REMOVE & REPLACE:

Barricade all limits of work area. Demo and haul 3,857 SF of existing 3" asphalt pavement. Fine grade and compact ABC. Pave 3,857 SF of new 1/2" hot asphalt. Roll and compact to an average finished depth of 3 inches.

EXCLUSIONS:

Bonds, Testing, Inspections & Inspection Coordination, Soils Report, SWPPP, ROW Permit, Dust Permit, Hydrant Meter, Utility Adjustments, Import/Export, As-builts, Survey & Staking Layout, Repair of Landscape/Irrigation, Jobsite Port-a-Johns, Striping Obliterations, towing of vehicles, traffic control, handling of spoils created by others, Additional mobilizations, Due to volatile oil pricing, asphalt material pricing included in this proposal is good for 30days from date of this proposal, Terms: Due upon receipt.

SUB TOTAL: **12,834.05**

Crackseal

CRACK SEALING:

Major cracks (1/4" width and larger, excluding alligatored areas) will be cleaned and sealed with a hot applied rubberized crack sealant. Price based on using approximately 65 gallons of sealant material. Written authorization will be required if additional quantities are necessary.

SUB TOTAL: **1,869.53**

Sealcoat-GuardTop

SEALCOAT:

Thoroughly clean all existing asphalt pavement, approximately 34,695 SF. Apply TWO coats of GuardTop pavement sealer.

SUB TOTAL: **4,024.47**

Stripe

STRIPE:

Re-stripe to match existing layout.

EXCLUSIONS:

Bonds, Testing, Inspections & Inspection Coordination, Soils Report, SWPPP, ROW Permit, Dust Permit, Hydrant Meter, Utility Adjustments, Import/Export, As-builts, Survey & Staking Layout, Repair of Landscape/Irrigation, Jobsite Port-a-Johns, Striping Obliterations, towing of vehicles, traffic control, handling of spoils created by others, Additional mobilizations, Due to volatile oil pricing, asphalt material pricing included in this proposal is good for 30days from date of this proposal, Terms: Due upon receipt.

SUB TOTAL: 123.91

Job total: \$18,851.96

Proposal submitted by: John McCormack, , john@regionalpavement.com

The above pricing, specifications, and conditions are satisfactory and hereby accepted. You are authorized to do the work as specified. I understand a preliminary notice of lien, Pre-lien, will be filed and this notice is simply an informative notice and not a lien against the property.

Accepted by _____

Date _____

Printed Name _____

Title _____