



To: Higley USD
2935 S Recker Rd.
Gilbert AZ 85295

Project: Higley USD-Higley Traditional Academy
3391 Vest Ave
Gilbert AZ 85295

Scope of Work:

Asphalt R&R(Adjacent Ways)

Project bid in accordance to 1GPA contract number 17-16P-03

ASPHALT REMOVE & REPLACE:

Barricade all limits of work area. Make all necessary saw cuts. Remove and haul off 2,793 SF of existing 3" asphalt. Fine grade and compact existing ABC. Pave 2,793 SF using new 1/2" hot mix asphalt. Roll and compact to an average finished depth of 3 inches.

TOTAL: \$9,926.80

Crack Sealing(Adjacent Ways)

CRACK SEALING:

Major cracks (1/4" width and larger, excluding alligatored areas) will be cleaned and sealed with a hot applied rubberized crack sealant. Price based on using approximately 198 gallons of sealant material. Written authorization will be required if additional quantities are necessary.

TOTAL: \$3,031.50

Sealcoat(Adjacent Ways)

SEALCOAT:

Thoroughly clean all existing asphalt pavement, approximately 104,520 SF. Apply TWO coats of GuardTop pavement sealer.

TOTAL: \$12,057.26

Stripe(Adjacent Ways)

STRIPE:

Re-stripe to match existing layout, including 175 LF of red curb painting.

TOTAL: \$750.88

Concrete

CONCRETE VAULT BOX REPAIR:

Barricade all limits of work area. Make all necessary saw cuts. Remove damaged Vault box cover and haul all debris off site. Install 20 LF of concrete Vault walls to a depth of 6 inches with #3 rebar dowels drilled and set into the existing concrete Vault walls for reinforcement. Install 1 new Vault frame ledge and reinforced galvanized diamond plate lid embedded into new concrete.

TOTAL: \$6,987.75

Fence

GATE WORK:

Adjust gate and install welded on metal caster wheels. Install gate rod holder in new asphalt pavement.

TOTAL: \$1,996.50

Crack Sealing(Non-Adjacent)

CRACK SEALING:

Major cracks (1/4" width and larger, excluding alligatored areas) will be cleaned and sealed with a hot applied rubberized crack sealant. Price based on using approximately 80 gallons of sealant material. Written authorization will be required if additional quantities are necessary.

TOTAL: \$2,468.74

Sealcoat(Non-Adjacent)

SEALCOAT:

Thoroughly clean all existing asphalt pavement, approximately 42,510 SF. Apply TWO coats of GuardTop pavement sealer.

TOTAL: \$5,376.44

Stripe(Non-Adjacent)

STRIPE:

Re-stripe to match existing layout.

EXCLUSIONS:

Bonds, Testing, Inspections & Inspection Coordination, Soils Report, SWPPP, ROW Permit, Dust Permit, Hydrant Meter, Utility Adjustments, Import/Export, As-builts, Survey & Staking Layout, Repair of Landscape/Irrigation, Jobsite Port-a-Johns, Striping Obliterations, towing of vehicles, traffic control, handling of spoils created by others, Additional mobilizations, Due to volatile oil pricing, asphalt material pricing included in this proposal is good for 30days from date of this proposal, Terms: Due upon receipt.

TOTAL: \$1,054.96

GRAND TOTAL: \$43,650.83

Proposal submitted by: John McCormack, , john@regionalpavement.com

The above pricing, specifications, and conditions are satisfactory and hereby accepted. You are authorized to do the work as specified. I understand a preliminary notice of lien, Pre-lien, will be filed and this notice is simply an informative notice and not a lien against the property.

Accepted by _____

Date _____

Printed Name _____

Title _____