

Current Status: Processing Complete 10/1/2019 2:55:25 PM **Submission ID:** 1312

Initial Submission Date:

Resubmission Date:

District Name: Mesa Unified District

Contact Person: Joseph Georges

Contact Phone: 4802506527

Contact Email: jbgeorges2@mpsaz.org

School: Adams Elementary School

Site Address: 555 S Lewis

Project Title: Red Mountain HS - Fire Lane Repairs

Project Detail: Thoroughly clean approximately 5209 square yards of the existing pavement surface. Cracks (1/4 inch and wider) in the center of the drive only will be caulked with a hot-applied, rubberized crack sealer, using up to a maximum of 100 gallons of material. Apply a MAG Type II CATIONIC polymer-modified micro seal at a rate of 22-24 pounds per square yard. Polymer modifications to micro seal improves binder cohesion and abrasion resistance, Lessening the impact of raveling and scuffing especially in a tight parking lot or cul-de-sac areas.

Project Date Range: 12/23/2019 **TO** 1/1/2020

Total Project Cost: \$37,832.00 **Adjacent Ways Cost:** \$37,832.00

Board Meeting Date:

Validation Status: No Review Required

Staff Analysis:

Board Decision: