

Current Status: Processing Complete 8/28/2020 10:18:34 AM **Submission ID:** 2408

Initial Submission Date:

Resubmission Date:

District Name: Willcox Unified District

Contact Person: Kevin Davis

Contact Phone: 5203848606

Contact Email: kevin.davis@wusd13.org

School: District Project

Site Address: 480 N. Bisbee Ave.

Project Title: Street Maintenance

Project Detail: Remove and Replace Asphalt Repairs
Provide Traffic Control And Barricades During Our Scope Of Work. Make Necessary Saw Cuts. Remove Approximately 39 Square Feet Of Failed Asphalt In Two Areas To A Depth Of 3". Compact Existing Base And Pave Approximately 39 Square Feet With 3" Of 1/2" Asphaltic Surface Course. The Depth Of The Existing Asphalt Is Only An Estimate. Additional Depth Will Require Additional Charges. The Removal Of The Asphalt Has Been Bid For That Function Alone And Does Not Include Excavation Of The Base Or Sub-base. If At The Time Of Removal, It Is Determined That Water Has Weakened Either The Base Or Sub-base, Additional Charges Would Be Required To Correct The Unforeseen Problem. If Upon The Removal Of The Asphalt, It Is Found That Structures Exist Below The Surface, Such As Concrete Footings, Abandoned Pipes, Metal Supports, Etc., An Additional Charge Would Be Required To Remove These Obstructions If They Would Impede Or Prohibit Grade Consistencies. Sunland Asphalt Will Not Be Held Liable For Any Underground Cables, Electrical Lines, Water Lines Or Any Other Underground Obstruction, Not Buried At Least 18 Inches Below Existing Finished Grade.

Crack Seal and Seal Coat Application
Provide Traffic Control And Barricades During Our Scope Of Work.
Clean With Compressed Air And Seal All Cracks 1/4" And Larger With Elastoflex 380 Crack Sealant. Alligatored Areas Not Included.
Power Sweep And Clean Asphalt Surface In Preparation Of Sealing.
Furnish And Apply Two (2) Coats Of PMM (RTU) Sealer By Spray Application On Approximately 2402 Square Feet.
Adhesion Or Bonding Of Materials Is Not Warranted In Areas Exposed To Automotive Fluids And/or Other Spills.

Restripe Seal Coat Application Area To Existing Layout.
This Proposal Is Based On Performing The Work In 1 Section

Project Date Range: 8/1/2020 **TO** 10/31/2020
Total Project Cost: \$5,887.19 **Adjacent Ways Cost:** \$5,887.19
Board Meeting Date:
Validation Status: No Review Required
Staff Analysis:
Board Decision: