

Current Status: Processing Complete 8/31/2020 10:30:30 AM **Submission ID:** 2420

Initial Submission Date:

Resubmission Date:

District Name: Willcox Unified District

Contact Person: Kevin Davis

Contact Phone: 5203848606

Contact Email: kevin.davis@wusd13.org

School: Willcox Middle School

Site Address: 360 N. Bisbee Ave.

Project Title: MS Bus Loop

Project Detail: Provide Traffic Control And Barricades During Our Scope Of Work.
Make Necessary Saw Cuts.
Remove Approximately 6698 Square Feet Of Failed Asphalt To A Depth Of 3".
Compact
Existing Base And Pave Approximately 6698 Square Feet With 3" Of 1/2" Asphaltic
Surface
Course. The Depth Of The Existing Asphalt Is Only An Estimate. Additional Depth Will
Require Additional Charges. The Removal Of The Asphalt Has Been Bid For That
Function
Alone And Does Not Include Excavation Of The Base Or Sub-base. If At The Time Of
Removal, It Is Determined That Water Has Weakened Either The Base Or Sub-base,
Additional Charges Would Be Required To Correct The Unforeseen Problem. If Upon
The
Removal Of The Asphalt, It Is Found That Structures Exist Below The Surface, Such
As
Concrete Footings, Abandoned Pipes, Metal Supports, Etc., An Additional Charge
Would Be
Required To Remove These Obstructions If They Would Impede Or Prohibit Grade
Consistencies. Sunland Asphalt Will Not Be Held Liable For Any Underground Cables,
Electrical Lines, Water Lines Or Any Other Underground Obstruction, Not Buried At
Least 18
Inches Below Existing Finished Grade.
Provide Traffic Control And Barricades During Our Scope Of Work.
Clean With Compressed Air And Seal All Cracks 1/4" And Larger With Elastoflex 380
Crack
Sealant. Alligatored Areas Not Included.
Power Sweep And Clean Asphalt Surface In Preparation Of Sealing.
Furnish And Apply Two (2) Coats Of PMM (RTU) Sealer By Spray Application On
Approximately 23580 Square Feet.
Adhesion Or Bonding Of Materials Is Not Warranted In Areas Exposed To Automotive
Fluids
And/or Other Spills.
Restripe Seal Coat Application Area To Existing Layout.
This Proposal Is Based On Performing The Work In 1 Section

Project Date Range: 9/1/2020 **TO** 11/1/2020

Total Project Cost: \$34,768.86 **Adjacent Ways Cost:** \$30,830.66

Board Meeting Date:

Validation Status: No Review Required

Staff Analysis:

--

Board Decision:

--