

Current Status: Processing Complete 8/31/2020 10:40:40 AM **Submission ID:** 2423

Initial Submission Date:

Resubmission Date:

District Name: Willcox Unified District

Contact Person: Kevin Davis

Contact Phone: 5203848606

Contact Email: kevin.davis@wusd13.org

School: Willcox Elementary School

Site Address: 501 W. Delos St.

Project Title: ES Admin Lot

Project Detail: Provide Traffic Control And Barricades During Our Scope Of Work.
Make Necessary Saw Cuts.
Remove Approximately 6772 Square Feet Of Failed Asphalt To A Depth Of 2.5".
Compact
Existing Base And Pave Approximately 6772 Square Feet With 2.5" Of 1/2" Asphaltic
Surface
Course. The Depth Of The Existing Asphalt Is Only An Estimate. Additional Depth Will
Require Additional Charges. The Removal Of The Asphalt Has Been Bid For That
Function
Alone And Does Not Include Excavation Of The Base Or Sub-base. If At The Time Of
Removal, It Is Determined That Water Has Weakened Either The Base Or Sub-base,
Additional Charges Would Be Required To Correct The Unforeseen Problem. If Upon
The
Removal Of The Asphalt, It Is Found That Structures Exist Below The Surface, Such
As
Concrete Footings, Abandoned Pipes, Metal Supports, Etc., An Additional Charge
Would Be
Required To Remove These Obstructions If They Would Impede Or Prohibit Grade
Consistencies. Sunland Asphalt Will Not Be Held Liable For Any Underground Cables,
Electrical Lines, Water Lines Or Any Other Underground Obstruction, Not Buried At
Least 18
Inches Below Existing Finished Grade.
Stripe Per Existing Layout

Project Date Range: 9/1/2020 **TO** 11/1/2020

Total Project Cost: \$26,410.80 **Adjacent Ways Cost:** \$15,705.30

Board Meeting Date:

Validation Status: No Review Required

Staff Analysis:

Board Decision: