



775 W. Elwood Street
Phoenix, AZ 85041
(p) 602.323.2800 (f) 602.910.3224

| | | | |
|--------------------------|--------------------------------------|--------------------|--------------|
| To: | Florence Unified School District #1 | Contact: | Mark Gomes |
| Address: | PO Box 2850 Florence, AZ 85132 US | Phone: | 480 474 6100 |
| | | Fax: | 520 868 2342 |
| Project Name: | Florence High School | Bid Number: | PH006303 |
| Project Location: | 1000 S Main St, Florence, AZ | Bid Date: | 6/9/2020 |

Bid in Accordance with the 1 GOVERNMENTAL PROCUREMENT ALLIANCE (1GPA)
Contract #17-16P-05 – Asphalt and Related Surfaces - Awarded May 2, 2019
UNIT PRICE BREAKDOWN CAN BE PROVIDED UPON REQUEST – ZONE #1

| Item Description | Total Price |
|---|-------------|
| <u>Remove And Replace Asphalt Repairs</u> Provide Traffic Control And Barricades During Our Scope Of Work. Make Necessary Saw cuts. Remove Approx. 5,181 Square Feet Of Failed Asphalt To A Depth Of 3". Compact Existing Base And Pave With 3" Of 1/2" MAG Asphaltic Surface Course. | \$17,545.00 |
| This Proposal Is Based On Performing The Work In 1 Phase/Mobilization. | |
| <u>Crack Seal / Type II Polymer Modified Slurry Seal / Pavement Markings</u> Provide Traffic Control And Barricades During Our Scope Of Work. Power Clean With High Volume Air As Needed And Seal All Cracks 1/4" And Larger With Crafcro PolyFlex III Crack Sealant. (Alligatored Areas Not Included.) Clean And Prepare Surface And Apply A MAG Polymer Modified Type II Slurry Seal At A Rate Of 16 To 18 Lbs. Of Aggregate Per Square Yard On Approx. 14,426 Square Yards. Roll With A Pneumatic Rubber Tired Roller As Needed. Slurry Seal Is Emulsified Asphalt Mixed With Specifically Graded Aggregate And 1/2% Of Portland Cement Per Square Yard. The Slurry Seal Is Applied Approximately 1/4" Inch In Thickness As Listed In The MAG Uniform Standard Specifications. The Elimination Of Any Existing Drainage Problem Or Reflective Cracking Is Not Intended Or Guaranteed. Power Steering Marks And Minor Raveling Are Normal And Should Not Be Cause For Undue Concern. Areas Not Accessible To A Slurry Seal Machine Will Be Done By Hand And It Will Have A Different Texture Than Machine Laid Areas. Work Will Not Be Warranted Where Sealing Is Placed Over Oil Stained Asphalt Pavement. Layout And Stripe To Existing Pattern: 4 Standard ADA Stalls Using Blue & Yellow Latex Traffic Paint. 12 Standard Arrows Using White Latex Traffic Paint. 2 Standard Speed Bumps Painted Solid Using Yellow Latex Traffic Paint. 800 Ln. Ft. Of 4" Line Using Yellow Latex Traffic Paint. | \$59,272.00 |

This Proposal Is Based On Performing The Work In 1 Phase/Mobilization.

Total Bid Price: \$76,817.00

Notes:

- Estimated material taxes are included in total price. In order to hold pricing, this proposal must be signed and returned within 30 days from the bid date specified above.
- Material pricing is good through 08-31-2020.

- The depth of the existing asphalt is only an estimate. Additional depth may require additional charges. The removal of the asphalt has been bid for that function alone and does not include excavation of the base or subbase. If at the time of the removal, it is determined that contamination of water has weakened either the base or the subbase, additional charges would be negotiated to correct the unforeseen problem. If upon the removal of the asphalt, it is found that structures exist below such as concrete footings, abandoned pipes, metal supports, etc., an additional charge would be negotiated to remove these obstructions if they would impede or prohibit grade consistencies. Sunland Asphalt will not be held liable for any underground cables, electrical lines, water lines or any other underground obstruction not locatable or not buried to a depth less than 18" below the existing finished grade.
- Pricing excludes night/weekend work, permits, fees, bonds, notifications, QC testing, gate loops, painting bumper blocks, permanent signage, herbicide, water source, or survey/staking in price unless noted above. Any pre-existing ADA compliance issues are excluded from contract unless specifically stated in proposal.
- Additional (downtime/mobilization) charges may result from delays beyond the control of Sunland Asphalt (or its subcontractors) which prohibit the above mentioned work from being completed as scheduled. (i.e., unmoved vehicles, disregard for Sunland traffic control, sanitation/delivery services, sprinkler runoff, etc.)

| | |
|--|--|
| <p>ACCEPTED:</p> <p>The above prices, specifications and conditions are satisfactory and are hereby accepted.</p> <p>Buyer: _____</p> <p>Signature: _____</p> <p>Date of Acceptance: _____</p> | <p>CONFIRMED:</p> <p>Sunland Asphalt & Construction, Inc.</p> <p>Authorized Signature: _____</p> <p>Project Consultant: Scott Hamilton (602) 288-5024 scott@sunlandasphalt.com</p> |
|--|--|

• **Sunland Asphalt Terms and Conditions:**

Contractor hereby accepts the terms of the attached Contract subject to the provisions as defined on the Contract Agreement as well as the Owner's Agreement with the terms set forth in this Addendum. This Addendum is attached hereto and incorporated herein by reference. If any of the terms of the Contract are inconsistent with the terms of this Addendum, then this Addendum shall be controlling and the parties shall be bound by the terms and conditions of this Addendum.

• 1. **PAYMENT**

Contractor shall be paid a monthly progress payment within 15 days after receipt of the payment by the Owner for the value of work performed. Final payment, including all retention, shall be due 15 days after the work described in the Proposal is substantially completed. No provision of this agreement shall serve to void the Contractor's entitlement to payment for properly performed work.

• 2. **INTEREST AND EXPENSES**

All sums not paid when due shall bear an interest rate of 1 1/2% per month or the maximum legal rate permitted by law, whichever is less, and all costs of collection, including a reasonable attorneys' fee, shall be paid by Owner.

• 3. **ATTORNEYS' FEES**

In the event of litigation or collection efforts by Contractor, the prevailing party shall be reimbursed for its reasonable attorneys' fees, which shall include all costs that would normally be passed through to the client, specifically but not limited to research charges, travel costs, expert witness costs, copying costs, mailing costs, facsimile costs, had-delivery costs, Federal Express or Express Mail costs, taxable costs and disbursements.

• 4. **CONTINUED PERFORMANCE**

Nothing in this subcontract agreement shall require the Contractor to continue performance if timely payments are not made to Contractor for suitably performed work.

• 5. **BACK CHARGES**

No back charges or claim of the Owner for services shall be valid except by an agreement in writing by the Contractor before the work is executed, except in the case of the Contractor's failure to meet any requirement of the subcontract agreement. In such event, the Owner shall notify the Contractor of such default, in writing, and allow the Contractor reasonable time to correct any deficiency before incurring any cost chargeable to the Contractor.

• 6. **WORK AREAS**

Owner is to prepare all work areas so as to be acceptable for Contractor work under the contract. Contractor will not be called upon to start work until sufficient areas are ready to insure continued work.

• 7. **TIME FOR PERFORMANCE**

Contractor shall be given a reasonable time in which to commence and complete the performance of the contract. Contractor shall not be responsible for delays or default where occasioned by any causes of any kind and extent beyond its control, including but not limited to: delay caused by Owner, architect and/or engineers, delays in transportation, shortages of raw materials, civil disorders, labor difficulties, vendor allocations, fires, floods, accident hazardous waste or controlled substances and acts of God. Contractor shall be entitled to equitable adjustment in the subcontract amount for additional costs due to unanticipated project delays or accelerations. Contractor shall not be obligated to provide any labor or materials outside the scope of work unless Owner shall first agree in writing to equitably adjust the subcontract amount to be paid Contractor.

• 8. **WORKMANSHIP**

All workmanship is guaranteed against defects for a period of one year from the date of substantial completion of installation. This warranty is in lieu of all other warranties, express or implied, including any warranties of merchantability or fitness for a particular purpose. The exclusive remedy shall be that Contractor will replace or repair any part of its work which is found to be defective. Contractor shall not be responsible for special, incidental or consequential damages. Contractor shall not be responsible for damage to its work by other parties or for improper use of equipment by other Standard of industry practice and will override strict compliance and strict performance.

• 9. **WORK HOURS**

Work called for herein is to be performed during Contractor's regular working hours as agreed to by the Owner and the Contractor.

• 10. **NOTICE**

Any notice or written claim required by the contract documents to be submitted to the Owner, on account of charges, extras, delays, acceleration, or otherwise, shall be furnished within a time period, and in a manner to permit the Owner to satisfy the requirements of the contract documents, notwithstanding any shorter time period otherwise provided.

• 11. **LIEN RIGHTS**

Nothing in this agreement shall serve to void Contractor's right to file a lien or claim on its behalf in the event that any payment to Contractor is not timely made.

• 12. **LABOR**

Contractor shall not be bound by any of Owner's labor agreements (in whole or in part).

• 13. **LIQUIDATED DAMAGES**

The Owner shall make no demand for liquidated damages for delays in any sum in excess of such amounts as may be specifically named in this Addendum and no liquidated damages may be assessed against Contractor for more than the amount paid by the Owner for unexcused delays to the event actually caused by the Contractor.

• 14. **SCHEDULE**

Contractor shall submit a schedule to Owner, Owner will review and notify Contractor of any schedule conflict. If Contractor finds it necessary to change his schedule, owner will give his best effort to meet this change in schedule. Contractor shall not be penalized for non-performance and will be paid for work performed.

• 15. **INSURANCE RESTRICTION**

Notwithstanding any provision to the contrary, Contractor shall maintain the types and limitations on insurance as shown on the attached certificate of insurance. Contractor is not required to waive any claims or rights of subrogation against the Owner or any others for losses and claims covered or paid by Owner's workers compensation or general liability insurance. Acceptance of the Certificate of Insurance constitutes acceptance of the insurance of Contractor, including any additional insured requirements. In addition, Contractor shall not provide completed operations under an additional insured requirement.

- 16. INDEMNITY, HOLD HARMLESS RESTRICTION
Any indemnification or hold harmless obligation of the Contractor shall extend only to claims relating to bodily injury and property damage and then only to that part or proportion of any claim damage, loss or defect that results from the negligence or intentional act of the indemnitor or someone for whom it is responsible. Contractor shall not under any circumstance have a duty to defend. Nothing in this agreement shall require the Contractor to indemnify any other party from any damages including expenses and attorneys' fees to persons or property for any amount exceeding the degree Contractor directly caused such damages. Contractor shall not be responsible for fines or assessments made against Owner and Contractor. Contractor retains all rights of subrogation. Contractor will not indemnify anybody for any actions except for Contractor's own negligence and only in the proportional amount of their negligence.
- 17. RIGHT TO RELY
Contractor shall rely on plans, drawings, specifications and other information provided by Owner, Owner, Architect or representatives of each. Contractor assumes no risk for unknown or unforeseen conditions not evident from the plans, drawings, specifications or other information provided to Contractor.
- 18. HAZARDOUS WASTE
Contractor shall have no obligation to handle (that is, to remove, treat or transport) any substance which is considered hazardous waste or substance under state or federal law ("hazardous waste"). Handling hazardous waste shall be outside the scope of work of this agreement. Title to all hazardous waste shall remain with others and shall not be property of Contractor.
- 19. DISPUTE RESOLUTION
Final determination of contract compliance and all dispute resolutions shall be handled in the jurisdiction and venue of Maricopa County, Arizona, and be governed by the laws of Arizona.

Florence High School
1000 S Main St
Florence, AZ 85132

Fire Lane
25' Wide



Sizes and locations of items indicated on map are approximate and are for informational purposes only. Please refer to the Project Proposal for exact sizes and locations.

Google Earth

Imagery Date: 11/5/2018 33°01'23.02" N 110°23'24.35" W elev 1518 ft eye alt 8426 ft


Florence High School
1000 S Main St
Florence, AZ 85132

Crackfill, Slurry, Restripe

R&R @ 3"



Sizes and locations of items indicated on map are approximate and are for informational purposes only. Please refer to the Project Proposal for exact sizes and locations.



Schedule of Values

| | | ADJACENT WAYS | | | | |
|---|---------------------------------------|---|------------------------------|---------------|--|------------------------|
| SFB AW 200-18 | | SCHEDULE OF VALUES | | | | |
| School District SFB Project Number Architect Name CM @ Risk Name County | | Florence Unified School District 2336 n/a Pinal | | | | |
| Permitting (Name of County/City) GMP | | Pinal Co./Florence, AZ n/a AW-Y <input type="checkbox"/> AW-N <input type="checkbox"/> | | | | |
| | = Cells to be completed - as required | Quantity | Cost per Unit (no markup) | District Cost | Other On-Site Funding (Adjacent Ways, etc.) | Off-Site Adjacent Ways |
| Div 1 | GENERAL CONDITIONS | | | | | |
| 01 00 00 | design services | | | | | |
| 01 50 00 | temporary facilities | | | | | |
| 01 56 19 | dust control | | | | | |
| 01 57 13 | track off pads | | | | | |
| | Division 1 total | | | \$0.00 | \$0.00 | \$0.00 |
| Div 2 | EXISTING CONDITIONS | | | | | |
| 02 21 13 | survey | | | | | |
| 02 41 13 | site demolition/removal | 5,181.00 | \$1.13 | | \$5,848.33 | |
| 02 60 00 | soil treatment | | | | | |
| | Division 2 total | | | \$0.00 | \$5,848.33 | \$0.00 |
| Div 3 | CONCRETE | | | | | |
| 03 00 00 | footings/walls (retaining) | | | | | |
| 03 00 00 | building | | | | | |
| 03 20 00 | rebar | | | | | |
| 03 30 53 | slabs | | | | | |
| 03 35 00 | sealed floors | | | | | |
| 03 40 00 | precast concrete | | | | | |
| | Division 3 total | | | \$0.00 | \$0.00 | \$0.00 |
| Div 4 | MASONRY | | | | | |
| 04 00 00 | masonry walls | | | | | |
| 04 00 00 | masonry columns | | | | | |
| 04 05 19 | rebar | | | | | |
| 04 22 00 | site masonry | | | | | |
| 04 22 00 | block fencing | | | | | |
| 04 43 00 | stonework | | | | | |
| | Division 4 total | | | \$0.00 | \$0.00 | \$0.00 |
| Div 5 | METALS | | | | | |
| 05 00 00 | miscellaneous steel | | | | | |
| 05 10 00 | structural steel | | | | | |
| 05 30 00 | metal decking | | | | | |
| 05 51 00 | stairs | | | | | |
| 05 70 00 | architectural steel | | | | | |
| | Division 5 total | | | \$0.00 | \$0.00 | \$0.00 |
| Div 6 | WOODS/PLASTICS/COMPOSITES | | | | | |
| 06 10 00 | rough carpentry structure | | | | | |
| 06 15 00 | wood decking | | | | | |
| 06 20 00 | finish carpentry | | | | | |
| 06 40 00 | millwork/casework | | | | | |
| 06 60 00 | plastic/glass fiber | | | | | |
| | Division 6 total | | | \$0.00 | \$0.00 | \$0.00 |
| Div 7 | THERMAL/MOISTURE | | | | | |
| 07 10 00 | waterproofing/dampproofing | | | | | |

Schedule of Values

| | = Cells to be completed - as required | Quantity | Cost per Unit | District Cost | Other On-Site Funding (Adjacent Ways, etc.) | Off-Site Adjacent Ways |
|---------------------------|---------------------------------------|----------|---------------|---------------|--|------------------------|
| | | | (no markup) | | | |
| 07 20 00 | building insulation | | | | | |
| 07 21 00 | foam roof | | | | | |
| 07 25 00 | weather barrier | | | | | |
| 07 31 00 | roof shingles | | | | | |
| 07 32 00 | roof tiles | | | | | |
| 07 50 00 | membrane roofing | | | | | |
| 07 60 00 | metal roof | | | | | |
| 07 60 00 | general sheet metal | | | | | |
| 07 72 00 | roof accessories | | | | | |
| 07 81 00 | sprayed fireproofing | | | | | |
| 07 84 00 | firestopping | | | | | |
| 07 95 00 | roof expansion joint | | | | | |
| 07 92 00 | joint sealants | | | | | |
| Division 7 total | | | | \$0.00 | \$0.00 | \$0.00 |
| Div 8 OPENINGS | | | | | | |
| 81 10 00 | doors & frames | | | | | |
| 08 33 00 | overhead doors | | | | | |
| 08 40 00 | storefronts | | | | | |
| 08 44 00 | curtain walls | | | | | |
| 08 50 00 | windows | | | | | |
| 08 60 00 | skylights | | | | | |
| 08 70 00 | hardware | | | | | |
| 08 71 13 | automatic doors | | | | | |
| 08 79 00 | knox box | | | | | |
| 08 80 00 | glass & glazing | | | | | |
| Division 8 total | | | | \$0.00 | \$0.00 | \$0.00 |
| Div 9 FINISHES | | | | | | |
| 09 24 00 | stucco/EIFS systems | | | | | |
| 09 20 00 | interior metal studs/gypsum board | | | | | |
| 09 22 00 | exterior metal stud framing | | | | | |
| 09 23 00 | decorative plaster | | | | | |
| 09 51 00 | acoustical ceilings | | | | | |
| 09 31 00 | ceramic tile | | | | | |
| 09 65 00 | resilient flooring | | | | | |
| 09 68 00 | carpet | | | | | |
| 09 64 00 | wood floors | | | | | |
| 09 67 00 | epoxy | | | | | |
| 09 80 00 | sound panels | | | | | |
| 09 90 00 | painting | | | | | |
| 09 77 00 | fiberglass reinforced panels | | | | | |
| Division 9 total | | | | \$0.00 | \$0.00 | \$0.00 |
| Div 10 SPECIALTIES | | | | | | |
| 10 11 00 | visual display boards | | | | | |
| 10 14 00 | signage | | | | | |
| 10 21 13 | toilet partitions & accessories | | | | | |
| 10 21 23 | cubicle track & curtain | | | | | |
| 10 22 26 | operable partitions/walls | | | | | |
| 10 26 00 | wall protection | | | | | |
| 10 44 00 | fire extinguishers & cabinets | | | | | |
| 10 50 00 | lockers | | | | | |
| 10 56 13 | storage shelving | | | | | |
| 10 73 00 | shelters | | | | | |
| 10 73 13 | awnings | | | | | |
| 10 73 13 | canopy/ramada | | | | | |
| 10 75 00 | flagpoles | | | | | |
| Division 10 total | | | | \$0.00 | \$0.00 | \$0.00 |
| Div 11 EQUIPMENT | | | | | | |

Schedule of Values

| | = Cells to be completed - as required | Quantity | Cost per Unit | District Cost | Other On-Site Funding (Adjacent Ways, etc.) | Off-Site Adjacent Ways |
|-------------------|---------------------------------------|----------|---------------|---------------|--|------------------------|
| | | | (no markup) | | | |
| 11 16 16 | floor safe | | | | | |
| 11 41 00 | kitchen equipment | | | | | |
| 11 51 00 | library equipment | | | | | |
| 11 52 00 | audio/visual equipment | | | | | |
| 11 52 13 | projection screens | | | | | |
| 11 53 13 | fume hoods | | | | | |
| 11 61 43 | stage curtain/equipment | | | | | |
| 11 66 00 | sports/PE equipment | | | | | |
| 11 68 00 | playground equipment | | | | | |
| 11 68 23 | site basketball courts | | | | | |
| 11 68 33 | ballfield backstop | | | | | |
| 11 68 33 | sports fields | | | | | |
| Division 11 total | | | | \$0.00 | \$0.00 | \$0.00 |
| Div 12 | FURNISHINGS | | | | | |
| 12 20 00 | window coverings | | | | | |
| 12 31 00 | metal casework | | | | | |
| 12 32 16 | plastic laminate casework | | | | | |
| 12 61 00 | auditorium seating | | | | | |
| 12 93 13 | bike racks | | | | | |
| 12 93 23 | trash enclosures | | | | | |
| Division 12 total | | | | \$0.00 | \$0.00 | \$0.00 |
| Div 13 | SPECIAL CONST | | | | | |
| 13 00 00 | equipment/storage enclosures | | | | | |
| 13 11 00 | swimming pools | | | | | |
| 13 34 16 | bleachers | | | | | |
| 13 34 19 | metal buildings | | | | | |
| Division 13 total | | | | \$0.00 | \$0.00 | \$0.00 |
| Div 14 | CONVEYING | | | | | |
| 14 00 00 | material handling | | | | | |
| 14 20 00 | elevators | | | | | |
| 14 42 00 | wheelchair lifts | | | | | |
| Division 14 total | | | | \$0.00 | \$0.00 | \$0.00 |
| Div 21 | FIRE SUPPRESSION | | | | | |
| 21 10 00 | fire protection/sprinklers | | | | | |
| Division 21 total | | | | \$0.00 | \$0.00 | \$0.00 |
| Div 22 | PLUMBING | | | | | |
| 22 11 00 | supply piping | | | | | |
| 22 13 00 | waste water piping | | | | | |
| 22 31 00 | water treatment (softener) | | | | | |
| 22 32 00 | water treatment (filtered) | | | | | |
| 22 35 00 | water heaters | | | | | |
| 22 42 00 | plumbing fixtures | | | | | |
| Division 22 total | | | | \$0.00 | \$0.00 | \$0.00 |
| Div 23 | MECHANICAL | | | | | |
| 23 07 13 | mechanical insulation | | | | | |
| 23 50 00 | HVAC - central plant (cooling) | | | | | |
| 23 60 00 | HVAC - central plant (heating) | | | | | |
| 23 76 00 | HVAC - evaporative | | | | | |
| 23 80 00 | HVAC - package units | | | | | |
| 23 81 26 | HVAC - split system | | | | | |
| Division 23 total | | | | \$0.00 | \$0.00 | \$0.00 |
| Div 25 | INTEGRATED AUTOMATION | | | | | |
| 25 50 00 | EMS | | | | | |
| Division 25 total | | | | \$0.00 | \$0.00 | \$0.00 |
| Div 26 | ELECTRICAL | | | | | |
| 26 10 00 | site electrical | | | | | |
| 26 10 00 | electrical | | | | | |

Schedule of Values

| | = Cells to be completed - as required | Quantity | Cost per Unit | District Cost | Other On-Site Funding (Adjacent Ways, etc.) | Off-Site Adjacent Ways |
|---------------|---|--------------------|---------------|-----------------|--|------------------------|
| | | | (no markup) | | | |
| 26 30 00 | generators | | | | | |
| 26 56 00 | exterior lighting | | | | | |
| | Division 26 total | | | \$0.00 | \$0.00 | \$0.00 |
| Div 27 | COMMUNICATIONS | | | | | |
| 27 20 00 | data cabling | | | | | |
| 27 24 00 | TV cabling | | | | | |
| 27 30 00 | intercom | | | | | |
| 27 32 13 | communications/phone | | | | | |
| | Division 27 total | | | \$0.00 | \$0.00 | \$0.00 |
| Div 28 | SAFETY AND SECURITY | | | | | |
| 28 10 00 | security system | | | | | |
| 28 20 00 | surveillance/alarm | | | | | |
| 28 31 00 | fire alarm system | | | | | |
| | Division 28 total | | | \$0.00 | \$0.00 | \$0.00 |
| Div 31 | EARTHWORK | | | | | |
| 31 23 00 | earthwork/mass excavation | | | | | |
| 31 23 00 | import/export dirt | | | | | |
| 31 31 00 | soil treatment - termite | | | | | |
| | Division 31 total | | | \$0.00 | \$0.00 | \$0.00 |
| Div 32 | EXTERIOR IMPROVEMENTS | | | | | |
| 32 00 00 | parking | 14,426.00 | \$3.42 | | \$49,357.50 | |
| 32 00 00 | unusual site conditions | | | | | |
| 32 10 00 | asphalt/paving | 5,181.00 | \$2.31 | \$0.00 | \$11,948.67 | |
| 32 13 00 | site concrete (curb & valley) | | | | | |
| 32 13 00 | sidewalks | | | | | |
| 32 17 00 | striping/signage | | | \$0.00 | \$1,200.00 | |
| 32 31 13 | chainlink fencing | | | | | |
| 32 31 19 | wrought iron fencing | | | | | |
| 32 32 00 | retaining walls | | | | | |
| 32 80 00 | irrigation | | | | | |
| 32 90 00 | landscaping | | | | | |
| | Division 32 total | | | \$0.00 | \$62,506.17 | \$0.00 |
| Div 33 | UTILITIES | | | | | |
| 33 00 00 | site utilities | | | | | |
| 33 21 00 | wells | | | | | |
| 33 32 16 | lift station | | | | | |
| 33 36 00 | septic system | | | | | |
| 33 40 00 | stormwater/drainage | | | | | |
| 33 49 23 | drywells | | | | | |
| | Division 33 total | | | \$0.00 | \$0.00 | \$0.00 |
| | Subtotal | \$68,354.50 | | \$0.00 | \$68,354.50 | \$0.00 |
| | Contractor Fee | | \$7,694.33 | \$0.00 | \$7,694.33 | |
| | Contactor Contingency | | \$0.00 | | | |
| | Builders Risk/Liability Insurance | | \$0.00 | | | |
| | Performance & Payment Bonds | | \$768.17 | \$0.00 | \$768.17 | |
| | Sales Tax | | \$0.00 | \$0.00 | \$0.00 | |
| | Subtotal | \$76,817.00 | | \$0.00 | \$76,817.00 | \$0.00 |
| | Grand Guaranteed Maximum Price (GMP) | | | Proposal | | |