

Current Status: Resubmitted 4/16/2021 3:44:17 PM **Submission ID:** 2529

Initial Submission Date: 4/13/2021

Resubmission Date: 4/16/2021

District Name: Washington Elementary District

Contact Person: Mike Kramer

Contact Phone: 6027577024

Contact Email: mike.kramer@wesdschools.org

School: Sahuaro School

Site Address: 12835 N 33rd Ave, Phoenix, AZ 85029

Project Title: Sahuaro School - Fire Lane Project

Project Detail: Adjacent ways funded: Construct new concrete fire lane with new MAG class 'A', 8-inch pavement with 10-inch turn-downs with 6x6-Q1.4 x W1.4 over 8-inch prepared subgrade. Joint as per plan and details. Dowel connect to existing concrete on all existing sides. Subgrade preparation as per MAG specifications Section 301. Concrete pavement as per MAG specifications Section 324.

School district funded: (1) new 6" DIP fire line and (1) new fire hydrant.

Project Date Range: 5/26/2022 **TO** 7/22/2022

Total Project Cost: \$794,280.31 **Adjacent Ways Cost:** \$663,030.31

Board Meeting Date:

Validation Status: Review Pending

Staff Analysis: reviewed and written up for May board meeting.
4/16/21: please add the engineer estimate as backup.

Board Decision: