

Current Status: Processing Complete 5/6/2021 3:20:16 PM **Submission ID:** 2542

Initial Submission Date:

Resubmission Date:

District Name: Littleton Elementary District

Contact Person: Michael Fisher

Contact Phone: 623-478-5690

Contact Email: fisher.mike@littletonaz.org

School: Littleton Elementary School

Site Address: 1252 S Avondale Blvd, Avondale, AZ

Project Title: Littleton Elementary School District #65: Littleton-Remove And Replace Asphalt Repairs

Project Detail: Adjacent Ways
Remove And Replace Asphalt Repairs
Provide Traffic Control And Barricades During Our Scope Of Work.
Make Necessary Saw cuts.
Remove Approx. 80 Square Feet Of Failed Asphalt To A Depth Of 3 Inches.
Compact Existing Base And Pave With 3 Inches Of 1/2 Inch MAG Asphaltic Surface Course.

This Proposal Is Based On Performing The Work In 1 Phase/Mobilization.

Crack Seal / Apply MasterSeal Sealer / Pavement Markings
Provide Traffic Control And Barricades During Our Scope Of Work.
Power Clean With High Volume Air As Needed And Seal All Cracks 1/4 In And Larger With Crafcro PolyFlex III Crack Sealant.
(Alligatored Areas Not Included.)
Power Sweep/clean Asphalt Surface.
Furnish And Apply Two (2) Coats Of MasterSeal Sealer By Spray Application On Approximately 112,990 Square Feet.
(Adhesion Or Bonding Of Seal Coat Materials Is Not Warranted In Areas Exposed To Automotive Fluids And/or Other Spills.)

Re-Stripe To Existing Pattern:
Re-stripe 1,600 In. ft. of 4 inch line.
Paint 7 arrows on pavement using white latex traffic paint.
Stencil 8 each NO PARKING using 12 inch characters on the asphalt using white paint.
Stencil 1 each BUSES ONLY using 24 inch characters on the asphalt using white paint.
Stencil 4 each ONLY using 60 inch characters on the asphalt using white paint.
Paint 6 each stop bars using white paint.

Project Date Range: 6/1/2021 **TO** 8/31/2021

Total Project Cost: \$21,840.00 **Adjacent Ways Cost:** \$14,751.00

Board Meeting Date:

Validation Status: No Review Required

Staff Analysis:

Board Decision: