

Current Status: Processing Complete 5/6/2021 3:47:27 PM **Submission ID:** 2544
Initial Submission Date:
Resubmission Date:
District Name: Littleton Elementary District
Contact Person: Michael Fisher
Contact Phone: 6234785690
Contact Email: fisher.mike@littletonaz.org
School: District Project
Site Address: 1600 S 107th Ave, Avondale, AZ
Project Title: Littleton Elementary School District #65: District Office-Remove And Replace Asphalt Repairs

Project Detail: Adjacent Ways
Remove And Replace Asphalt Repairs
Provide Traffic Control And Barricades During Our Scope Of Work.
Make Necessary Saw cuts.
Remove Approx. 2,018 Square Feet Of Failed Asphalt To A Depth Of 3 Inches.
Compact Existing Base And Pave With 3 Inches Of 1/2 Inch MAG Asphaltic Surface Course.

This Proposal Is Based On Performing The Work In 1 Phase/Mobilization.

Crack Seal / Apply MasterSeal Sealer / Pavement Markings
Provide Traffic Control And Barricades During Our Scope Of Work.
Power Clean With High Volume Air As Needed And Seal All Cracks 1/4 In And Larger With Crafcro PolyFlex III Crack Sealant.
(Alligatored Areas Not Included.)
Power Sweep/clean Asphalt Surface.
Furnish And Apply Two (2) Coats Of MasterSeal Sealer By Spray Application On Approximately 119,700 Square Feet.
(Adhesion Or Bonding Of Seal Coat Materials Is Not Warranted In Areas Exposed To Automotive Fluids And/or Other Spills.)

Re-Stripe To Existing Pattern:
Re-stripe 2,184 In. ft. of 4" line.
Paint 10 arrows on pavement using white latex traffic paint.
Paint approx. 996 Ln. Ft. of curb top & face with red paint.
Paint 28 each FIRE LANE NO PARKING stencils on the face of curb using white paint.

Project Date Range: 6/1/2021 **TO** 8/31/2021
Total Project Cost: \$31,709.00 **Adjacent Ways Cost:** \$27,321.00

Board Meeting Date:
Validation Status: No Review Required

Staff Analysis:

Board Decision: