MAINLINE

SCALE:1"=40'

N

AB-20-06 | AB-20-07
AB-20-11 | AB-20-10

W ELWOOD ST

S 55TH AVE

W ILLINI ST

PH259193
PH259192
PH259191
PH259190
PH259189

TO PH259194

TO PD-1001

1
E-PDP-1018

RAS

COR No. 25 Location

CUSTOMER NOTE:

CUSTOMER TO MODIFY
FENCE AROUND SWITCHES

CONDUIT SPLICE POINT

-CUSTOMER TO EXCAVATE 4'x8' WORK PIT
-CUSTOMER TO EXPOSE CONDUIT AND
CALL 602-236-0676 FOR HOT PHASE I.D.
-SRP TO I.D. CONDUITS AND REMOVE WIRE
FROM PDP-1018 TO PD-1017
-CUSTOMER TO SPLICE CONDUIT
-SRP TO INSPECT CONDUIT SPLICE
-CUSTOMER TO BACKFILL & RESTORE SURFACE

2
C-P-1102
500-
277/480V

C-2-USC750A (SRP)
C-2-4"K (CUST)
28'

600A
277/480V
3Ø-4W
27,452 AFC

3'
F/C

45°

4' F/C

3
C-P-1103
2500-
277/480V

12' F/C

C-PB (CUST)

2'
F/C

C-18-USC750A (SRP)
C-25-4"K (ENCASED BY CUST)
65'

CUSTOMER TO PROVIDE
12' GATE ACCESS TO SES

3600A
277/480V
3Ø-4W
59,990 AFC

±48' IRR.

38' PROP. R/W
24' B/C
29' BS/W

4 C-PD-1104
600A GOS

5 C-PD-1105
600A GOS

83'

45°

45°

130.5'

6
CONDUIT SPLICE
POINT (BY CUST)

2'WTR
±24.5' B/C
33' R/W
±29.5' ELEC.

7
E-PD-1017
600A GOS

E-PD-1016

E-P-1033
25- 257870 -C

145'

152'

±29' COMM.

TO PD-1034
TO PH259188

CONTACTS:

DESIGN CONSULTANT:
LUZ JOHNSON
OFFICE:(602)236-4809
MOBILE:(602)332-0045

PROJECT LEADER:
WES SHREVE
MOBILE:(602)316-3773

INSPECTIONS:
OFFICE:(602)236-0676

CONSTRUCTION CONSULTANT:
TONY CROCKETT
MOBILE:(602)448-1568

NATURAL GAS YES ☐ NO ☒

JOB NAME MARICOPA INSTITUTE OF TECHNOLOGY
ADDRESS/LOCATION 3900 S 55TH AVE
CONTACT MICHAEL SUNDBERG PHONE 602-319-5195
BILLING ACCT NO.
FIS JO MAP 1/4 SW S20 T1N R2E
40/ACRE AB-20-11 COORDS 7 3/8E - 2 7/16N
AMP WO T3279162 AMP VERSION
COST CENTER 22640
ROUTING CODE DDY+10

Contact Arizona 811 at least two full working days before you begin excavation
Call 811 or click Arizona811.com

SHEET NUMBER 3 OF 7

FOR CUSTOMER APPROVAL
NOT FOR CONSTRUCTION

22x34frm.JD2 01-23-2019

SRP PROPRIETARY