

**Current Status:** Resubmitted 4/12/2022 5:55:12 AM **Submission ID:** 2624

**Initial Submission Date:** 4/11/2022

**Resubmission Date:** 4/12/2022

**District Name:** Washington Elementary District

**Contact Person:** Mike Kramer

**Contact Phone:** 6027577024

**Contact Email:** mike.kramer@wesdschools.org

**School:** Sahuaro School

**Site Address:** 12835 N 33rd Ave, Phoenix, AZ 85029

**Project Title:** Sahuaro School - Fire Lane Project

**Project Detail:** Adjacent ways funded: Construct new concrete fire lane with new MAG class 'A', 8-inch pavement with 10-inch turn-downs with 6x6-Q1.4 x W1.4 over 8-inch prepared subgrade. Joint as per plan and details. Dowel connect to existing concrete on all existing sides. Subgrade preparation as per MAG specifications Section 301. Concrete pavement as per MAG specifications Section 324.

School district funded: (1) new 6" DIP fire line and (1) new fire hydrant.

**Project Date Range:** 5/22/2023 **TO** 7/21/2023

**Total Project Cost:** \$1,904,597.13 **Adjacent Ways Cost:** \$1,452,870.42

**Board Meeting Date:**

**Validation Status:** Review Pending

**Staff Analysis:** returning per district request so they can add updated OPC estimate

**Board Decision:**