



PROPOSAL

Client Isaac School District No. 5
Contact Mr. David Morales Jr.
Date November 10, 2022
Project Alta E. Butler Elementary – Drop-off Lane Asphalt Replacement
1GPA 1GPA Procurement #18-15PV-11

In response to your request, RYTAN Construction is pleased to offer this bid proposal pricing for the above referenced project.

Scope of Work:

1. Remove and haul off approximately 1,067 SY's of existing asphalt at small parking lot and bus drop-off area.
2. Light grade and compact existing base.
3. Pave with ½" asphalt to an average finished depth of 3" to 4" after compaction.
4. Work to be completed in three (3) move-ins.
5. All necessary on-site barricades and traffic control shall be provided.
6. Clean-up all areas and dispose of all debris off-site.

Exclusions: Payment and performance bonds, plans, permits, engineering, driveways, and any work not expressly included above. Pricing good for 30 days from proposal date.

TOTAL PRICE with tax: \$92,526.00

Sincerely,

Sean Murphy

Sean Murphy
Cell: 480-414-0906
smurphy@rytanconstruction.com