

Current Status: Submitted 11/16/2022 4:44:21 PM **Submission ID:** 2681

Initial Submission Date: 11/16/2022

Resubmission Date:

District Name: Maricopa Unified School District

Contact Person: Robert Duran

Contact Phone: 5205685120

Contact Email: rduran@musd20.org

School: Maricopa Wells Middle School

Site Address: 45725 W Honeycutt Ave, Maricopa, AZ 85139

Project Title: MUSD - Maricopa Wells Fire-Lane Paving (On-Site & Adjacent Ways)

Project Detail: REMOVALS & ASPHALT PAVING (WSP): 22,040.00 SF; Existing Decomposed Granite And Dirt Will Be Milled To ~ 9" Depth. Spoils Will Be Hauled Off And Legally Disposed Of. Exposed Base Will Be Graded And Compacted, Then Six Inches Of New MAG Spec ABC Will Be Installed And Compacted. Following ABC, New MAG Spec Hot Asphalt Mix Will Be Installed 3 Inch Thick. Two Speed Humps (12"x19") Will Be Constructed At Each Gate.

ADJUSTMENTS: Valves And Manholes Will Be 10.00 EACH; Adjusted To The Pavement Elevation And Set In New Concrete Collars. Includes 8-Water Valves And 2-Manholes.

STRIPING: Pavement Markings Will Be 1.00 LS; Repainted To The Existing Layout With Permanent Traffic Marking Paint. Curbing Will Be Painted Red On Face And Top And "FIRE LANE" Stencils Added.

Project Date Range: 12/19/2022 **TO** 1/19/2023

Total Project Cost: \$129,118.00 **Adjacent Ways Cost:** \$129,118.00

Board Meeting Date:

Validation Status: Review Pending

Staff Analysis:

Board Decision: