

Current Status: Submitted **4/3/2023 8:17:46 AM** **Submission ID:** 2708

Initial Submission Date: 4/3/2023

Resubmission Date:

District Name: Chandler Unified District

Contact Person: Kyle Walker

Contact Phone: 480-536-0745

Contact Email: walker.kyle@cusd80.com

School: Perry High School

Site Address: 1919 E Queen Creek Rd, Gilbert, AZ 85297

Project Title: Ingress and Egress Improvements

Project Detail: Create loop and additional space to ensure safe ingress/egress from public way to main school entrance.

Grade & Pave

Make necessary saw cuts to existing asphalt/concrete.

Remove & haul approx 100 LF of single curb concrete.

Remove & haul approx. 800 SF of concrete sidewalk & curbing.

Excavate 7" of existing DG & subgrade.

Haul off and dispose of any excess material.

Prepare subgrade and compact to proper densities.

Install 4" of aggregate base course and compact with a steel drum vibratory roller.

Finish roll and leave barricaded off new asphalt.

Install approx. 230' of curb and gutter per MAG 220.

Install approx. 60' of single curb per MAG 222.

Install approx. 90' of sidewalk with curb & gutter per MAG.

Place and compact new 1/2" mix asphalt using a self propelled paving machine and vibratory steel drum rollers.

Layout & stripe.

Project Date Range: 5/30/2023 **TO** 7/31/2023

Total Project Cost: \$76,030.95 **Adjacent Ways Cost:** \$76,030.95

Board Meeting Date:

Validation Status: Review Pending

Staff Analysis:

Board Decision: