

Current Status: Submitted

6/12/2023 4:37:58 PM

Submission ID: 2748

Initial Submission Date: 6/12/2023

Resubmission Date:

District Name: Tolleson Union High School District

Contact Person: Gabriel Martinez

Contact Phone: (623)478-4102

Contact Email: gabriel.martinez@tuhsd.org

School: Tolleson Union High School

Site Address: 9419 W. Van Buren St.
Tolleson, AZ 85353

Project Title: Tolleson Union HS- Paving Project

Project Detail: Make Necessary Saw Cuts. Remove Approx. 765 Square Feet Of Failed Asphalt To A Depth Of 3 Inches. Compact Existing Base And Pave With 3 Inches Of 1/2 Inch MAG Asphaltic Surface Course. Mill/Grade/Pave
Mill Approx. 16,835 Square Feet Of Existing Asphalt To A Depth Of 3 Inches. Fine Grade Approx. 16,835 Square Feet Of Existing Base, Add Moisture, And Compact To Grade. Pave Approx. 16,835 Square Feet With 1/2 Inch MAG Asphalt Surface Course To An Average Finished Depth Of 3 Inches. Raise 5 Sewer Cleanouts, Flush With New Asphalt Elevation Including Concrete Collar. Add 4 Percent Cement To Approx. 16,835 Square Feet. Blend To A Depth Of 12 Inches. Power Clean With High Volume Air As Needed And Seal All Cracks 1/4 In And Larger With Crafcro PolyFlex III Crack Sealant. Stripe To Existing Pattern:
Curb Painting 1,300 Linear Feet
Stripe Hash Out 1,575 Linear Feet
Stripe Yellow Center Line 700 Linear Feet

Project Date Range: 6/12/2023 **TO** 9/12/2023

Total Project Cost: \$174,669.40 **Adjacent Ways Cost:** \$118,686.72

Board Meeting Date:

Validation Status: Review Pending

Staff Analysis:

Board Decision: