

Current Status:	Processing Complete	8/25/2023 12:52:27 PM	Submission ID:	2771
Initial Submission Date:				
Resubmission Date:				
District Name: Maricopa Unified School District				
Contact Person: Robert Duran				
Contact Phone: 5205685100				
Contact Email: rduran@musd20.org				
School: Desert Wind Middle School				
Site Address: 35565 Honeycutt Road, Maricopa				
Project Title: MUSD - Desert Wind MS - Fire Lane PM				
Project Detail: <div>MOBILIZATION - CRACK SEALING: 1.00 LS CRACK SEALING: Cracks 1/4" And Wider Will Be Blown Out 1,000.00 LB With Compressed Air And Then Sealed With Hot-Applied Polymer Sealant. WIDE CRACK SEALING: Cracks 1" And Wider Will Be Blown 350.00 LB Out With Compressed Air And Then Filled With MASTIC Gap-C Sealer With Aggregate. GATORPAVE PATCH REPAIR: Distressed Areas Will Be 416.00 SF Cleaned And Tacked With Asphalt Binder, Then A Thin Layer Of MAG Spec Hot Asphalt Mix Will BE Installed. MOBILIZATION - STRIPER 1.00 LS STRIPING: Pavement Markings Will Be Repainted To The 1,609.00 LF</div>				
Project Date Range:	9/25/2023	TO	10/6/2023	
Total Project Cost:	\$5,808.06	Adjacent Ways Cost:		\$5,808.06
Board Meeting Date:				
Validation Status: No Review Required				
Staff Analysis:				
Board Decision:				