

<b>Current Status:</b>	Resubmitted	12/14/2023 9:46:43 AM	<b>Submission ID:</b>	2790
<b>Initial Submission Date:</b>	11/21/2023			
<b>Resubmission Date:</b>	12/14/2023			
<b>District Name:</b>	Washington Elementary District			
<b>Contact Person:</b>	Tim Woodward			
<b>Contact Phone:</b>	6023472835			
<b>Contact Email:</b>	Tim.Woodward@wesdschools.org			
<b>School:</b>	Palo Verde Middle School			
<b>Site Address:</b>	7502 N. 39th Ave Phoenix, AZ 85051			
<b>Project Title:</b>	Palo Verde - Fire Lane			
<b>Project Detail:</b>	Adjacent ways funded. Construct new fire lane with concrete driveway as per COP, 6" vertical curb and gutter as per MAG Std Dtl 200 Type "A"; 6" Vertical curb MAG Std Dtl 222 Type "A"; 4" concrete roll curb as Per MAG Std Dtl 222 Type "D"; concrete sidewalk; fire land concrete w/reinforcement; 5" asphaltic concrete pavement over 8" ABC (COP ROW); offsite slurry & seal coat per COP; fire lane asphalt - 3-inch AC over 8-inch AB. See included engineering documentation for further details.			
<b>Project Date Range:</b>	3/16/2024	<b>TO</b>	6/30/2024	
<b>Total Project Cost:</b>	\$1,854,388.33	<b>Adjacent Ways Cost:</b>	\$1,143,263.03	
<b>Board Meeting Date:</b>				
<b>Validation Status:</b>	Review Pending			
<b>Staff Analysis:</b>	11/26/23: Please use the SFD Schedule of Values form. Do not add any columns. All other info looked acceptable (assuming the ADJW work scope is red portion and District on the blue portion) 12/6/23: returned for info requested per District request. An item was overlooked in submission. 12/13/23: please revise the SOV to show all the offsite ADJW costs in the onsite ADJW column			
<b>Board Decision:</b>				