

Current Status: Resubmitted 3/25/2024 7:08:09 AM **Submission ID:** 2816

Initial Submission Date: 3/5/2024

Resubmission Date: 3/25/2024

District Name: Creighton Elementary District

Contact Person: Scott Wells

Contact Phone: 6029080623

Contact Email: swells@creightonschools.org

School: Warehouse & Support Services

Site Address: 2802 E. McDowell Rd.

Project Title: Bus, Fuel Pump and Fire Access

Project Detail: 30 year old asphalt and concrete drive for school bus, warehouse deliveries and maintenance vehicles egress and ingress to transportation yard and fuel pumps. Full depth mill and haul off existing asphalt. Fine Grade and compact existing base as necessary. Asphalt Paving tack all edges of existing curb and/or asphalt as necessary. Place and compact new mix asphalt using a self propelled paving machine and vibratory steel drum rollers. Speed bump install 3 speed bumps. Re-stripe to match existing layout. Price does not include red curb fire lane striping unless otherwise noted.

Project Date Range: 5/28/2024 **TO** 6/30/2024

Total Project Cost: \$703,381.96 **Adjacent Ways Cost:** \$238,513.62

Board Meeting Date:

Validation Status: Review Pending

Staff Analysis: 3/7/24: please attach a filled out SOV form from SFD webpage. Also, please ensure the ADJW portion shown in red encompasses what a fire lane or emergency vehicle can navigate (as in look again at the pointy red areas)

Board Decision: