

Current Status: Processing Complete 6/3/2024 8:40:23 AM **Submission ID:** 2854

Initial Submission Date:

Resubmission Date:

District Name: Cave Creek Unified District

Contact Person: Michael Santina

Contact Phone: 4805752055

Contact Email: msantina@ccusd93.net

School: Lone Mountain Elementary School

Site Address: 5250 E Montgomery Rd.,
Cave Creek, AZ 85331

Project Title: LMES Sealcoat

Project Detail: Adjacent Ways

Crack Seal / Apply PMM Sealer / Pavement Markings
Provide Traffic Control And Barricades During Our Scope of Work Power Clean With High Volume Air As Needed And Seal All Cracks 1/4 In And Larger With Crafcro PolyFlex III Crack Sealant. (Alligatored Areas Not Included.)
Power Sweep/clean Asphalt Surface.
Furnish And Apply Two (2) Coats Of PMM Sealer By Spray Application On Approximately 42,495 Square Feet. SealMaster PMM Has 3-5 Lbs. Of Aggregate Per Gallon Blended With 2 Percent Polymer Modified Latex. (Adhesion Or Bonding Of Seal Coat Materials Is Not Warranted In Areas Exposed To Automotive Fluids And/or Other Spills.)
Stripe To Existing Pattern:
Stripe 1,346 LF Of Cross Hash Markings Using Red Line On Asphalt Or Yellow On Concrete.
Paint 19 Arrows On Pavement Using White Latex Traffic Paint.
Stencil 124 Individual 12 Inch Characters On The Asphalt Using White Paint. Paint Approx. 1,190 Ln. Ft. Of Curb Top & Face With Red Paint.
This Proposal Is Based On Performing The Work In 1 Phase/Mobilization. Standard Funding

Project Date Range: 7/1/2024 **TO** 9/1/2024

Total Project Cost: \$23,077.03 **Adjacent Ways Cost:** \$23,077.03

Board Meeting Date:

Validation Status: No Review Required

Staff Analysis:

Board Decision: