



AZROC# 111922 | AZROC# 095189

3030 S. 7TH STREET, PHOENIX, AZ 85040
PHONE: 602.323.2800 | WWW.SUNLANDASPHALT.COM

To:	Cave Creek Unified School District #93	Contact:	Mike Santana
Address:	33016 N 60th St Cave Creek, AZ 85327 US	Phone:	480 575 2055
		Fax:	480 488 2474
Project Name:	Desert Arroyo Middle School	Bid Number:	PH021078
Project Location:	33401 N 56th Street, Cave Creek, AZ	Bid Date:	7/24/2023

Bid in Accordance with the 1 GOVERNMENTAL PROCUREMENT ALLIANCE (1GPA)
 Contract #22-15P-04 – Asphalt and Related Surfaces - Awarded June 28, 2022
 UNIT PRICE BREAK DOWNS ARE AS FOLLOWS – PER ZONE IDENTIFIED BELOW,
 HIGHLIGHTED PRICES INDICATE AUTHORIZED UNIT PRICE REDUCTIONS PER RFP

Item Description	Total Price
Adjacent Ways	
<u>Mill / Grade / Pave - BUDGET BID</u>	
Provide Project Management Including Travel Time, Meetings, Paperwork, And Billings. Provide The Following Limited Construction Permits: - Dust Control Permit, Water Meter Permit And Water Buy. Provide Traffic Control And Barricades During Our Scope Of Work. GPS & Pre-lower Utilities Prior To Milling. Mill Approx. 57,500 Square Feet Of Existing Asphalt To A Depth Of 3 Inches. Millings Will Be Hauled Offsite. Proposal Is Based On A 3 Inch Mill Depth, If Asphalt Is Found To Be Deeper Than 3 Inches, Additional Charges May Be Incurred. Fine Grade Approx. 57,500 Square Feet Of Existing Base, Add Moisture, And Compact To Grade. Pave Approx. 57,500 Square Feet With 1/2 Inch MAG Asphalt Surface Course To An Average Finished Depth Of 3 Inches After Compaction With A Steel Wheeled Vibratory Roller. Install Speed Bumps 4 Each This Proposal Is Based On Performing The Work In 1 Phase/Mobilization.	\$218,118.30
<u>Crack Seal / Apply PMM</u>	
Provide Barricades During Our Scope Of Work. Power Clean With High Volume Air As Needed And Seal All Cracks 1/4 In And Larger With Crafcro PolyFlex III Crack Sealant. (Alligatored Areas Not Included.) Power Sweep/clean Asphalt Surface. Furnish And Apply Two (2) Coats Of PMM Sealer By Spray Application On Approximately 57,500 Square Feet. SealMaster PMM Has 3-5 Lbs. Of Aggregate Per Gallon Blended With 2 Percent Polymer Modified Latex. (Adhesion Or Bonding Of Seal Coat Materials Is Not Warranted In Areas Exposed To Automotive Fluids And/or Other Spills.) This Proposal Is Based On Performing The Work In 1 Phase/Mobilization.	\$15,729.25
<u>Pavement Markings</u>	
Stripe To Existing Pattern: Stripe Speed Bumps 4 Each Stripe Arrow 13 Each Curb Painting 1,275 Linear Feet Stripe Crosswalk Hash/stop Bars/solid Lane Divider 862 Linear Feet This Proposal Is Based On Performing The Work In 1 Phase/Mobilization.	\$3,083.75

Subtotal for above Adjacent Ways Items:	\$236,931.30
COUNTY OF MARICOPA AND CITY OF CAVE CREEK TAX 7.345%:	\$17,402.60
Total Price for above Adjacent Ways Items:	\$254,333.90