

Current Status: Resubmitted

11/1/2024 9:47:52 AM

Submission ID: 2861

Initial Submission Date: 6/3/2024

Resubmission Date: 11/1/2024

District Name: Cave Creek Unified District

Contact Person: Mike Santina

Contact Phone: 4805752055

Contact Email: msantina@ccusd93.net

School: District Project

Site Address: 33016 N 60th St  
Scottsdale AZ

Project Title: DO Sealcoat- Adjacent Ways

Project Detail: Adjacent Ways

Remove And Replace 3" Asphalt  
Provide Traffic Control And Barricades During Our Scope Of Work.  
Make Necessary Saw Cuts.  
Remove Approx. 18,765 Square Feet Of Failed Asphalt To A Depth Of 3 Inches.  
Compact Existing Base And Pave With 3 Inches Of 1/2 Inch MAG Asphaltic Surface Course.  
Raise 5 Manholes Flush With New Asphalt Elevation Including Concrete Collar.  
This Proposal Is Based On Performing The Work In 1 Phase/Mobilization At The Same Time As The Standard Funding Scope Of Work.

Crack Seal / Apply PMM Sealer

Provide Traffic Control And Barricades During Our Scope Of Work.  
Power Clean With High Volume Air As Needed And Seal All Cracks 1/4 In And Larger With Crafco PolyFlex III Crack Sealant. (Alligatored Areas Not Included.)  
Power Sweep/clean Asphalt Surface.  
Furnish And Apply Two (2) Coats Of PMM Sealer By Spray Application On Approximately 56,200 Square Feet. SealMaster PMM Has 3-5 Lbs. Of Aggregate Per Gallon Blended With 2 Percent Polymer Modified Latex. (Adhesion Or Bonding Of Seal Coat Materials Is Not Warranted In Areas Exposed To Automotive Fluids And/or Other Spills.)  
This Proposal Is Based On Performing The Work In 1 Phase/Mobilization At The Same Time As The Standard Funding Scope Of Work.

Pavement Markings

Stripe To Existing Pattern:  
Stripe 500 LF Of 4" Double Yellow Lines Using Yellow Latex Traffic Paint.  
Stripe 175 LF Of 4" Single White Lines Using White Latex Traffic Paint.  
Paint 5 Arrows On Pavement Using White Latex Traffic Paint.  
Stencil 40 "FIRE LANE NO PARKING" Using 4 Inch Characters On The Asphalt Using White Paint.  
Paint Approx. 2,605 Ln. Ft. Of Curb Top & Face With Red Paint.  
This Proposal Is Based On Performing The Work In 1 Phase/Mobilization At The Same

Time As The Standard Funding Scope Of Work.

Cement Stabilization

Blend To A Depth Of 12 Inches.

Add Moisture And Compact To Grade.

Add 3 Percent Cement To Approx. 18,765 Square Feet.

This Proposal Is Based On Performing The Work In 1 Phase/Mobilization.

No Standard Funding Project will be done.

**Project Date Range:** 7/1/2024 **TO** 9/1/2024

**Total Project Cost:** \$143,716.56 **Adjacent Ways Cost:** \$143,716.56

**Board Meeting Date:**

**Validation Status:** Review Pending

**Staff Analysis:** After reviewing the required documents with the district, the SFD liaison determined that this request appropriately uses Adjacent Ways funds.

8/19/2024: The Schedule of Values is incomplete. The entire project cost must be included in the SOV and broke out by line item in the District Cost and Adjacent Ways columns. Please breakout the cost of the signage/stripping, and tax in both the District Cost and On-site Adjacent Ways Cost columns. Upload the revised SOV and adjust the Estimated Cost, Total Amount on this application to the Total Project Cost, then resubmit for review. Thank you. KC

**Board Decision:**