

Current Status: Processing Complete

6/3/2024 9:39:47 AM

Submission ID: 2862

Initial Submission Date:

Resubmission Date:

District Name: Cave Creek Unified District

Contact Person: Mike Santina

Contact Phone: 480-575-2055

Contact Email: msantina@ccusd93.net

School: Transportation and Warehouse Facility

Site Address: 33424 N 60th St  
Scottsdale, AZ

Project Title: Transportation Sealcoat

Project Detail: Adjacent Ways  
Crack Seal / Apply PMM/ Pavement Markings

Provide Traffic Control And Barricades During Our Scope Of Work.  
Power Clean With High Volume Air As Needed And Seal All Cracks 1/4 In And Larger With CrafcO PolyFlex III Crack Sealant. (Alligatored Areas Not Included.)  
Power Sweep/clean Asphalt Surface.  
Furnish And Apply Two (2) Coats Of PMM Sealer By Spray Application On Approximately 61,625 Square Feet. SealMaster PMM Has 3-5 Lbs. Of Aggregate Per Gallon Blended With 2 Percent Polymer Modified Latex. (Adhesion Or Bonding Of Seal Coat Materials Is Not Warranted In Areas Exposed To Automotive Fluids And/or Other Spills.)  
Stripe To Existing Pattern:  
Stripe Arrows 9 Each  
This Proposal Is Based On Performing The Work In 2 Phases/Mobilizations.

Project Date Range: 7/1/2024 TO 9/1/2024

Total Project Cost: \$15,990.92

Adjacent Ways Cost: \$15,990.92

Board Meeting Date:

Validation Status: No Review Required

Staff Analysis:

Board Decision: