



1640 S Stapley Dr #209
• Mesa, AZ 85204

Project # 2025-0829

Date: 6/9/2025 10:13:27 AM

Submitted To:

Cody Chischilly
Page Unified School District
817 Aqua St
Page, AZ 86040

Contact Information:

Phone: (928) 608-4182
Mobile: (928) 660-8306
E-mail: cchischilly@pageud.org
Fax:

Site Description: # S126890

Desert View Intermediate School
462 S Lake Powell Blvd
Page, AZ 86040

Site Contact:

Site Phone:

Site Email:

Prepared By:

Chris Bunker

Contact Information:

Mobile: 480-745-9712
Office: 763-424-9191
E-mail: cbunker@roadrunnerpaving.com

Project Manager:

Joe Ortiz
Mobile: 928-916-8061

Change Order # 1

Qty	Additional Work Description	Depth	
6,314 Sq. Ft.	<ul style="list-style-type: none">•Provide necessary hydrant water meter for construction use.•Mill and haul off existing asphalt to a depth of 3 inches.•Mill and haul off existing grass/native soil to an average depth of 10 inches. (Leave Millings on site)•Remove & haul 50 LF of plastic curb & 90 LF of extruded curb.•Fine grade and compact existing base material as necessary.•Install 4 inches of aggregate base course (ABC) and compact with a steel drum vibratory roller in the grass/native soil area only.•Tack all edges of existing curb and/or asphalt as necessary.•Place and compact new 1/2" mix asphalt to a finished depth of 3 inches using a self-propelled paving machine and vibratory steel drum rollers.•Work will be completed in conjunction with base bid.•Price does not include striping/red curb fire lane striping unless otherwise noted.•Fencing & playground structure to be removed by school district.	3	\$81,420.60

Above additional work to be performed under same conditions as specified in original contract unless otherwise stipulated

Pavement Consultant Chris Bunker

Accepted Authorized Signature