

Current Status: Submitted 7/1/2024 9:00:32 PM **Submission ID:** 2884

Initial Submission Date: 7/1/2024

Resubmission Date:

District Name: Cartwright Elementary District

Contact Person: James Serbin

Contact Phone: 6025457777

Contact Email: sfbprojects@csd83.org

School: District Complex

Site Address: Cartwright School District

Project Title: Cartwright School District Office - Roadway removal & replacement of driveway surface

Project Detail: Driveway off of 51st Avenue into District Office driveway is in need of replacement. Driveway serves as one of three entrances into the District Office Complex. Drives also serves as a fire lane into the complex.
Remove And Replace Asphalt Repairs \$48,095.45
Provide Traffic Control And Barricades During Our Scope Of Work.
Make Necessary Saw Cuts.
Remove Approx. 7,150 Square Feet Of Failed Asphalt To A Depth Of 4 Inches.
Fine Grade And Compact Approx. 7,150 Square Feet Of Existing Base.
Pave Approx. 7,150 Square Feet With 4 Inches Of 1/2 Inch MAG Asphaltic Surface Course.
Includes Contingency for Cement Stabilization
Add 4 Percent Cement To Approx. 7,150 Square Feet. Blend To A Depth Of 8 Inches.
Add Moisture And Compact To Grade.

Project Date Range: 7/10/2024 **TO** 8/15/2024

Total Project Cost: \$63,978.58 **Adjacent Ways Cost:** \$63,978.58

Board Meeting Date:

Validation Status: Review Pending

Staff Analysis:

Board Decision: