

PROJECT:

TRANSPORTATION FACILITY - PHASE 1
LIBERTY ESD #25
BUCKEYE, AZ

PREPARED FOR:

LIBERTY ELEMENTARY SCHOOL DISTRICT #25
BUCKEYE, AZ

GMP #2 - 100% CD
May 6, 2024

PREPARED BY: **FCI Constructors, Inc.**

FCI Constructors, Inc.

TRANSPORTATION FACILITY - PHASE 1

LIBERTY ESD #25

GMP #2 - 100% CD

OVERALL COST MODEL

May 6, 2024

	FUELING ISLAND		SITWORK		ADJACENT WAYS	GRAND TOTAL	
DESCRIPTION		5,250	8.30 ACRES				
	TOTAL COST	COST/SF	TOTAL COST	TOTAL COST		TOTAL COST	NOTES
020000 SELECTIVE DEMOLITION	\$ -	\$ -	\$ 90,000	\$ -	\$ -	\$ 90,000	REMOVE EXISTING FUELING SYSTEM
030000 CONCRETE	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	N/A-EXCLUDED
040000 MASONRY	\$ -	\$ -	\$ 33,103	\$ -	\$ -	\$ 33,103	TRASH ENCLOSURE
050000 METALS	\$ 25,421	\$ 4.84	\$ -	\$ -	\$ -	\$ 25,421	BOLLARDS
060000 WOOD & PLASTICS	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	N/A-EXCLUDED
070000 THERMAL & MOISTURE PROTECTION	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	N/A-EXCLUDED
080000 DOORS & WINDOWS	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	N/A-EXCLUDED
090000 FINISHES	\$ 4,750	\$ 0.90	\$ -	\$ -	\$ -	\$ 4,750	PAINT BOLLARDS
100000 SPECIALTIES	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	N/A-EXCLUDED
110000 EQUIPMENT	\$ 359,484	\$ 68.47	\$ -	\$ -	\$ -	\$ 359,484	FUELING EQUIPMENT
120000 FURNISHINGS	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	N/A-EXCLUDED
130000 SPECIAL CONSTRUCTION	\$ 175,151	\$ 33.36	\$ -	\$ -	\$ -	\$ 175,151	FUEL SHADE CANOPY
140000 CONVEYING SYSTEMS	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	N/A-EXCLUDED
210000 FIRE SUPPRESSION	\$ 24,192	\$ 4.61	\$ -	\$ -	\$ -	\$ 24,192	FIRE SUPPRESSION
220000 PLUMBING	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	N/A-EXCLUDED
230000 HVAC	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	N/A-EXCLUDED
260000 ELECTRICAL	\$ 15,000	\$ 2.86	\$ 533,602	\$ -	\$ -	\$ 548,602	POWER TO FUEL/SITE LIGHTING
27/280000 LOW VOLTAGE/SPECIAL SYSTEMS	\$ 3,000	\$ 0.57	\$ 18,000	\$ -	\$ -	\$ 21,000	CAT6 FOR CAMERA'S AND CARD READERS
310000 EARTHWORK - SITE	\$ -	\$ -	\$ 474,282	\$ 19,700	\$ -	\$ 493,982	EARTHWORK/SWPPP
320000 SITE IMPROVEMENTS	\$ -	\$ -	\$ 1,780,369	\$ 31,448	\$ -	\$ 1,811,817	ASPHALT/CURBS/PAVING/LANDSCAPE
330000 UTILITIES	\$ -	\$ -	\$ 917,222	\$ 124,000	\$ -	\$ 1,041,222	UTILITIES
SUBTOTAL - DIRECT COST	\$ 606,998	\$ 115.62	\$ 3,846,578	\$ 175,148	\$ -	\$ 4,628,725	
CONTINGENCY- ESTIMATING/DESIGN	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	0.00%
CONTINGENCY- ESCALATION - .5%/MONTH FOR 2 MONTHS	\$ 6,070	\$ 1.16	\$ 38,466	\$ 1,751	\$ -	\$ 46,287	1.00%
CONTINGENCY- CONSTRUCTION	\$ 21,640	\$ 4.12	\$ 137,131	\$ 6,244	\$ -	\$ 165,015	3.57%
GENERAL CONDITIONS	\$ 7,960	\$ 1.52	\$ 634,988	\$ 39,465	\$ -	\$ 682,413	8.5 MONTH DURATION
BUILDERS RISK INSURANCE	\$ 472	\$ 0.09	\$ 3,417	\$ 163	\$ -	\$ 4,052	0.065%
GENERAL LIABILITY INSURANCE	\$ 7,265	\$ 1.38	\$ 52,568	\$ 2,511	\$ -	\$ 62,344	1.00%
SUBCONTRACTOR DEFAULT INSURANCE	\$ 7,663	\$ 1.46	\$ 48,563	\$ 2,211	\$ -	\$ 58,438	1.25%
SOILS INVESTIGATION / GEOTECHNICAL ENGINEERING	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	BY OWNER
MATERIALS TESTING / INSPECTION	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	BY OWNER
BUILDING PERMIT / PLAN REVIEW FEES	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	BY OWNER
ARCHITECTURAL DESIGN & ENGINEERING (C/S/M&E)	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	BY OWNER
FCI PAYMENT/PERFORMANCE BONDS	\$ 5,248	\$ 1.00	\$ 37,971	\$ 1,814	\$ -	\$ 45,033	0.72%
FCI PRECONSTRUCTION PHASE FEE	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	INCL. w/ SEPARATE AGREEMENT
FCI CONSTRUCTION PHASE FEE	\$ 34,595	\$ 6.59	\$ 250,324	\$ 11,959	\$ -	\$ 296,878	5.00%
AZ SALES TAX - PRIME	\$ 28,579	\$ 5.44	\$ 206,798	\$ 9,880	\$ -	\$ 245,257	4.095% (65% of 6.3%) MARICOPA
ESTIMATED CONSTRUCTION COST - MAY 2024	\$ 726,490	\$ 138.38	\$ 5,256,805	\$ 251,148	\$ -	\$ 6,234,443	
OWNER CONSTRUCTION CONTINGENCY						\$ 124,689	2.00%
GRAND TOTAL CONSTRUCTION COSTS						\$ 6,359,132	

TOTAL PROJECT CONSTRUCTION COST WITH BWCDD (CANAL) LATERAL 21S RELOCATION \$ 540,868 BWCDD Canal Pipeline Relo (LES# 25)
 \$ 6,900,000
 + Design/Permits