

**Current Status:** Resubmitted 12/12/2024 3:30:22 PM **Submission ID:** 3911

**Initial Submission Date:** 10/29/2024

**Resubmission Date:** 12/12/2024

**District Name:** Glendale Elementary District

**Contact Person:** JoAnna Svoboda

**Contact Phone:** 623-237-6201

**Contact Email:** jsvoboda@gesd40.org

**School:** Horizon School

**Site Address:** 8520 N. 47th Avenue  
Glendale, AZ. 85302

**Project Title:** Parking Lot/Bus Bay Lanes/Fire Lanes

**Project Detail:** Concrete Flatwork/Patch Back  
Make Necessary Saw Cuts  
Demo and Haul off 156 LF of existing concrete extruded curb  
Demo and Hall off 2280 SF of existing asphalt at 3" thickness  
Excavate and Haull off 2280 SF of existing dirt at 5" thickness  
Form and pour 156 LF of curb and gutter  
Patch approx 312 SF with 3" of 1/2" MAG asphaltic surface course  
  
Remove and Replace Asphalt Repairs  
Make Necessary Saw Cuts  
Remove Appx 1850 SF of failed asphalt to a depth of 3"  
Compact existing base and pave with 3" of 1/2" MAG asphaltic surface course  
  
Crack Seal/Apply Sealer/Pavement Markings  
Power clean with high volume air as needed and seal all cracks 1/4" and larger with  
Crafco Parking lot Sealant Crack Sealant.  
Power Sweep/Clean Asphalt Surface  
Furnish and Apply 2 coats of Master Seal Sealer by Spray application on approx  
25455 SF  
Stripe to existing pattern  
Stripe 1329 LF of cross hash marking using yellow latex paint  
Paint 10 Arrows on pavement with White latex paint  
Paint Approx 40 LF of curb top and face with yellow paint  
Paint 905LF of curb top and face with yellow paint  
Remove 13 flexible delineators and install 9 new delineators.  
  
All of this work is being done at the bus barn/depot where all of our buses are parked  
and stored daily.

**Project Date Range:** 3/17/2025 **TO** 3/21/2025

**Total Project Cost:** \$76,923.17 **Adjacent Ways Cost:** \$72,644.97

**Board Meeting Date:**

**Validation Status:** Review Pending

**Staff Analysis:** 11/1/24  
Thank you for your submission. While reviewing your application, we need some

clarification on the project title. Please update the project tile to replace the work that needs to be done. Additionally, this submission is missing the required documentation that needs to be reviewed to support this request.

Please upload the missing documents as follows:  
The SOV ( Schedule of Values) for on and offsite work  
Google Site Map

Thanks, Tashma

**Board Decision:**