

GESD – Desert Spirit – South Sidewalk

7355 W Orangewood Ave, Glendale, AZ 85303

3 - Concrete

- Furnish & install 5' wide, 4" thick concrete sidewalk on compacted fill per MAG Standard Detail 230 (± 24 CY). See attached sketch for quantity takeoff. Field measure prior to ordering. See [photos](#) for more information.
 - o Expansion joint along entire sidewalk-to-wall joint.
 - o Expansion joints to be caulked & dusted with silica sand.

31 – Earthwork

- Furnish & install 11' wide, 18" deep clean fill dirt (± 348 T) and compact. 4:1 max slope to existing retention. See attached sketch for quantity takeoff. Field measure prior to ordering. See [photos](#) for more information.

32 – Landscaping

- By Owner: Cut down & cap (20) existing irrigation heads.

Desert Spirit - South Sidewalk

Quantity Takeoff

	Description	Quantity	Unit
■	Clean Fill Dirt	4,163	sf
/	E.J. - Caulk & Sand	420.15	ft
■	Sidewalk	1,871	sf

Desert Spirit School

Desert Spirit School, 7355 W Orangewood Ave, Glendale, AZ 85303

GQVM+M3 Glendale, Arizona

portals.gesd40.org

(623) 237-4016

District
 Glendale Elementary District

Highest grade
 Eighth Grade

Save to project

40 m Camera: 666 m 33°32'32"N 112°13'00"W 340 m

131'-3"