

Current Status: Resubmitted 11/22/2024 11:07:43 AM **Submission ID:** 3918

Initial Submission Date: 11/5/2024

Resubmission Date: 11/22/2024

District Name: Paradise Valley Unified District

Contact Person: Tim Waymire

Contact Phone: 602-721-1802

Contact Email: twaymire@pvschools.net

School: Shea Middle School

Site Address: 2728 E. Shea Boulevard
Phoenix, AZ 85028

Project Title: Shea, Asphalt Paving

Project Detail: Asphalt Remove & Replace:

- Remove approximately 32,089 sq ft of asphalt to a depth of 4".
- Compact existing base and pave with 4" of 1/2" MAG Asphaltic Surface Course.
- Raise 3 water valves, 2 man holes flush with new asphalt elevation including concrete collar.
- Install 2 speed bumps (3' wide x 3" height to 0" on edge.)

Cement Stabilization:

- Add 3% lime/cement to approximately 32,089 sq ft, blend to a depth of 12"
- Add moisture and compact to grade.

Crack Seal / Apply Sealer / Pavement Markings:

- Power clean with high volume air as needed and seal all cracks 1/4" and larger.
- Power sweep & clean asphalt surface.
- Apply 2 coats of PMM sealer by spray application on approximately 24,870 sq ft.
- Stripe to existing pattern:
 - Stripe 2,328 LF of 4" lines using yellow latex traffic paint.
 - Paint 9 arrows on pavement using white latex traffic paint.
 - Stencil 18 "FIRE LANE NO PARKING" using 4" characters on the curb using white paint.
 - Paint 2 speed bumps solid using yellow latex traffic paint.
 - Paint approximately 2,417 LF of curb top and face with red paint.

Project Date Range: 5/1/2025 **TO** 8/1/2025

Total Project Cost: \$350,236.02 **Adjacent Ways Cost:** \$289,201.27

Board Meeting Date:

Validation Status: Review Pending

Staff Analysis: 11/19/2024 - Please revise the Schedule of Values to include the District portion.

Board Decision: