

Current Status: Resubmitted

11/22/2024 11:23:59 AM

Submission ID: 3929

Initial Submission Date: 11/7/2024

Resubmission Date: 11/22/2024

District Name: Paradise Valley Unified District

Contact Person: Tim Waymire

Contact Phone: 602-721-1802

Contact Email: twaymire@pvschools.net

School: Mountain Trail Middle School

Site Address: 2323 E Mountain Gate Pass
Phoenix, AZ 85024

Project Title: Bus & Fire Lane Asphalt Paving

Project Detail: Asphalt Remove & Replace

- Mill approximately 29,308 sq ft of existing asphalt to a depth of 4".
- Fine grade approx. 29,308 sq ft with 1/2" MAG asphalt surface course to average depth of 4" after compaction with steel wheeled vibratory roller.
- Raise 6 water valves flush with new asphalt elevation including concrete collar.
- Stripe to existing pattern:
 - Stripe 454 LF of cross hash marking using yellow latex traffic paint.
 - Stripe 831 LF of 4" lines using yellow latex traffic paint.
 - Paint 21 arrows on pavement using white latex traffic paint.
 - Stencil "THRU LANE NO STOP" using 12" characters on the asphalt using white paint.
 - Paint approx. 1,202 LF of curb top & face with red paint.
 - Stencil "FIRE LANE NO PARKING" using 4" characters on the curb using white paint.

Cement Stabilization

- Add 3% cement to approx. 29,308 sq. ft. Blend to a depth of 12".
- Add moisture and compact to grade.

Project Date Range: 5/1/2025 TO 8/1/2025

Total Project Cost: \$352,947.30

Adjacent Ways Cost: \$240,280.73

Board Meeting Date:

Validation Status: Review Pending

Staff Analysis: 11/19/2024 - Please revise the Schedule of Values to include the District portion.

Board Decision: