



# ROADRUNNER PAVING & ASPHALT MAINTENANCE

1959 S Power Rd  
Suite 103-419  
Mesa, AZ 85206

Date: Monday, December 9, 2024

Proposal # 2024-2076

**Submitted To:**

Mike Kramer  
Mesa Public Schools.  
535 South Lewis  
Mesa, AZ 85210

**Contact Information:**

Phone: (602) 347-2835  
Mobile:  
E-mail: mjkrumer@mpsaz.org

**Site Description:** # S126270

Mesa Academy  
6919 E Brown Rd  
Mesa, AZ 85207

Site Contact:  
Site Phone:  
Site Email:

**Sales Rep:**

Chris Bunker

**Contact Information:**

Mobile: 480-745-9712  
Office: (480) 892-7101  
cbunker@roadrunnerpavingaz.com

**Estimator:**

Joe Ortiz  
Mobile: 928-916-8061  
joe@roadrunnerpavingaz.com

Proposed Service(s) & Description(s)

Qty

Depth

## **ADJACENT WAYS (Fire Lane):**

### **Asphalt Removal & Replacement (Large Crack)**

- Make necessary sawcuts to existing asphalt.
- Remove deteriorated asphalt. Grade and compact existing base material as necessary.
- Tack all edges of existing curb and/or asphalt as necessary.
- Place and compact new 1/2" mix asphalt.
- All repairs will be shaped symmetrically where possible.
- Work to be completed in 1 trip(s).

1,770 Sq. Ft.

3"

### **Asphalt Mill & Pave (Red)**

- Provide necessary hydrant water meter for construction use.
- Mill and haul off existing asphalt to a depth of 3 inches.
- Fine grade and compact existing base material as necessary.
- Tack all edges of existing curb and/or asphalt as necessary.
- Place and compact new 1/2" mix asphalt to a finished depth of 3 inches using a self-propelled paving machine and vibratory steel drum rollers.
- Work will be completed in 1 trip(s).
- Re-stripe to match existing layout.
- Price includes red/yellow curb striping.

44,559 Sq. Ft.

3"

### **Subtotal for the Above Adjacent Ways Items**

\$146,928.11

### **County of Maricopa and City of Mesa Taxes**

\$6,579.01

### **2% Bond Rate**

\$3,070.14

### **Total Price for the Above Adjacent Ways Items**

\$156,577.26



## **ROADRUNNER PAVING & ASPHALT MAINTENANCE**

### **STANDARD FUNDING (Parking Lot):**

#### **Asphalt Mill & Pave**

13,120 Sq. Ft.

3"

- Provide necessary hydrant water meter for construction use.
- Mill and haul off existing asphalt to a depth of 3 inches.
- Fine grade and compact existing base material as necessary.
- Tack all edges of existing curb and/or asphalt as necessary.
- Place and compact new 1/2" mix asphalt to a finished depth of 3 inches using a self-propelled paving machine and vibratory steel drum rollers.
- Work will be completed in 1 trip(s).
- Re-stripe to match existing layout.

#### **Subtotal for the Above Standard Funding Items**

\$38,399.01

#### **County of Maricopa and City of Mesa Taxes**

\$1,865.34

#### **2% Bond Rate**

\$805.29

#### **Total Price for the Above Standard Funding Items**

\$41,069.64

### **Total Project Price**

\$197,646.90



# ROADRUNNER PAVING & ASPHALT MAINTENANCE

## **Mohave Unit Pricing**

*1 Paving Barricade Mob - \$500.00*  
*1 Paving Barricade De-Mob - \$500.00*  
*1 Asphalt Sawcutting Mob - \$350.00*  
*1,770 LF of 3" AC sawcutting - \$1,327.50*  
*1 Remove/Replace Mob - \$1,000.00*  
*1,770 SF Remove/Replace - \$5,310.00*  
*2 Milling Mobs - \$2,000.00*  
*57,679 SF of 3" Milling - \$25,955.55*  
*2 Haul Off Mobs - \$2,000.00*  
*17 CY of haul off - \$850.00*  
*2 Sweeping Mobs - \$1,000.00*  
*16 hours Sweeping - \$2,480.00*  
*2 Fine Grade Mobs - \$2,400.00*  
*6,409 SY Fine Grading - \$16,022.50*  
*2 Paving Mobs - \$2,000.00*  
*57,679 SF of 3" Paving - \$83,634.55*  
*2 Striping Mobs - \$480.00*  
*9 Arrows - \$540.00*  
*14,119 LF 4" line - \$3,247.37*  
*1,142 Yellow Curb Striping - \$856.50*  
*970 Red Curb Striping - \$727.50*  
*Additional Labor - \$40,590.00*

---

**This proposal may be withdrawn at our option if not accepted within 30 days of Dec 9, 2024**

**Pavement Consultant: Chris Bunker**

**Client's Authorized Signature**

## TERMS & CONDITIONS

---

1. Payment is balance due upon completion; any amount over 30 days will be assessed late charges of 2% monthly.
2. Warranty: Two year on materials, labor, and workmanship. Roadrunner Paving & Asphalt Maintenance will repair any areas at our expense that are deemed warranty covered. Normal wear and tear, severe weather, abuse, or acts of God will not be considered under warranty coverage. Reflective cracking on overlays will not be covered.
3. All towing of vehicles to be coordinated by owner. A towing charges of \$60 per vehicle will occur if vehicles are in work area on date selected for work to be performed. All towing to be approved by owner prior to commencement of work.
4. Unless otherwise noted in proposal, notification of work dates to residents are not included in this proposal.
5. Crack fill will not be placed in extremely cracked, "alligatored" areas
6. Unless otherwise noted in proposal, traffic control will only be maintained while Roadrunner employees are on site. Once the employees have left the job, it becomes the responsibility of the customer to maintain traffic control. Portions of the project will be unusable while work is performed and to let material have time to setup / cure.
7. Roadrunner Paving & Asphalt Maintenance maintains adequate insurance and workers compensation policies.
8. Unless otherwise noted in proposal, this proposal does not include engineering, testing, permits or any other associated fees.
9. Roadrunner Paving & Asphalt Maintenance is not responsible for any damage due to unmarked and or shallow utilities. Utility adjustments are not included unless specifically stated on this proposal.
10. There are no guarantees on drainage unless otherwise specifically outlined above.
11. On projects where we are milling or pulverizing the existing pavement, areas that have saturated subgrade or grade issues must be addressed. This may or may not impact the amount listed on this proposal.
12. Fire lane curb that is striped over existing red fire lane curb and flakes due to previous paint flaking will not be covered by warranty. Roadrunner Paving & Asphalt Maintenance can clean the existing curb at an additional cost.
13. Roadrunner Paving & Asphalt Maintenance is not responsible for any utility adjustment fees required by municipality
14. On sealcoat projects, oil spots will be cleaned as thoroughly as possible and a primer will be applied to the heaviest areas. However, some delamination of sealer may take place in these areas.
15. If a project date has been agreed on between Roadrunner and customer, and needs to be rescheduled within 48 hours of scheduled date for any reason, a cancellation fee of \$750 will be incurred.
16. If any work performed by Roadrunner during the project schedule dates is damaged by residents, delivery vehicles or any other form of traffic, a charge to repair damaged area will be incurred.
17. Market oil prices may or may not result in material price changes that are out of Roadrunner's control.



