

<b>Current Status:</b>	Resubmitted	1/14/2025 1:36:33 PM	<b>Submission ID:</b>	3941
<b>Initial Submission Date:</b>	12/19/2024			
<b>Resubmission Date:</b>	1/14/2025			
<b>District Name:</b>	Paradise Valley Unified District			
<b>Contact Person:</b>	Erin Arakaki			
<b>Contact Phone:</b>	6024492249			
<b>Contact Email:</b>	earakaki@pvschools.net			
<b>School:</b>	Liberty Elementary School			
<b>Site Address:</b>	5125 E Marilyn Rd Scottsdale, AZ 85254			
<b>Project Title:</b>	Asphalt removal and replacement			
<b>Project Detail:</b>	<div>-Remove And Replace 3" Asphalt -Remove Approx. 10,270 Square Feet Of Failed Asphalt To A Depth Of 3 Inches. -Compact Existing Base And Pave With 3 Inches Of 1/2 Inch MAG Asphaltic Surface Course. -Raise 2 Water Valves Flush With New Asphalt Elevation Including Concrete Collar. Pavement Markings -Stripe To Existing Pattern -Stripe 609 LF Of Cross Hash Markings Using Yellow Latex Traffic Paint. -Paint 6 Arrows On Pavement Using White Latex Traffic Paint. -Stencil 5 "FIRE LANE NO PARKING" Using 4 Inch Characters On The Asphalt Using White Paint. -Paint Approx. 105 Ln. Ft. Of Curb Top &amp; Face With Red Paint.</div>			
<b>Project Date Range:</b>	5/1/2025	<b>TO</b>	8/1/2025	
<b>Total Project Cost:</b>	\$126,174.63	<b>Adjacent Ways Cost:</b>	\$89,139.49	
<b>Board Meeting Date:</b>				
<b>Validation Status:</b>	Review Pending			
<b>Staff Analysis:</b>	<div>12/23/2024 - Please have contractor revise the color overlay since the parking spots under the solar panels is not part of the fire lane (that would be district cost), which would also require the reworking of the proposal. In addition, the SFD Schedule of Values should also include the District cost portions of the Adjacent Ways project, not just the Adjacent Ways costs. Please revise both items and resubmit.</div>			
<b>Board Decision:</b>				