

**Current Status:** Submitted      2/4/2025 1:08:56 PM      **Submission ID:** 3955

**Initial Submission Date:** 2/4/2025

**Resubmission Date:**

**District Name:** Paradise Valley Unified District

**Contact Person:** Tim Waymire

**Contact Phone:** 602-721-1802

**Contact Email:** twaymire@pvschools.net

**School:** Pinnacle High School

**Site Address:** 3535 E Mayo Blvd  
Phoenix, AZ, 85050

**Project Title:** Bus & Fire Lane Asphalt Paving

**Project Detail:** Mill/Grade/Pave:

- Mill approx. 22,722 sq ft of existing asphalt to 3" depth
- Fine grade approx. 9,969 sq ft with half inch MAG asphalt surface course to average finished depth of 4" after compaction with steel wheeled vibratory roller.
- Raise 1 water valve, 2 man holes flush with new asphalt elevation including concrete collar.
- Stripe to existing pattern:
  - stripe 308 LF of cross hash markings using yellow latex traffic paint
  - stripe 155 LF of 4"
  - stripe 294 LF of 12" lines using yellow latex traffic paint
  - paint 20 arrows on pavement using white latex traffic paint
  - stencil 51 "FIRE LANE NO PARKING" using 4" characters on asphalt using white paint
  - paint approx. 4,642 LF of curb top & face with red paint

Crack Seal/Apply Sealer:

- Power clean with high volume air as needed and seal all cracks 1/4" and larger with Crafcro Parking Lot Sealant crack sealant.
- Power sweep/clean asphalt surface.
- Furnisha & apply two coats of PMM Sealer by spray application on approx. 53,206 sq. ft. SealMaster PMM has 3-5 lbs. of aggregate per gallon blended with 2% polymer modified latex.

Cement Stabilization:

- Add 3% cement to apporx. 32,691 sq ft, blend to a depth of 12".
- Add moisture and compact to grade.

**Project Date Range:** 5/1/2025      **TO**      8/1/2025

**Total Project Cost:** \$1,371,000.82      **Adjacent Ways Cost:** \$239,262.66

**Board Meeting Date:**

**Validation Status:** Review Pending

**Staff Analysis:**

**Board Decision:**