

Current Status: Processing Complete 4/9/2025 10:28:01 AM **Submission ID:** 4026

Initial Submission Date:

Resubmission Date:

District Name: Yuma Elementary District

Contact Person: David Tamayo

Contact Phone: 619 756 2833

Contact Email: dtamayo@yuma.org

School: James B Rolle School

Site Address: 2711 Engler Ave. Yuma, AZ 85365

Project Title: James B Rolle

Project Detail: BASE BID: Remove And Replace Asphalt
Provide Traffic Control And Barricades During Our Scope Of Work.
Make Necessary Saw Cuts.
Remove Approx. 37,327 Square Feet Of Failed Asphalt To A Depth Of 4.5 Inches.
Compact Existing Base And Pave With 3 Inches Of MAG 1/2 LV Hot Mix.
Layout And Stripe Pavement Markings To Existing Pattern.
This Proposal Is Based On Performing The Work In 1 Mobilization Over 2 Days.
The Depth Of The Existing Asphalt Is Only An Estimate. Additional Depth Will Require Additional Charges. The Removal Of The Asphalt Has Been Bid For That Function Alone And Does Not Include Excavation Of The Base Or Sub-base. If At The Time Of Removal, It Is Determined That Water Has Weakened Either The Base Or Sub-base, Additional Charges Would Be Required To Correct The Unforeseen Problem. There Will Be An Extra Charge Based On Time And Material For The Removal And Replacement Of Dirt Or If Upon The Removal Of The Asphalt, It Is Found That Structures Exist Below The Surface, Such As Concrete Footings, Abandoned Pipes, Etc. An Additional Charge Would Be Required To Remove These Obstructions If They Would Impede Or Prohibit Grade Consistencies. Sunland Asphalt Will Not Be Held Liable For Any Underground Cables Or Underground Utilities. Sunland Asphalt Will Not Be Held Liable For Any Underground Cables, Electrical Lines, Water Lines Or Any Other Underground Obstruction, Not Buried At Least 18 Inches Below Existing Finished Grade.
BASE BID: Pavement Markings
Layout And Stripe Lot To The Existing Pattern.
Adhesion Or Bonding Of Striping Materials Is Not Warranted In Areas Exposed To Automotive Fluids And/or Other Spills.
This Proposal Is Based On Performing The Work In 1 Mobilization Over 1 Day.
OPTION: Remove And Replace Asphalt
Remove Approx. 3,537 Square Feet Of Failed Asphalt To A Depth Of 4.5 Inches.
Demo Center Island, Approx. 148 Square Feet.
Compact Existing Base And Pave With 3 Inches Of PAG 2 LV Hot Mix.
Layout And Stripe New Parking Lines.
This Option Is Based On Performing The Work On The Same Days As The Base Bid Remove And Replace Asphalt.

Project Date Range: 6/2/2025 **TO** 6/27/2025

Total Project Cost: \$155,560.64 **Adjacent Ways Cost:** \$49,878.94

Board Meeting Date:

Validation Status: No Review Required

Staff Analysis:

--

Board Decision:

--