

Current Status: Submitted 11/6/2025 6:42:49 AM **Submission ID:** 4127

Initial Submission Date: 11/6/2025

Resubmission Date:

District Name: Paradise Valley Unified District

Contact Person: Tim Waymire

Contact Phone: 602-721-1802

Contact Email: twaymire@pvschools.net

School: Pinnacle High School

Site Address: 3535 E. Mayo Boulevard
Phoenix, AZ 85050

Project Title: Pinnacle High School asphalt, updated

Project Detail: Mill/Grade/Pave

- Mill approx. 22,722 square feet of existing asphalt to a depth of 3 inches.
- Fine grade approx. 9,969 square feet with half inch MAG asphalt surface course to an average finished depth of 4 inches after compaction with a steel wheeled vibratory roller.
- Raise 1 water valve, 2 man holes flush with new asphalt elevation including concrete collar.
- Stripe to existing pattern:
 - Stripe 308 LF of cross hash markings using yellow latex traffic paint.
 - Stripe 155 LF of 4" lines using yellow latex traffic paint.
 - Stripe 294 LF of 12" lines using yellow latex traffic paint.
 - Paint 20 arrows on pavement using white latex traffic paint.
 - Stencil 47 "FIRE LANE NO PARKING" using 4" characters on the asphalt using white latex traffic paint.
 - Paint approx. 3,856 LF of curb top & face using red paint.

Crack Seal / Apply Sealer

- Power clean with high volume air as needed and seal all cracks 1/4" and larger with Crafcro Parking Lot Sealant crack sealant.
- Power sweep/clean asphalt surface.
- Furnish & apply two coats of PMM sealer by spray application on approx. 40,473 sq. ft.

Cement Stabilization

- Add 3% cement to approx. 32,691 sq. ft. blend to a depth of 12"
- Add moisture and compact to grade

Project Date Range: 12/19/2025 **TO** 6/30/2026

Total Project Cost: \$1,373,374.26 **Adjacent Ways Cost:** \$236,180.86

Board Meeting Date:

Validation Status: Review Pending

Staff Analysis:

Board Decision: