

Current Status: Processing Complete 1/15/2026 4:09:37 PM Submission ID: 4138

Initial Submission Date:

Resubmission Date:

District Name: Mesa Unified District

Contact Person: Aaron Navarro-razo

Contact Phone: 4804726039

Contact Email: anavarrorazo@mpsaz.org

School: Broadway Transportation Center

Site Address: 109 E Broadway Rd, Mesa, AZ 85210

Project Title: Broadway Transportation - Fire Lane Maintenance and Replace

Project Detail: Remove & Replace Asphalt - Adjacent Ways Fund 620: \$23,094.00

- Provide Barricades To Safely Perform Our Scope Of Work.
- Saw-cut And Remove Approximately 2,595 Square Feet Of Failed Asphalt Up To A Depth Of 3 Inches At (1) Location.
- Fine Grade And Compact Existing Base Materials To An Unyielding Condition.
- Replace Excavated Areas To Match Existing Up To 3 Inches Of MAG 1/2-inch Hot Mix Asphalt.
- Machine Roll To Proper Compaction.
- Scope Of Work Shall Be Performed In 1 Continuous Mobilization (Excludes Weekends And Holidays).

Crack Sealing - Adjacent Ways Fund 620: \$1,715.00

- Provide Barricades And/or Cones To Safely Perform Our Scope Of Work.
- Prep And Clean Existing Cracks.
- Crack Seal Existing Cracks 1/4 Inch To 1 Inch With A Hot Rubberized Crack Sealant. (Areas Adjacent To Curbs/sidewalks/gutters And Alligator Cracking Are Excluded).
- Proposal Is Based On Placing 426 Pounds Of Crack Seal Materials. Additional Lbs. (If Needed) Will Be Charged With Authorized Approval From Customer.

PMM Seal Coat - Adjacent Ways Fund 620: \$11,147.62

- Provide Barricades And/or Cones To Safely Perform Our Scope Of Work.
- Prep And Clean Existing Pavement Prior To Sealcoat Application.
- Areas Where Oil Has Leaked On Existing Pavement Will Be Treated With Poly Oil Spot Primer. However, Bonding Of Seal Coat Materials Cannot Be Guaranteed Unless Repairs Are Made Prior To Seal Coat Application.
- Spray Apply Two (2) Coats Of Polymer Modified MasterSeal (PMM) To Approximately 48,322 Square Feet Of Asphalt.
- Scope Of Work Shall Be Performed In 3 Mobilizations Shared With Non Adjacent Ways Sealcoat Work.

Striping - Adjacent Ways Fund 620: \$1,413.00

- Restripe All Pavement Markings Per The Existing Layout, Not Including Curb Paint.
- 4" Stall Lines And Hashing - 450LF
- 6 Foot Arrows - 21

Board Meeting Date:

Validation Status: No Review Required

Staff Analysis:

Board Decision: